

Note:

This drawing may not be copied, reproduced or given to any third party without the prior written consent of ArchitectsNetwork Ltd. All rights reserved.

Please note this drawing is protected under Copyright and remains the property of ArchitectsNetwork Ltd at all times.

All dimensions must be checked on site and not scaled from the drawing.

Proposals are subject to approval by statutory authorities.

Buildings and structures taken from drawings provided.

Submitting drawings for Architects Network Approval of General Arrangement before Fabrication.

ArchitectsNetwork Ltd

architectsnetwork

note:

overall dimensions to be checked on site.

Layout subject to hotel and client's approval.

Layout to be co-ordinated with SE's proposal.



PROPOSED PARTITION BETWEEN BEDROOMS AND BEDROOMS AND CORRIDORS.

Gypswall Quiet Sf partitions (extending full height to underside of concrete floor above):

2 layers of 15mm Soundblock board fixed to 70mm wide metal frame at 600mm centres with gyf/frame resilient bars (to one side). 50mm Isover insulation between the metal frame. Finished in vinyl paper lining or paint

finish. Include deflection head details for the internal metal stud partitions on all floors.

In bathrooms or wet areas use moisture resistant boards to take tiles. All joints to be sealed to prevent sound transmission between rooms. For fixing allow for 15mm WBP plywood. For bathroom use 48mmwide metal studs with 2 layers of 15mm wall board on both side. When tiles use 1 layer of WBP plywood instead of wall board.

Project

Ibis hotel 272-276 Bath Road

Drawing Title **Second floor plan as proposed 1:100**

Drawing No. 14L09 PL 03

Rev

Ref. 14L09AL00