

OVERVIEW

Terracoat Textured Coating is a range of ready-mixed acrylic textured coatings. It provides the unique combination of a quality architectural finish with outstanding economy through ease of application, a low material consumption rate and surface durability. Terracoat is guaranteed for 10 years against peeling and fading. Terracoat adheres to most exterior and interior surfaces including plywood, chipboard, anti-rust primed steel, gypsum dry wall, sand/cement render and concrete. Terracoat has been developed to withstand extreme climatic conditions such as desert climate and extreme cold. Terracoat Excel and Terracoat Granule are the products of choice for finishing the Terraco EIFS system.

PROPERTIES

Terracoat is formulated from crushed and precisely graded fillers, pure acrylic binders and additives which give it elastic properties, long life and durability against colour fading and pollution. Its rich texture and in-built flexibility helps cover defects and minor cracks in the substrate. Terracoat is available in a range of different texture grades and attractive colours. All grades of Terracoat are designed to withstand large temperature swings between day and night.

Excel

Terracoat Excel is a trowel applied texture giving an alpine scratch finish. Terracoat Excel is specifically designed for application in E.I.F.S. systems as well as for use with conventional masonry substrates. Available in 3 grain sizes.

Granule

Terracoat Granule is a trowel applied texture giving a granular finish with various grain sizes. Can also be applied by spray. Terracoat Granule is specifically designed for application in E.I.F.S. systems as well as for use with conventional masonry substrates. Available in 2 grain sizes.

Sahara

Terracoat Sahara is a trowel applied texture giving a filled granular finish with various grain sizes. Can also be applied by spray. Terracoat Sahara is specifically designed for application in E.I.F.S. systems as well as for use with conventional masonry substrates. Available in 2 grain sizes.

AREA OF USE

Terracoat is designed for use as the finish in the Terraco EIFS system. The coating performs equally well on interior surfaces of gypsum dry wall and chipboard and is widely used as a decorative ceiling and wall finish.

PRODUCT GRADES/CODES

Excel 1mm	61466
Excel 2mm	61410
Excel 3mm	61470
Granule 1mm	61420
Granule 2mm	61480
Sahara 1mm	61521
Sahara 2mm	61525

PREPARATION OF SURFACE

New surfaces: Ensure that all dust, dirt and foreign matter are scraped and brushed away. Also ensure the surfaces are free from salts, oil, grease and ridges. Protect all adjacent surfaces not to be covered. All cracks, chips, voids and damages should be repaired with an appropriate filler

Old surfaces: Before applying Terracoat Textured Coating to old surfaces, ensure the substrate is firm. First wash down the surface with a soda / water solution, rinse and allow to dry before repairing or applying the first coat.

PRIMING

Prime surfaces with a coat of Penetrating Primer prior to application of Terracoat.

APPLICATION & CLEANING OF TOOLS

Trowel application is done using a steel trowel to lay on the material and a wetted plastic trowel is used to pattern the surface.

Clean tools and equipment with water after use.

HEALTH & SAFETY

Avoid prolonged contact with eyes and skin. For detailed information refer to relevant material safety data sheet.

PACKAGING & STORAGE

Terracoat is supplied in 25kg plastic pails.

Store containers in a clean dry area protected from direct sunlight and extreme heat and cold. Unopened containers can be stored for 12 months. Use oldest material first.

TECHNICAL DATA

Product	Acrylic based textured coating.
Binder	Pure Acrylic.
Thinning	Water if required.
Drying Time	3 - 4 hours.
Toxicity	Non-toxic.
Flame Spread	Class 0 ASTM E84-81H
Colours	50 standard colours.
Storage	12 months in original unopened containers.

Grade	Specific Gravity	Viscosity ('000 cps.)	Material consumption (Kg / m ²)	Application method	Pack sizes (Kg.)
Excel 1mm	1.70	35-45	1.5-2.0	Trowel	25
Excel 2mm	1.70	35-45	2.5-3.0	Trowel	25
Excel 3mm	1.70	35-45	3.5-4.5	Trowel	25
Granule 1mm	1.65	35-45	2.5-3.0	Trowel	25
Granule 2mm	1.65	35-45	3.5-4.5	Trowel	25
Sahara 1mm	1.65	35-45	2.5-3.0	Trowel	25
Sahara 2mm	1.65	35-45	3.5-4.5	Trowel	25

TERRACO offers a comprehensive range of products and services for most concrete and finishing needs. Please contact the TERRACO Technical Service Department or your local TERRACO agent for further information, samples, demonstrations and instructor services. The information given in this leaflet is based upon laboratory research, as well as extensive field work and application. All products are sold subject to standard conditions of sale which are available on request. This information is based on TERRACO's present state of knowledge and is intended to provide general information on TERRACO's products and their methods of use. The prospective user is recommended to determine the suitability of TERRACO's suggestions and products before adopting them on a commercial scale.

For technical enquiries please contact your nearest Terraco representative:

CHINA:

Terraco Architectural Coatings China Co., Ltd.
Tel: +86 (0)20 8759 4742
Fax: +86 (0)20 8526 8056
E-mail: sales@terraco.com.cn
Web: www.terraco.com.cn

Terraco Chemical (Shanghai) Co., Ltd.

Tel: +86 (0)21 621020 48 / 18
Fax: +86 (0)21 625205 47
Email: sales@terraco.com.cn
Web: www.terraco.com.cn

EGYPT:

Terraco Egypt Chemical Industries S.A.E.
Tel: +20 (0)22 29184 53 / 57 / 58
Fax: +20 (0)22 29184 80
E-mail: terraco@terraco.com.eg
Web: www.terraco.com.eg

JORDAN:

Jordan Swedish Polymers Industrial Corp.
Tel: +962 (0)6 553 8751
Fax: +962 (0)6 553 6560
E-mail: terraco@nol.com.jo
Web: www.terraco.jo

IRELAND:

Terraco Technical Centre, Ireland
Tel: +353 (0) 404 66555
Fax: +353 (0) 404 66654
E-mail: technical-centre@terraco.com
Web: www.terraco.com

PAKISTAN:

Terraco Pakistan Pvt. Ltd.
Tel: +92 (0)42 3529 70 56-8
Fax: +92 (0)42 3529 70 55
Email: terraco@terraco.pk
Web: www.terraco.com

ROMANIA:

Terraco Romania SRL
Tel: +40 (0)749 203 133
Fax: +40 (0)318 148 810
E-mail: ahaque@terraco.com
Web: www.terraco.com

RUSSIA:

OOO Terraco Sweden Ltd, Russia
Tel: +7 (0)495 9212 237
Fax: +7 (0)495 6273 881
E-mail: adm@terraco.ru
Web: www.terraco.ru

OOO Terraco Vostok Ltd

Tel: +7 (0)4212 410563
Fax: +7 (0)4212 410591
E-mail: terracovostok@terraco.khn.ru
Web: www.terraco.com

SOUTH KOREA:

Terraco Korea Co., Ltd
Tel: +82 (0) 2 5611 551
Fax: +82 (0)2 5671 771
E-mail: terraco@terraco.co.kr
Web: www.terraco.co.kr

THAILAND:

Terraco Industry (Thailand) Limited
Tel: +66 (0)2 946 68 56 / 58
Fax: +66 (0)2 946 68 59
E-mail: terraco@terraco.co.th
Web: www.terraco.com

TURKEY:

Terraco Yapi Malzemeleri Sanayi Ve Ticaret AS
Tel: +90 (0)222 236 0423
Fax: +90 (0)222 236 0425
E-mail: terraco@terraco.com.tr
Web: www.terraco.com.tr

UAE:

Terraco UAE Ltd
Tel: +971 (0)4 326 2699
Fax: +971 (0)4 326 2733
E-mail: sales@addagrip.co.uk
Web: www.terraco.com

UK:

ADDAGRIP
Tel: +44 (0)1825 761 333
Fax: +44 (0)1825 768 566
E-mail: sales@addagrip.co.uk
Web: www.addagrip.co.uk / www.terraco.com

VIETNAM:

Terraco Vietnam Co., Ltd
Tel: +84 (0)650 3 820 100
Fax: +84 (0)650 3 820101
E-mail: terraco@terraco.com.vn
Web: www.terraco.com