



The 112mm Roundstyle system features distinctive integral flexible clips that allow quick and easy snap together assembly on to the gutter length.

External fixing lugs allow the use of cordless power tools, for fast and efficient installation. All fixings may now be kept out of the 'wet' areas of the system, greatly reducing the risk of problems after installation.

The system has been designed to facilitate the conversion of the running outlet into a stopend outlet. Simply trim off the exposed fixing lug and insert an internal stopend, thus preventing the need for handed stopend outlet components.

112mm ROUNDSTYLE RAINWATER SYSTEM

	GUTTER FLOW CAPACITY LITRES PER SECOND		MAXIMUM ROOF AREA m ²	
	Level	1:600	Level	1:600
Outlet at one end	1.00	1.3	48	62
Outlet at centre	1.82	2.43	87	116

