

Tanners Mill Flagstones - Grey-Green Riven Antique Style Concrete Paving

Paving - Concrete Paving Slabs

SPECIAL OFFER

Product details

Antique Flagstone Paving

There are many period and traditionally styled homes, properties and gardens in Britain that require congruous and compatible traditional "antique" paving in keeping with their aesthetic. Tanners Mill decorative concrete paving slabs have been specifically designed to offer an authentic reproduction of fine antique paving flags from a bygone era.

York Flagstones Colouring

With its grey/green colouring and realistic lightly riven surface for a classic look, this range emulates the characteristics of the York flagstones that were being produced in Victorian times. The distinctive worn antique appearance and shades complement many period properties and are perfect for use in any traditional British garden setting.

Weathered Look & Feel

Finding aged and weathered flagstone paving can be time-consuming and very costly. Tanners Mill flagstones provide you with exactly what you are looking for - with the right colouring, weathering and visual characteristics of well-worn and aged antique paving. This predictability and specificity in the aesthetic properties mean your project is going to save an awful lot of time and money getting what you know will work.

Tanners Mill paving has tapered and rounded edges emulating antique paving. It has a simulated smoothed slightly riven and pitted finish to capture the aesthetic of ageing and weathering.

Sourcing Antique Flagstones

Reclaimed flagstones can, and often do, look spot on. But, if you don't have enough of them or they are from multiple sources and don't quite match, you could run into difficulties. This is exactly the sort of project Tanners Mill was designed to solve. Its consistent and scaleable look and feel (in the volumes you might need), means days saved trying to source and match materials. As well as helping save money when sourcing materials, Tanners Mill is competitively priced too, so you'll be saving on two counts by choosing them.

Flagstone Size-Format & Pack Options

Tanners Mill is available in four flagstone formats and comes in two pack options:

Flagstone Sizes

- 300mm x 300mm
- 600mm x 300mm
- 600mm x 450mm
- 600mm x 600mm

Pack Options

- 600mm x 450mm
- Contractor Pack (Mixed Sizes)

We also offer a similar style product in a French rustic style cream/light beige colour - [Garonne Abbey](#) (/decorative-concrete-garonne-abbey).

Free Help & Advice

If you would like any advice or help regarding Tanners Mill and paving for traditional/antique projects please don't hesitate to give our team a call or drop us a line.

Laying Advice

To install and lay concrete patio paving slabs, you'll need to do the following steps:

1. Measure up and mark out your patio - ensure you calculate both 1) area in square metres (m²) and 2) the fall (slope) required for drainage.
2. Dig out the patio area to create the substrate (220 -230 mm depth).
3. Lay the sub-base of MOT Type-1 hardcore (compacted & 150 mm depth).
4. Coat the slabs' underside with priming slurry (/pavestone-priming-slurry) to improve their bond and help prevent moisture transfer. As concrete is porous, priming slurry will help protect the slabs from moisture transfer and capillary action from beneath the slabs.
5. Trowel-in and lay a bedding course of mortar mix (50 mm depth) immediately prior to laying each slab.
6. Lay the paving slabs on to the mortar bed and tamp down. Ensure you leave the desired joint spacing between the slabs and the slabs are "level" to the fall.
7. Leave to set for 24 hours, so the mortar mix can cure enough for you to walk on the slabs.
8. Fill the joints between the paving (pointing) with jointing compound (/pointfix-jointing-compound).
9. Optional: protect your paving by sealing the slabs with a purpose made sealant (natural finish (/pavestone-natural-finish-stone-sealer) or colour enhancing (/pavestone-colour-enhancing-stone-sealer)).

To calculate the areas of paving in square-metres (m²), the amount of sub-base hardcore or the amount of sand and cement you'll need for the mortar mix bedding course, please refer to our [paving calculators](#) (/info/patio-paving-calculators/).

For the full step-by-step guide with videos for each step, see our [How to Lay Patio Paving Slabs](#) (/info/how-to-lay-a-patio) article.

Care & Maintenance

Concrete is a porous material and contains tiny capillaries and micro-fissures throughout its structure. Consequently, concrete paving is susceptible to water-based chemical erosion (acidic corrosion), physical erosion (frost action), and from staining from waterborne grime, salts and other mineral and particulate deposits. Therefore, as the UK has high winter humidity (generally 80-90%) and damp conditions are the norm, we recommend that you help protect and elongate the life of your paving by sealing the slabs against the water/damp based issues. Our impregnating sealers are designed to enter the capillaries and micro-fissures in the slabs, blocking those spaces to prevent water entering the paving.

1. Natural finish sealer ([/pavestone-natural-finish-stone-sealer](#))
2. Colour enhancing sealer ([/pavestone-colour-enhancing-stone-sealer](#))

In addition to sealing the slabs, we recommend ensuring you brush away leaves, dirt and other detritus regularly, especially in the autumn and winter when leaves, twigs, seeds and other windfall materials are likely to fall on your patio. If left on your paving, especially if damp, and worse still, allowed to rot down and become mulch-like, your paving will almost certainly acquire brown stains from the release of tannins from the windfall materials (think a used tea bag left on a kitchen counter for a model of what will happen).

As well as brushing off dirt and windfall materials, give your patio a hose down with water every so often. Use a low-pressure hose or keep any jet-wash far enough away from the slabs to ensure you don't damage them with the high-pressure water jet. For more stubborn stains and the build-up of grime, we recommend using a specialist non-acidic [patio cleaner](#) ([/pavestone-patio-cleaner](#)).

Specifications

	Contractor Pack 40 Pieces (Mixed Sizes)	1 x Sample	Half Pack 20 Pieces (Mixed Sizes)	Tanners Mill 600 x 600
No. of Pieces	40	1	20	30
Pack Coverage (m ²)	9	0.02	4.5	10.99
Range	Premium Concrete	Premium Concrete	Premium Concrete	Premium Concrete
Prod Type	Concrete Paving Slabs	Sample	Concrete Paving Slabs	Concrete Paving Slabs
Material	Concrete	Concrete	Concrete	Concrete
Finish	Light Textured	Light Textured	Light Textured	Light Textured
Finish (Edge)	Tapered / rounded	Tapered / rounded	Tapered / rounded	Tapered / rounded
Colour	Grey	Light Grey	Grey	Grey
Colour Group	Grey	Grey	Grey	Grey
Dimension (W)	Varies	200	Varies	600
Dimension (H)	Varies	100	Varies	600
Dimension (D)	30	30	30	40
Interior / Exterior	Exterior	Exterior	Exterior	Exterior
Pack Contents	C/PACK	Sample	H/PACK	600 x 600
Pack Sold As	Contractor Pack	Sample	Half Pack	Single Size Pack
Pack Description	600 x 600 Qty 10 600 x 450 Qty 10 600 x 300 Qty 12 300 x 300 Qty 8	1 x sample	600 x 600 Qty 5 600 x 450 Qty 5 600 x 300 Qty 6 300 x 300 Qty 4	600 x 600 Qty 30
Pieces Description	Paving Slabs	sample	Paving Slabs	Paving Slabs