

Planting Schedule

Trees					
Species Name	Girth	Height	Density	Specification	No.
Pyrus calleryana 'Chanticleer'	16-18cm	5.0-6.0m	Counted	Heavy Standard :Clear Stem 175-200 :RB	5 No.
Acer platanoides 'Globosum'	16-18cm	5.0-6.0m	Counted	Heavy Standard :Clear Stem 175-200 :RB	3 No.
Crataegus monogyna 'Stricta'	16-18cm	5.0-6.0m	Counted	Heavy Standard :Clear Stem 175-200 :RB	2 No.
Betula pendula 'Fastigiata'	16-18cm	5.0-6.0m	Counted	Heavy Standard :Clear Stem 175-200 :RB	3 No.
Prunus avium 'Plena'	16-18cm	5.0-6.0m	Counted	Heavy Standard :Clear Stem 175-200 :RB	2 No.
Fagus sylvatica	80-100cm	0.3Ctr		Transplant :Bushy :3 brks :3x :BR :Planted and maintained as hedge	22 No.
Fagus sylvatica	80-100cm	0.4Ctr Double Staggered at 0.3m offset		Transplant :Bushy :3 brks :3x :BR :Planted and maintained as hedge	38 No.

Conifers				
Species Name	Height	Pot Size	Specification	Density No.
Cupressocyparis leylandii	100-125cm	10L	Single leader: Ball	Counted 2 No.

Shrubs				
Species Name	Height	Pot Size	Specification	Density
Cornus sanguinea 'Midwinter Fire'	60-80cm	5L	Bushy :C	2/m²
Euonymus japonicus 'Grey Beauty'	60-80cm	7.5L	Bushy :C :Plant and maintain as hedge	3/m
Fuchsia 'Mrs Popple'	40-50cm	5L	Bushy :C	2/m²
Hebe 'Nicola's Blush'	30-40cm	5L	Bushy :C	2/m²
Hebe albicans	30-40cm	5L	Bushy :C	2/m²
Hebe franciscana 'Variegata'	30-40cm	5L	Bushy :C	2/m²
Ilex crenata	60-80cm	10L	Bushy :C :Plant and maintain as hedge	0.3Ctr Double Staggered at 0.3m offset
Lavandula angustifolia 'Munstead'	30-40cm	5L	Bushy :C	3/m²
Ligustrum delavayanum	120-130	15-20L	Half standard :C :Plant as specimen	Counted
Ligustrum delavayanum	125-150cm	15-20L	Half standard :C :Plant as specimen	Counted
Phormium 'Yellow Wave'	60-90cm	7.5L	Several shoots :C :Plant as specimen	Counted
Photinia fraseri 'Red Robin'	60-80cm	7.5L	Bushy :C :Plant and maintain as hedge	3/m
Pyracantha saphyr 'Yellow'	60-80cm	7.5L	Bushy :C :Plant and maintain as hedge	3/m
Rhododendron yakushimanum	45-60cm	7-7.5L	Bushy :C	2/m²
Rosmarinus officinalis 'Miss Jessopp's Upright'	60-80cm	10L	Bushy :C	2/m²

Sarcococca confusa	45-60cm	5L	Bushy :C	2/m²	11 No.
Sarcococca hookerana humilis	45-60cm	5L	Bushy :C	2/m²	5 No.
Viburnum davidii	45-60cm	7-7.5L	Bushy :C	2/m²	38 No.
Viburnum opulus 'Fructo-Luteo'	60-80cm	10L	Bushy :C	2/m²	10 No.

Herbaceous				
Species Name	Height	Pot Size	Specification	Density No.
Astrantia Large White	3L	Full Pot	3/m²	8 No.
Helleborus niger	3L	Full Pot	2/m²	23 No.
Miscanthus sinensis 'Zebrinus'	3L	Full Pot	2/m²	23 No.
Origanum vulgare	2L	Full Pot	3/m²	8 No.
Phlox 'Danielle'	3L	Full Pot	4/m²	15 No.

Ferns				
Species Name	Height	Pot Size	Specification	Density No.
Polystichum aculeatum	3L	Full Pot	3/m²	12 No.

Grasses				
Species Name	Height	Pot Size	Specification	Density No.
Hackonechloa macra	3L	Full Pot	2/m²	8 No.

Legend



Existing trees to be retained and protected during construction



Proposed tree planting within soft landscape. See detail on sheet 12



Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties. Irrigation tubing to root system of *Ligustrum* & *Cupressocyparis* specimens as required



Proposed climbing plants to be trained up adjacent wall/fence with galvanised wires and hook set 250mm apart with support canes removed prior to planting



Proposed *Euonymus* (spindleberry) hedge planting to be planted in a single row at 300mm centres. To be maintained at 1m height



Proposed hedge planting to be planted in a double staggered row 300mm apart and at 300mm centres in each row. To be maintained at 1m height



Proposed shrub planting to receive 75mm bark mulch after planting operations



Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices

SPECIFICATION

All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING



B	26.07.18	Client Comments	JNT
A	30.05.18	Client comments	AD
Rev	Date	Details	Drawn



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

Unit 50, Space Business Centre Gloucester, Olympus Park,
Quedgeley, Gloucester, GL2 4AL
Tel: 07769 263864

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk



scheme: 297 Long Lane
Uxbridge

client: Howarth Homes

drawing: Soft Landscape

date: May 2018

scale: 1:200@A2

drawing no: HOW21700-11B

drawn: JNT checked: JS

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted: 2011. Copyright of this plan remains with ACD until all fees have been paid in full.