



SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTES:
DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY

62No *Corylus avellana* 20%
92No *Crataegus monogyna* 30%
77No *Carpinus betulus* 25%
77No *Fagus sylvatica* 25%

Entire site plan and soft landscape proposals location
NTS

Legend

- Existing trees to be retained and protected during construction
- Proposed mixed native hedge planting to be planted in a double staggered row 500mm apart and at 500mm centres in each row. To be maintained at 1.8m height. Species to be planted in groups of 3-5. No trench digging, to be hand dug within existing tree RPA's and planted by hand
- Proposed animal exercise paddock areas to be seeded with tough grass mix
- Existing verge grassland, to be over-seeded as required

0 1 2 3 4

Rev	Date	Details	Drawn
C	01/05/26	Remove hedge from vis splay	JS
B	08/12/25	Updated layout graphics	JS
A	27/11/25	Comments and updated layout	AD

ACD ENVIRONMENTAL
HEAD OFFICE
Rodbourn Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646
4 & 5 The Old Mill, Fry's Yard, Bridge Street,
Godalming, GU7 1HP
Tel: 01483 425714
Suite 6, Crescent House, Yonge Close,
Eastleigh, SO50 9SX
Tel: 02382 026300
email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

scheme: Airpets, Spout Lane North, Heathrow
client: Airpets
drawing: Landscape Proposals
date: October 2025
scale: 1:100@A1
drawing no: PRI24982 11C Sheet 2 of 2
drawn: AD checked: JS

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

tina under