

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by	NT	 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather	Overcast			
Date:	20.12.23										Tagged	No			
Client:	Columbia Threadneedle Investments														
				Canopy Spread											
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category
T1	Quercus palustris (Pin Oak)	8	250	4	3	4	4	1	2	MA	Good	Good	None	40+	B2
T2	Quercus palustris (Pin Oak)	8	220	4	2	4	3	1	2	MA	Fair - upper crown die back	Good	None	10-20	C1
T3	Quercus palustris (Pin Oak)	8	270	3	3	4	3	1	2	MA	Fair - upper crown die back	Good	None	10-20	B2
T4	Quercus palustris (Pin Oak)	8	210	3	2	4	2	1	2	MA	Fair - upper crown die back	Good	None	10-20	C1
T5	Quercus palustris (Pin Oak)	8	210	2	3	4	3	1	2	MA	Good	Good	None	40+	B2
T6	Quercus palustris (Pin Oak)	8	200	3	2	3	2	1	2	MA	Good	Good	None	40+	B2
T7	Quercus palustris (Pin Oak)	8	200	4	2	4	3	1	2	MA	Good	Good	None	40+	B2
T8	Quercus palustris (Pin Oak)	8	200	4	3	4	3	1	2	MA	Fair - upper crown die back	Good	None	10-20	C1
T9	Quercus palustris (Pin Oak)	8	200	4	3	3	3	1	2	MA	Good	Good	None	40+	B2
T10	Quercus palustris (Pin Oak)	9	220	4	3	3	3	1	2	MA	Good	Good	None	40+	B2
T11	Quercus palustris (Pin Oak)	8	200	3	3	3	3	1	2	MA	Good	Good	None	40+	B2
T12	Quercus palustris (Pin Oak)	8	190	3	3	3	3	1	2	MA	Good	Good	None	40+	B2

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations	Surveyed by		NT	 Greenspace Ecological Solutions			
Ref:	J21357_Arb								Weather		Overcast				
Date:	20.12.23								Tagged		No				
Client:	Columbia Threadneedle Investments														
				Canopy Spread											
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category
T13	Quercus palustris (Pin Oak)	8	210	3	3	4	3	1	2	MA	Good	Good	None	40+	B2
T14	Quercus palustris (Pin Oak)	8	200	3	3	4	3	1	2	MA	Good	Good	None	40+	B2
T15	Quercus palustris (Pin Oak)	7	200	3	3	3	2	1	2	MA	Poor - moribund	Fair	Remove tree.	<10	U
T16	Quercus palustris (Pin Oak)	7	200	3	1	2	2	1	2	MA	Dead	Fair	Remove tree.	0	U
T17	Quercus palustris (Pin Oak)	8	200	2	2	3	4	1	3	MA	Good	Good	None	40+	B2
T18	Quercus palustris (Pin Oak)	9	220	2	2	3	3	1	3	MA	Good	Good	None	40+	B2
T19	Quercus palustris (Pin Oak)	8	210	2	2	3	3	1	3	MA	Good	Good	None	40+	B2
T20	Quercus palustris (Pin Oak)	8	200	2	2	2	3	1	3	MA	Good	Good	None	40+	B2
T21	Quercus palustris (Pin Oak)	9	250	2	2	3	3	1	3	MA	Good	Good	None	40+	B2
T22	Quercus palustris (Pin Oak)	8	160	2	2	1	1	1	3	MA	Poor - suppressed.	Fair	None	<10	U
T23	Quercus palustris (Pin Oak)	9	250	2	2	4	3	1	2	MA	Good	Good	None	40+	B2
T24	Quercus palustris (Pin Oak)	10	280	4	3	5	3	1	3	MA	Good	Good	None	40+	B2

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by	NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather	Overcast				
Date:	20.12.23										Tagged	No				
Client:	Columbia Threadneedle Investments															
				Canopy Spread												
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category	
T25	Quercus palustris (Pin Oak)	8	200	3	2	3	3	1	3	MA	Good	Good	None	40+	B2	
T26	Quercus palustris (Pin Oak)	10	270	3	4	4	4	1	2	MA	Good	Good	None	40+	B2	
T27	Populus alba (White Poplar)	16	660	1	3	10	9	1	6	M	Good	Fair - Poor shape & form.	None	20-40	B2	
T28	Populus alba (White Poplar)	18	670	2	3	10	12	1	4	M	Good	Fair - Poor shape & form.	None	20-40	B2	
T29	Populus canescens (Grey Poplar)	18	570	5	2	3	1	1	6	M	Fair - Die back. Off site.	Fair - large deadwood	None	20-40	B3	
T30	Populus canescens (Grey Poplar)	18	577	3	2	7	2	2	4	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3	
T31	Populus canescens (Grey Poplar)	18	540	1	4	7	2	1	4	M	Fair - Poor shape & form. Die back. Off site.	Fair	None	20-40	B3	
T32	Populus canescens (Grey Poplar)	18	549	3	2	11	2	2	4	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3	
T33	Populus canescens (Grey Poplar)	18	950	4	2	6	6	3	4	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3	
T34	Quercus palustris (Pin Oak)	8	200	2	3	4	3	1	3	MA	Good	Good	None	40+	B2	
T35	Quercus palustris (Pin Oak)	8	260	2	3	3	4	1	2	MA	Good	Good	None	40+	B2	
T36	Populus canescens (Grey Poplar)	18	600	4	5	7	1	1	4	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3	

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by		NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather		Overcast				
Date:	20.12.23										Tagged		No				
Client:	Columbia Threadneedle Investments																
				Canopy Spread													
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category		
T37	Populus canescens (Grey Poplar)	18	650	8	5	7	2	1	4	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3		
T38	Populus canescens (Grey Poplar)	18	440	0	1	9	7	1	4	M	Fair - Poor shape & form. Off site.	Fair	None	10-20	C1		
T39	Populus canescens (Grey Poplar)	18	600	6	3	6	7	1	6	M	Fair - Poor shape & form. Off site.	Fair	None	20-40	B3		
T40	Quercus palustris (Pin Oak)	12	300	4	4	5	3	1	2	MA	Good	Good	None	40+	A2		
T41	Quercus palustris (Pin Oak)	11	300	4	2	4	5	1	2	MA	Good	Good	None	40+	B2		
T42	Quercus palustris (Pin Oak)	7	200	3	2	3	3	1	2	MA	Poor - moribund	Fair	Remove tree.	0	U		
T43	Quercus palustris (Pin Oak)	11	340	4	5	4	3	1	2	MA	Good	Good	None	40+	A2		
T44	Quercus palustris (Pin Oak)	9	230	4	2	4	4	1	2	MA	Good	Good	None	40+	B2		
T45	Quercus palustris (Pin Oak)	8	220	4	4	3	2	1	3	MA	Good	Good	None	40+	B2		
T46	Quercus palustris (Pin Oak)	8	250	4	3	5	3	1	2	MA	Good	Good	None	40+	B2		
T47	Quercus palustris (Pin Oak)	10	250	4	3	5	3	1	2	MA	Good	Good	None	40+	A2		

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by		NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather		Overcast				
Date:	20.12.23										Tagged		No				
Client:	Columbia Threadneedle Investments																
				Canopy Spread													
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category		
T48	Quercus palustris (Pin Oak)	10	250	3	3	4	3	1	3	MA	Good	Good	None	40+	B2		
H24	Taxus baccata (Yew)	1	40	0.6	1	1	1	1	0	MA	Good	Good	None	40+	C1		
T49	Quercus palustris (Pin Oak)	6	200	3	3	4	3	1	3	MA	Good	Good	None	40+	B2		
T50	Quercus palustris (Pin Oak)	6	170	2	3	2	2	1	3	MA	Poor - Die back.	Fair	None	<10	U		
T51	Quercus palustris (Pin Oak)	7	200	3	3	2	3	1	3	MA	Good	Good	None	40+	B2		
T52	Quercus palustris (Pin Oak)	6	210	3	5	3	3	1	3	MA	Good	Good	None	40+	B2		
T53	Quercus palustris (Pin Oak)	11	320	4	5	4	4	1	3	MA	Good	Good	None	40+	B2		
T54	Quercus palustris (Pin Oak)	11	290	4	3	5	4	1	2	MA	Good	Good	None	40+	B2		
T55	Quercus palustris (Pin Oak)	10	200	4	3	4	3	1	3	MA	Good	Good	None	40+	A2		
T56	Quercus palustris (Pin Oak)	10	200	3	4	3	4	1	3	MA	Good	Good	None	40+	B2		
T57	Quercus palustris (Pin Oak)	10	200	3	4	4	4	1	3	MA	Good	Good	None	40+	B2		

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by		NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather		Overcast				
Date:	20.12.23										Tagged		No				
Client:	Columbia Threadneedle Investments																
				Canopy Spread													
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category		
T58	Quercus palustris (Pin Oak)	10	180	3	4	4	4	1	3	MA	Good	Good	None	40+	B2		
T59	Quercus palustris (Pin Oak)	10	190	3	3	3	4	1	3	MA	Good	Good	None	40+	B2		
T60	Quercus palustris (Pin Oak)	6	170	3	3	3	3	1	3	MA	Fair - Declining.	Good	None	10-20	C1		
T61	Quercus palustris (Pin Oak)	10	190	4	3	3	3	1	3	MA	Good	Good	None	40+	B2		
T62	Quercus palustris (Pin Oak)	6	170	4	3	4	3	1	3	MA	Fair - Declining.	Good	None	10-20	C1		
T63	Quercus palustris (Pin Oak)	7	180	3	3	2	3	1	3	MA	Good	Good	None	40+	B2		
T64	Quercus palustris (Pin Oak)	9	190	3	4	3	4	1	2	MA	Good	Good	None	40+	B2		
T65	Quercus palustris (Pin Oak)	9	140	2	3	2	4	1	2	MA	Good	Good	None	40+	B2		
T66	Quercus palustris (Pin Oak)	9	200	4	3	3	4	1	3	MA	Good	Good	None	40+	B2		
T67	Quercus palustris (Pin Oak)	11	240	3	3	4	3	1	2	MA	Good	Good	None	40+	B2		
T68	Quercus palustris (Pin Oak)	6	190	3	3	3	3	1	3	MA	Fair - Declining.	Good	None	10-20	C1		

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations	Surveyed by		NT	 Greenspace Ecological Solutions			
Ref:	J21357_Arb								Weather		Overcast				
Date:	20.12.23								Tagged		No				
Client:	Columbia Threadneedle Investments														
				Canopy Spread											
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category
T69	Quercus palustris (Pin Oak)	7	160	4	3	4	3	1	3	MA	Fair - Declining.	Good	None	10-20	C1
T70	Quercus palustris (Pin Oak)	5	150	4	3	3	3	1	2	MA	Fair - Declining.	Good	None	10-20	C1
T71	Quercus palustris (Pin Oak)	7	190	4	3	4	3	1	2	MA	Good	Good	None	40+	B2
T72	Quercus palustris (Pin Oak)	9	180	3	3	3	3	1	3	MA	Good	Good	None	40+	B2
T73	Quercus palustris (Pin Oak)	10	180	3	4	3	4	1	3	MA	Good	Good	None	40+	B2
T74	Quercus palustris (Pin Oak)	9	170	3	3	3	3	1	3	MA	Good	Good	None	40+	B2
T75	Quercus palustris (Pin Oak)	10	200	3	3	3	4	1	3	MA	Good	Good	None	40+	B2
T76	Quercus palustris (Pin Oak)	11	220	3	3	3	4	1	3	MA	Good	Good	None	40+	B2
T77	Quercus palustris (Pin Oak)	9	180	3	3	1	4	1	3	MA	Good	Good	None	40+	B2
T78	Quercus palustris (Pin Oak)	9	180	2	4	2	4	1	3	MA	Good	Good	None	40+	B2
T79	Quercus palustris (Pin Oak)	9	160	2	4	2	4	1	3	MA	Good	Good	None	40+	B2
T80	Quercus palustris (Pin Oak)	11	290	3	5	4	3	1	2	MA	Good	Good	None	40+	B2
T81	Quercus palustris (Pin Oak)	9	170	3	3	2	3	1	3	MA	Good	Good	None	40+	B2

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by		NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather		Overcast				
Date:	20.12.23										Tagged		No				
Client:	Columbia Threadneedle Investments																
				Canopy Spread													
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category		
T82	Quercus palustris (Pin Oak)	11	240	3	4	3	4	1	2	MA	Good	Good	None	40+	B2		
T83	Quercus palustris (Pin Oak)	9	230	3	3	4	4	1	2	MA	Good	Good	None	40+	B2		
T84	Quercus palustris (Pin Oak)	10	250	4	3	5	4	1	2	MA	Good	Good	None	40+	B2		
G1	Taxus baccata (Yew),Prunus laurocerasus (Cherry Laurel)	3	Varied							Y	Good - soft landscape planting	Good	None	40+	C1		
G2	Taxus baccata (Yew),Prunus laurocerasus (Cherry Laurel)	3	Varied							Y	Good - soft landscape planting	Good	None	40+	C1		
G3	Taxus baccata (Yew),Prunus laurocerasus (Cherry Laurel)	3	Varied							Y	Good - soft landscape planting	Good	None	40+	C1		
G4	Corylus avellana (Hazel),Crataegus monogyna (Hawthorn)	6	Varied							Y	Good - boundary group. Off site.	Good	None	40+	C1		
G5	Prunus laurocerasus (Cherry Laurel)	1.5	Varied							Y	Good - soft landscape planting	Good	None	40+	C1		
G6	Prunus laurocerasus (Cherry Laurel)	1.5	Varied							Y	Good - soft landscape planting	Good	None	40+	C1		

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by	NT	 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather	Overcast			
Date:	20.12.23										Tagged	No			
Client:	Columbia Threadneedle Investments														
				Canopy Spread											
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category
G7	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
G8	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
G9	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
G10	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
G11	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
G12	Tilia X europaea (Common Lime)	6	Varied							MA	Good - linear group of pollards.	Good	None	40+	B2
H1	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1
H2	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1
H3	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1
H4	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1
H5	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by	NT	 Greenspace Ecological Solutions			
Ref:	J21357_Arb										Weather	Overcast				
Date:	20.12.23										Tagged	No				
Client:	Columbia Threadneedle Investments															
				Canopy Spread												
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category	
H6	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H7	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H8	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H9	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H10	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H11	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H12	Carpinus betulus (Hornbeam)	3	Varied								Y	Good - boundary hedge	Good	None	40+	C1
H13	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H14	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H15	Taxus baccata (Yew)	1	Varied								Y	Good - internal hedge	Good	None	40+	C1
H16	Carpinus betulus (Hornbeam)	3	Varied								Y	Good - boundary hedge	Good	None	40+	C1

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by	NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather	Overcast				
Date:	20.12.23										Tagged	No				
Client:	Columbia Threadneedle Investments															
				Canopy Spread												
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category	
H17	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H18	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H19	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H20	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H21	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H22	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H23	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H25	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H26	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H27	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H28	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations	Surveyed by		NT	 Greenspace Ecological Solutions				
Ref:	J21357_Arb								Weather		Overcast					
Date:	20.12.23								Tagged		No					
Client:	Columbia Threadneedle Investments															
				Canopy Spread												
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category	
H29	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H30	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H31	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H32	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H33	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H34	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H35	Carpinus betulus (Hornbeam)	3	Varied							Y	Good - boundary hedge	Good	None	40+	C1	
H36	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H37	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H38	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	
H39	Taxus baccata (Yew)	1	Varied							Y	Good - internal hedge	Good	None	40+	C1	

Project:	3 The Square, Stockley Park							BS 5837 2012 Trees in relation to design, demolition and construction- recommendations			Surveyed by		NT		 Greenspace Ecological Solutions		
Ref:	J21357_Arb										Weather		Overcast				
Date:	20.12.23										Tagged		No				
Client:	Columbia Threadneedle Investments																
				Canopy Spread													
Tree No.	Species	Height (m)	Stem Dia. (mm)	N	E	S	W	Stems	Height of crown clearance	Age class	Physiological condition problems/comments	Structural condition	Preliminary management recommendations	Estimated remaining contribution years	BS category		
H40	Taxus baccata (Yew)	1	Varied						Y	Good - internal hedge	Good	None	40+	C1			