

Aggregate Industries...
Marston House,
Marston Bigot,
FROME,
Somerset,
BA11 5DU
Contract: Torr

Date: 25 August 2015
Test Report Ref: STR 426626

Order No: 7056520
Page 1 of 1

LABORATORY TEST REPORT

TEST REQUIREMENTS:

To determine the Fragmentation of Aggregate - Los Angeles
Test Method in accordance with **BS EN 1097-2: 2010**

SAMPLE DETAILS:

Certificate of sampling received:	Yes
Laboratory Ref. No:	S54142
Client Ref. No:	Aggs21772 - 63181C
Date and Time of Sampling:	03/08/2015 (06:30)
Date of Receipt at Lab:	11/08/2015
Date of Start of Test:	20/08/2015
Sampling Location:	Current Production Belt
Name of Source:	Torr Works
Method of Sampling:	Unknown
Sampled By:	Client
Material Description:	6/14mm SS Carboniferous Limestone
Target Specification:	N/A

RESULTS:


Size fraction from which the test portion was obtained: 14mm to 12.5mm
12.5mm to 10.0mm

Los Angeles Coefficient (LA) = 24

Comments

None

Certificate
Prepared by:-


Neil Hughes
Job Coordinator

Approved by: -



Eric Goulden
Technical Manager