

PLANTING SCHEDULE						
CLASS		NO.	UNIT	SPECIES	SIZE & SPECIFICATION	ROOT
Trees	Ame Lam	4 no.		Amelanchier lamarckii	multistem - umbrella form 250-300cm	RB
	Bet Jaq	3 no.		Betula utilis var. jacquemontii	multistem, min 3 trunks, 350-400cm	RB
Specimens	Ali Hol	21 no.		Alium hollandicum	Full pot, fully rooted, healthy clump	5L
	Cal Kar	20 no.		Calamagrostis x acutifolia 'Karl Foerster'	30-40cm dia, bushy, full pot	10L
	KnI Ulv	5 no.		Kniphofia ulvaris	Full pot, fully rooted, healthy clump	5L
	Per Blu	6 no.		Perovskia atriplicifolia 'Blue Spire'	80-100cm ht, Full Pot	10L
	Pho Ten	11 no.		Phormium tenax 'Jester'	40-50cm dia, full pot	20L
	Pin Mug	12 no.		Pinus mugo 'Mops'	30-40cm dia, bushy, full pot	10L
	Sax Urb	8 no.		Saxifraga x urbinum	30-40cm, bushy, full pot	10L
	Ver Bon	1 no.		Verbena bonariensis	Full pot, fully rooted, healthy, full pot	10L
Shrubs	Alc Mol	34 no.		Alchemilla mollis	Full pot, fully rooted, healthy clump	3L
	Car Fla	46 no.		Carex flacca 'Blue Zinger'	Full pot, fully rooted, healthy clump	5L
	Eup Pal	29 no.		Euphorbia Palustris	60-80cm ht, branched min 7 breaks	10L
	Heb Pin	101 no.		Hebe pinguifolia 'Sutherlandii'	60-80cm ht, branched min 7 breaks	10L
	Heu Pal	39 no.		Heuchera 'Palace Purple'	60-80cm ht, branched min 5 breaks	10L
	Jun Wil	48 no.		Juniperus horizontalis 'Wiltonii'	20-30cm ht, bushy, min 5 breaks	5L
	Sal Nem	64 no.		Salvia nemorosa	40-60cm ht, branched, min 5 breaks	5L
	Sax Urb	10 no.		Saxifraga x urbinum	Full pot, fully rooted, healthy clump	5L
	Spi Gol	29 no.		Spirea japonica 'Gold Flame'	20-30cm dia, bushy, full pot	5L
	Ver Bon	7 no.		Verbena Bonariensis	Full pot, fully rooted, healthy clump	5L
General Notes				All new planting to be top-dressed with a 50mm layer of medium grade bark mulch. All shrubs & seed to be of local (UK) provenance. Use of herbicides to be avoided.		

Refer to 06-992-701 for Planting Plan

OUTLINE SPECIFICATION

Existing trees and shrubs to be retained shall be protected in accordance with the current British Standard 'Trees in relation to construction'. Generally fencing shall be a 1.2m high cleft chestnut or 1.8m 'Herres' type fencing secured and maintained in position for the duration of construction.

GENERAL

All planting work & plants shall be in accordance with all approved current/relevant horticultural & British Standard specifications including 'Nursery stock', 'Landscape Operations', 'Trees in relation to Design, Demolition & Construction', 'Tree Work' and the latest National Building Specification, National Plant Specification & HTA 'Handling & Establishing Landscape Plants. Herbicides, pesticides and other chemicals may only be used with the approval of the CA Use of chemicals shall be in accordance with all relevant guidelines and the manufacturers recommendations. Imported topsoil shall be a minimum specification of general-purpose grade, unless otherwise instructed. 1 cu.m approved compost/organic material/soil ameliorant per 20 sq m shall be cultivated into topsoil before planting. Peat shall not be used. Following planting all shrub beds shall be treated with an approved granular fertilizer at rates recommended by the manufacturer. All ornamental planting beds shall be mulched with 50mm depth medium grade ornamental bark mulch. All hedge and native planting shall be mulched with 75mm depth mushroom compost.

TOPSOIL

Imported topsoil shall be a minimum specification to current British Standard Multi-purpose grade from an approved source in accordance to the above specification, unless otherwise instructed. 1 cu.m approved compost/organic material/soil ameliorant per 20 sq m shall be cultivated into topsoil before planting. Peat shall not be used.

MAINTENANCE

The defects liability period for planting shall be 12 months from completion of the works, to the current British Standard. During this period, any plant which is found to be dead, dying or otherwise defective shall be replaced at the expense of the contractor during the next planting season. The contractor shall make maintenance visits as required to ensure the successful establishment of the planting and maintain all shrub areas in a weed free condition. Regular visits (minimum 8 No.) required, to maintain all planted areas in a weed and litter free condition using a combination of chemical spray and hand weeding to be agreed with the CA. Maintenance to include watering, pruning, pest and disease control and re-mulching as required to current British Standard. Final visit to be immediately prior to handing over and to include a fertilizer treatment of Enmag (6:20:10) at 100g/m2 and 25mm depth bark mulch top up to all ornamental planted area. Amenity grass mowing at two-week intervals during growing season, meadow grass maintained in accordance with seed supplier's recommendation. Maintenance to be carried out in years 2-5 to be agreed.

PLANT SCHEDULE

Trees - Trees planted into tree pits 75mm deeper than the root system and wide enough to accommodate roots when fully spread. Root balled trees to be dug 500mm wider and same depth as the rootball. If the site is on an uncultivated site or where clay soils could get waterlogged the tree pits should be 2-3 times the size of the rootball. Hedges - Planted into 450mm depth topsoil. Specimen Shrubs - Planted Into 450mm depth topsoil. Ornamental Shrubs and Groundcovers - Planted into 450mm depth topsoil. Climbers - Planted Into 450mm depth topsoil as indicated. Support to be provided as required. Grass area - 100mm depth topsoil

TREE PLANTING

All trees are to be planted as shown ensuring a minimum of 5 metres from buildings and 3 metres from drainage. Tree pits to have suitable topsoil to the current British Standard to a suitable depth, with irrigation, drainage, root protection, aeration, root cells as required to suit ground conditions, as approved by CA.

PLANT MATERIAL TREATMENT

All to be British grown stock and fully hardened off. Root Dip - Proprietary Root Dip applied to all bare rooted stock (1) at time of lifting at nursery and (2) prior to planting. Anti-Desiccant - Proprietary anti-desiccant to be applied to foliage of all containerized root balled material in leaf, specimen conifers and evergreen etc., (1) prior to transportation and (2) during any delay in planting.

Pruning - Allow for pruning of all deciduous trees and shrubs by 113rd following planting at Landscape Architects instruction or as indicted in the planting schedule. Tree stakes and ties - Stakes to be pressure treated, round, smooth and peeled larch or chestnut, not less than 100mm in diameter. Advanced nursery stock - double staked with cross bar



Alchemilla mollis



Allium hollandicum



Calamagrostis x acutifolia 'Karl Foerster'



Kniphofia ulvaris



Perovskia atriplicifolia 'Blue Spire'



Phormium tenax 'Jester'



Pinus Mugo 'Mops'



Saxifraga urbium



Salvia nemorosa



Carex flacca 'Blue Zinger'



Euphorbia Palustris



Hebe pinguifolia 'Sutherlandii'



Heuchera 'Palace Purple'



Juniperus horizontalis 'Wiltonii'



Spirea japonica 'Gold Flame'



Verbena bonariensis



Amelanchier lamarkii



Betula utilis var. Jacquemontii



Note:
The material contained in this document has been reproduced from an Ordnance Survey map with permissionof the Controller of Her Majesty's Stationery Office. Crown Copyright Licence number AL100035542

Rev A, 08.07.2021 Amended southern garden space, LB
revision / date / description / drawn

Gloucester House,
399 Silbury Boulevard,
Milton Keynes,
Buckinghamshire
MK9 2AH
T 01908 303701
W www.enplan.net



client	
ARRI	
project	scale
ARRI - PHASE 2	1:100 @ A1
-	date
	MAY 2021
title	drawn
Plant Schedule and Specification	LB
	checked
	DC
drawing number	revision
06-992-702	A
issue	
	For Infomation