

Native Hedgerow-2-5.824 sq m	Native Hedgerow-2-5.633 sq m	Native Hedgerow-2-25.380 sq m
6-Ilex aquifolium	6-Ilex aquifolium	25-Ilex aquifolium
6-Corylus avellana	6-Corylus avellana	25-Corylus avellana
3-Rosa canina	3-Rosa canina	13-Rosa canina
3-Viburnum opulus	3-Viburnum opulus	13-Viburnum opulus
3-Malus sylvestris	3-Malus sylvestris	13-Malus sylvestris
3-Amelanchier lamarckii (shrub)	3-Amelanchier lamarckii (shrub)	13-Amelanchier lamarckii (shrub)
6-Fagus sylvatica (h)	6-Fagus sylvatica (h)	25-Fagus sylvatica (h)

NOTES

- For planting shedges please refer to drawing PW1605_L6

-For herbaceous planting please refer to drawing PW1605_L5

-For tree planting specification please refer to the soft landscape specification.

Shrub and Climbers Planting Schedule

Quantity	Abbr	Latin Name	Specification
Shrubs to be planted in locations as shown on planting plans.			
4	BB	Acanthus mollis	5L
1	Ala	Amelanchier lamarckii	35L Multistem
8	Bus (cone)	Buxus sempervirens (F40-60cm, 10L	
6	CBM	Ceanothus 'Blue Moun	5L
12	CsN	Chaenomeles specios	10L
4	Cp	Cistus x purpureus	5L
4	Ecsw	Euphorbia characias s	10L
3	Fj	Fatsia japonica	10L
3	Gh	Genista hispanica	10L
15	HPE	Hebe 'Pink Elegance'	5L
9	Hr	Hebe rakaiensis	5L
2	HnWP	Helianthemum nummu	5L
4	HsOB	Hibiscus syriacus 'Oise	10L
3	HmP	Hydrangea macrophyll	10L
5	LavH	Lavandula angustifolia	2L
3	MaA	Mahonia aquifolium 'A	10L
16	Mstr	Matteuccia struthiopter	2L
1	Mm	Melianthus major	10L
3	Od	Osmanthus delavayi	10L
6	PRa	Penstemon 'Raven'	5L
1	PMH	Philadelphus 'Manteau	15L
3	PPS	Phormium 'Pink Stripe'	10L
10	PFF	Pieris 'Forest Flame'	10L
1	PxOG	Pyracantha x 'Orange	5L
1	RMW	Rosa 'Munstead Wood	3L
3	RLS	Rosa 'Lady of Shalott'	5L
6	RMIP	Rosa 'Madame Isaac F	5L
4	RoMJU	Rosmarinus officinalis	5L
1	ScN	Santolina chamaecyp	5L
7	Sc	Sarcococca confusa	10L
12	Vd	Viburnum davidii	

Hedge Planting Schedule

Quantity	Abbr	Latin Name	Specification
Hedges to be planted in locations as shown on planting plans.			
Carpinus betulus hedge to be planted in a single row, 3 per linear meter.			
Native hedgerow mix to be planted to be planted in a random mix, double staggered rows. 5 per linear meter.			
182	Ia	Ilex aquifolium	BR, 120-150, 1+1 trainsplant. Breaks and laterals
182	Coa	Corylus avellana	BR, 120-150, 1+1 trainsplant. Breaks and laterals
92	Rcan	Rosa canina	BR, 120-150, 1+1 trainsplant. Breaks and laterals
92	Vo	Viburnum opulus	BR, 120-150, 1+1 trainsplant. Breaks and laterals
92	Ms(s)	Malus sylvestris	BR, 120-150, 1+1 trainsplant. Breaks and laterals
92	Als	Amelanchier lamarckii (shrub)	BR, 120-150, 1+1 trainsplant. Breaks and laterals
182	Fs(h)	Fagus sylvatica (h)	BR, 120-150, 1+1 trainsplant. Breaks and laterals
242	CB	Carpinus betulus	RB, 150-175cm, feathered tree.



- GENERAL NOTES
- Scaled dimensions must not be taken from this drawing.
 - This drawing must be read in conjunction with all relevant drawings, documents and information prepared by the Landscape Architect, other consultants and specialists.
 - Any discrepancy on this drawing must be referred to the Landscape Architect and clarification obtained prior to any works commencing.
 - All dimensions must be checked on site before commencing works or prior to the preparation of drawings by other consultants.

Portus + Whitton
landscape architects

Portus + Whitton
58 Ashcroft Road Cirencester
Gloucestershire GL7 1GX
T: 01285 644336 F: 01285 644336
E: contact@portusandwhitton.co.uk

Anchor Hanover Group					
St Andrew's Park Extra Care Development					
Soft Landscape - Hedge & Specimen Shrub Planting Plan					
scale	date	project no.	prof.	dig. no.	rev.
1:100	A0	JUL 2019	1605	L	4 D
The contents of this drawing are the copyright of PORTUS & WHITTON					
purpose of issue					
DISCHARGE OF CONDITIONS					

REVISIONS		
Rev A - First Issue		29.08.19
Rev B - Drawing updated to revised building layout.		30.09.19
Rev C - Drawing issued for discharge of conditions		10.03.20
Rev D - Notes added about work within the existing RPA.		11.06.20