

CCTV legend



CCTV Camera (Dome Type)

The system proposed shall comprise high definition fixed (dome type) and pan, tilt and zoom (PTZ) IP based colour cameras.

The complete CCTV system shall be IP addressable and wired using Cat6 (UTP) cable terminating in rack mounted 24 port patch panels. All fixed cameras shall be powered via power over Ethernet (POE) connections. Dedicated 24 channel Cisco or similar approved, POE switches shall be provided within the data cabinets containing the CCTV network equipment. The switches shall be positioned to accommodate easy cross patching of outlets.

The system shall be modular in design to allow future expansion without previously installed items becoming obsolete.

The CCTV network shall be capable of extension and shall include appropriate security protection to allow monitoring by authorised staff only such as the councils security team.

The CCTV shall have the facility for remote interrogation utilising Internet connection.

The hard drive disc recording equipment shall be evidential standard. The control equipment shall be located in the Management Company's office in the basement. The system shall include for 2no 21" LED screens located on the controllers desk, allowing for monitoring of individual cameras. A dedicated PC with 2no dual output graphic cards to allow a fully integrated system. A USB joystick controller shall be provided for operating the PTZ cameras.

We are proposing a digital scheme which can be addressed over the Internet which should make it compatible with the Councils CCTV scheme.

The cameras will be as supplied by Swift Fire & security or similar approved.

Cameras will be positioned generally as indicated on the drawings.

The system will be a digital micro CCTV system provided by Swift Fire & Security Ltd, or similar approved, to cover the following areas:
Ground floor entrance lobbies, facing the front door.
A central location within the site

NOTES

This drawing is the copyright of Thrive Ltd ©. All rights reserved.
Ordnance Survey Data © Crown Copyright. All rights reserved.
Licence No. 100007359. DO NOT scale from this drawing.
Contractors, Sub Contractors and Suppliers are to check all relevant dimensions and levels of the site and building before commencing any shop drawings or building work. Any discrepancies should be recorded to the Architect.
Where applicable this drawing is to be read in conjunction with the Consultants' drawings.

REV	DESCRIPTION	DATE	AUTH	CHK'D
A	Apartment UA repositioned and access ramp added.	13/08/16	LD	
B	Camera positions amended	20/07/17	SJ	
C	Plots 19 & 22 boundaries amended	29/10/19	MRM	
D	Camera positions amended to suit client request dated 3/3/2021	08/03/21	CW	

PRELIMINARY



architects

Romsey Office

Building 300, The Grange, Romsey Road, Michelmersh, SO51 0AE
t: 01794 367703 f: 01794 367276 www.thrivearchitects.co.uk

PROJECT

St Andrews Park, Uxbridge


Phase 4

for St Modwen

DRAWING

CCTV Camera Locations

SCALE	DATE	AUTHOR	CHK'D
1:500 @ A2	August 2016	TS	
JOB NO.	DRAWING NO.	REV	
STMO160306	CL.01	D	
CLIENT REF.			



scale 1:500

