



To:	7142G19 - CASH SALE WEST DRAYTON SUPERBRANCH	WOLSELEY WEST DRAYTON		
FAO:	BGH	UNIT 3/4 ZODIAC PARK		
Quotation Number:	BGHJ35124	HIGH ROAD		
Your Ref:		WEST DRAYTON		
Job/Site Ref:	BGH	UB8 2GU		
Quotation Date:	03/03/2020	01895 439888		
		01895 439673		
Quotation Total		£1,036.00		
Product Description	Quantity	Per	Each (£)	Total Line Value (£)
211368 TOWELRADS EVERSLY TOWELRAIL 1200X500	1		203.867	203.867
250804 INTA 15MM ANG CHROME TRV+METAL LS PK	1		17.703	17.703
D13266 COLINA COMFORT HEIGHT PAN WHITE	1		141.712	141.712
D13267 COLINA COMFORT HEIGHT CISTERN WHITE	1		72.628	72.628
D13268 COLINA SOFT CLOSE SEAT WHITE	1		48.414	48.414
D13203 DEBBA 500MM 1TH BASIN WHITE	1		60.548	60.548
C20226 * CB 32MM CONTEMPORARY BOTTLE TRAP	1		20.400	20.400
C50535 * NABIS 1 25" BSN WST SPIN SLOTTED CP	1		7.200	7.200
D45253 TARGA SMOOTH BODY BASIN MXR NO PWU CHR	1		81.706	81.706
D62483 2.1878.002 MIRA RELATE DUAL OUTLETVALVE	1		173.404	173.404
G60597 LV100TS TIMER SQUARE SIMPLY SILENT	1		42.486	42.486
D53370 IMPY 200W/2.0M2 AQUA MAT	1		73.707	73.707
D54013 TOUCH THERMOSTAT/TIMER - WHITE	1		92.228	92.228
Quotation Total				£1,036.00
Product Description	Quantity	Per	Each (£)	Total Line Value (£)
N57525 MULTIPANEL CLS HLK 1200 WHITE SNOW	2		106.406	212.81
N57522 MULTIPANEL CLS U/L 1200 WHITE SNOW	3		95.624	286.87
N36714 MULTIPANEL CLASSIC TYPE A INT CORNER WHT	3		11.781	35.34
N42408 MULTIPANEL HIGH GRAB ADHESIVE 290ML	5		4.911	24.55
N36716 MULTIPANEL CLASSIC TYPE C END CAP WHT	1		7.361	7.36
N36715 MULTIPANEL CLASSIC TYPE B EXT CORNER WHT	1		13.438	13.44
Quotation Total				£580.38
Product Description	Quantity	Per	Each (£)	Total Line Value (£)

PRICES CORRECT ONLY AS AT QUOTATION DATE SHOWN. Price as at INVOICE date may differ due to market fluctuations. Carriage charges may apply. Prices quoted include the cost of packaging and insurance etc. Prices quoted EXCLUDE VAT unless stated otherwise. Wolseley UK Conditions of Business apply at all times. To view Wolseley UK Terms and Conditions please visit <http://www.wolseley-terms.co.uk/>

Rena Luna stainless steel Towel Radiator 1200mm x 500mm from **JUST RADIATORS** 01772 346933  
Product Code RNS-LN5120  
Inc VAT Free delivery £218.00

## Notes for builder

1. Remove existing tiles, replace with new Redland Rosemary tiles to match existing up to the level of the bathroom sill.
2. The front door and window of main house is not to be removed until the new bathroom and hallway is built and secure.
3. Pipe work for radiator, shower, sink and toilet, to be taken from supplies under existing bathroom floor, copper pipe work is to be used and fully insulated through new roof space and chased into walls on drops, roof space fully insulated as to drawings.
4. New roof structure woodwork formed, any insect or water damaged woodwork to be replaced, all new wood treated. New felt under battens, hips and edging tiles mortared into place.
5. Fan, lights and under floor heating electrical supply taken from newly installed distribution box (certificate of compliance no: 25795144) to be run directly under floor space of main house using cable rods to pull cables, low voltage lighting and fan used in wet room.
6. Electrical work to be carried out by Part 'P' self certification scheme registered electrician and certificate of compliance sent to building control .
7. Existing protruding brickwork inside and outside remaining porch to be cut back flush before plastering, rendering etc.
8. Lining duct used to sleeve fan duct, 110mm soil pipe off cut?

## Building Regulations Plan Number

58690/FP/2020/35

**Conditions of full plans approval** The plans have been passed subject to the conditions which are listed below being met:

1. Details of the proposed background ventilation to the new front extension are to be provided prior to commencement.
2. There is to be a minimum of 270mm rockwool provided between and over the new crown roof to the front extension.
3. A minimum of 75mm PIR or 100mm Jablite is to be provided to the new ground floor slab
4. All electrical work controlled under Part P (Electrical Safety) must be designed, installed, inspected and tested by a person competent to do so.

*Under the requirements of the Building Regulations the person carrying out the work to which the building regulations relate is required to notify the Authority at certain stages during the execution of the work.*

## Front window

These prices are from Dunster House DIY Windows and Doors 01234 868628, they say 20-25 days delivery. But any supplier can be used provided the same design and specification are met.

Type: **w6**,  
Width: **700mm**,  
Height: **1150mm**,  
[Vert.: 360mm, 760mm]  
Window colour: **White**,  
External Cill Size: **150mm**,  
Window Board: **No**,  
Handle colour: **White**,  
Friction Stays: **Standard**,  
Shootbolt Locking: **FREE**,  
Trickle Vent/s: **Yes**,  
Decoration: **None**,  
Type of glass: **Autumn Leaf**,  
Fixing Pack: **Yes**,  
£219.74 inc VAT and delivery

## Side window

External & Internal colour, Door colour side: **External & Internal colour**, Door opening: **In, Hinged Left**, Door glass Decoration: **Cotswold**, Knocker: **Chrome Spy Hole**, Letter box: **White**, Handle: **White Handle**, Security: **Ingenious Duplex 4 hook, hookbolt and latch**, Door Cylinder: **APECS Diamond Grade Cylinder**, Frame (including side panel) colour: **White**, External Cill Size: **Document M Threshold**, Fixing Pack: **Yes**, £694.88 inc VAT and delivery

## Front door

Style: **site\_low**, Type: **Portrush**, Width: **900mm**, Height: **2100mm**, Door colour: **White**, Door colour side: **External & Internal colour**, Door opening: **In, Hinged Left**, Door glass Decoration: **Cotswold**, Knocker: **Chrome Spy Hole**, Letter box: **White**, Handle: **White Handle**, Security: **Ingenious Duplex 4 hook, hookbolt and latch**, Door Cylinder: **APECS Diamond Grade Cylinder**, Frame (including side panel) colour: **White**, External Cill Size: **Document M Threshold**, Fixing Pack: **Yes**, £1,129.12 Total for door and windows inc VAT and delivery

## Wet room door

1930s Style 4 panel white primed internal door  
Supplier is "Online door store 0208 158 6700  
78 inch x 30 inch £135 inc VAT and delivery

## Schedule of plans submitted

Drawing issue 3 2 of 2

Plan numbers M50 – received 14<sup>th</sup> Feb 2020

Plan number M52 – received 07 Feb 2020

Location plan – received 07 Feb 2020