

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|--|-------|--------------------------------------|----------------------|---|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|---|
| T001 | Not Tagged | Wild cherry x2 (<i>Prunus avium</i>) Norway maple x8 (<i>Acer platanoides</i>) Common lime x6 (<i>Tilia x vulgaris</i>) | Group | Trees: 16 Life Stage: Semi Mature | Owned by the estate. | Group of 16 trees adjacent to East boundary fence. Trees planted in curbed buffer strip behind the parking bays. The roots are starting to cause displacement to block paving parking bays. Two cherry trees have excessive ivy. some of the crowns are in minor contact with neighbouring buildings. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518488270529346,-0.4786308083750316 | Sever ivy on two Cherry trees, either end of the group. Timescale: 30-Jan-2025 (6 Months) |

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|---|-------|---|----------------------|--|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|---|
| T002 | Not Tagged | Common hawthorn (<i>Crataegus monogyna</i>) Common ash (<i>Fraxinus excelsior</i>) Weeping willow x2 (<i>Salix babylonica</i>) Wild cherry (<i>Prunus avium</i>) Sycamore x2 (<i>Acer pseudoplatanus</i>) | Group | Trees: 7 Life Stage: Mature | Owned by the estate. | A group of trees amongst dense vegetation and ivy. Crowns viewed behind vegetation look to have no ill health. A mixture of mature and semi mature trees. One trifurcated willow is separating from the base, two stems are resting on boundary fence. one prunus crown is in minor conflict with adjacent building. Significant deadwood overhanging seating area along Grand Union Canal from one mature willow in the south corner. | Fair | Fair | Fair | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51738268740151,-0.47937300495057983 | Mitigation Actions 1: Remove major deadwood from one weeping willow overhanging canal seating area. Timescale: 30-Jan-2025 (6 Months) Mitigation Actions 2: Coppice willow to ground level with Tag No.1228. Timescale: 30-Jan-2025 (6 Months) |
| T003 | 1216 | Scots pine (<i>Pinus sylvestris</i>) | Tree | Height (m): 11 - 15 Crown Radius (m): 3 DBH (mm): 370 Life Stage: Early Mature | Owned by the estate. | Tree growing in low hedging. Crown is in minor conflict with adjacent roof to the west. No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51778556479278,-0.47911860482967805 | |
| T004 | 1217 | Scots pine (<i>Pinus sylvestris</i>) | Tree | Height (m): 6 -10 Crown Radius (m): 3 DBH (mm): 360 Life Stage: Early Mature | Owned by the estate. | Low crown over a low target area. No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51803063882256,-0.47906605010366576 | |

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|--|------|--|----------------------|---|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|-----------------|
| T005 | 1218 | Common lime (<i>Tilia x vulgaris</i>) | Tree | Height (m): 8 Crown Radius (m): 3 DBH (mm): 225 Life Stage: Semi Mature | Owned by the estate. | In the middle of Eleagnus hedge, stem base not visible. No work required at the time of inspection. | Good | Good | Good | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518544705152365,-0.4798974288753607 | |
| T006 | 1219 | Common lime (<i>Tilia x vulgaris</i>) | Tree | Height (m): 6.5 Crown Radius (m): 2 DBH (mm): 190 Life Stage: Semi Mature | Owned by the estate. | In the middle of Eleagnus hedge, stem base not visible. No work required at the time of inspection. | Good | Good | Good | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51864116717925,-0.479673551870982 | |
| T007 | 1220 | Wild cherry (<i>Prunus avium</i>) | Tree | Height (m): 8 Crown Radius (m): 3 DBH (mm): 150-200 Life Stage: Semi Mature | Owned by the estate. | No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51879931727583,-0.47942210823195497 | |
| T008 | 1221 | Wild cherry (<i>Prunus avium</i>) | Tree | Height (m): 7 Crown Radius (m): 3 DBH (mm): 160 Life Stage: Semi Mature | Owned by the estate. | No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518796355882984,-0.4794988851994553 | |
| T009 | 1222 | Wild cherry (<i>Prunus avium</i>) | Tree | Height (m): 7 Crown Radius (m): 3 DBH (mm): 120 Life Stage: Young | Owned by the estate. | Excessive ivy in the crown. Ivy severed by surveyor. No work required at the time of inspection. | Good | Good | Good | Ivy / Vines | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518827509791336,-0.47954368185830853 | |
| T010 | 1223 | Scots pine (<i>Pinus sylvestris</i>) | Tree | Height (m): 9 Crown Radius (m): 3 DBH (mm): 295 Life Stage: Semi Mature | Owned by the estate. | Historic kink in lower stem at 1mH. Crown acroaching adjacent building. No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.5188893964105,-0.47962853300881053 | |

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|---|------|---|----------------------|---|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|--|
| T011 | 1224 | Scots pine (<i>Pinus sylvestris</i>) | Tree | Height (m): 6.5 Crown Radius (m): 2 DBH (mm): 110 Life Stage: Young | Owned by the estate. | Within dense low hedging. No work required at the time of inspection. | Good | Good | Good | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518720533072376,-0.4791020203215154 | |
| T012 | 1225 | Norway maple (<i>Acer platanoides</i>) | Tree | Height (m): 12 Crown Radius (m): 5 DBH (mm): 450 Life Stage: Mature | Owned by the estate. | Ivy recently severed at ground level, but Ivy still impedes inspection. Significant deadwood overhanging parking bays. | Fair | Fair | Fair | Ivy / Vines | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518702918015165,-0.47874213305288627 | Remove major deadwood. Timescale: 30-Jan-2025 (6 Months) |
| T013 | 1226 | Common ash (<i>Fraxinus excelsior</i>) | Tree | Height (m): 12 Crown Radius (m): 5 DBH (mm): 200 - 250 Life Stage: Semi Mature | Owned by the estate. | Historically bifurcated at 1mH, in more recent years one stem to the south has been removed. Crown affected by Ash dieback and dropped deadwood on vehicles below. Pests and Diseases: Ash Dieback Infection Level 3: 50% to 75% | Fair | Fair | Fair | None | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51861320678748,-0.47864740062630967 | Fell to ground level. Timescale: 30-Jul-2025 (1 Year) |

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|--|-------|---|---|--|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|--|
| T014 | Not Tagged | Mixed species (<i>Mixed species</i>) | Group | Trees: 8 Life Stage: Semi Mature | Owned by the estate. | Group adjacent to east boundary. Ash, Maple, Cherry, Hawthorn and Walnut. Multiple trees have restricted access to their base. Ash trees within the group have early stages of Ash dieback. Standing dead trees within the group in falling distance of the road. Low crowns overhang the adjacent road. | Fair | Fair | Fair | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518955271736736,-0.4790707078404238 | Mitigation Actions 1: Raise low crowns to 5mH. Timescale: 30-Jan-2025 (6 Months) Mitigation Actions 2: Remove standing dead trees or trees with dieback of more than 50%. Timescale: 30-Jan-2025 (6 Months) |
| T015 | Not Tagged | Common ash (<i>Fraxinus excelsior</i>) | Tree | Height (m): 12 Crown Radius (m): 7 DBH (mm): 550 - 600 Life Stage: Over Mature | Owned by the estate. Owned by 3rd party. | Mature tree in neighbouring land. Late stages of ash dieback. Striking distance to MITIE car park below. 3rd party need informing. Pests and Diseases: Ash Dieback Infection Level 4: 75% to 100% | Poor | Poor | Poor | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51970572175672,-0.4796577078793723 | Fell to ground level. Timescale: 30-Jan-2025 (6 Months) |
| T016 | Not Tagged | Mixed species (<i>Mixed species</i>) | Group | Life Stage: Semi Mature | Owned by 3rd party. | Group adjacent to north boundary fence owned by the neighbouring land. Ash, cherry and sycamore. Ash have early stages of Ash dieback. Significant deadwood over the parking bays from one cherry. | Varied | Varied | Varied | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.519486199926035,-0.48010001499802724 | Remove major deadwood overhanging parking bays. Timescale: 30-Jan-2025 (6 Months) |

| Tree ID | Tree Tag No | Species | Type | Measurements | Ownership | Survey Notes | Physiological Condition | Structural Condition | Overall Condition | Inspection Limitations | Inspected | Inspection Due | Google Maps | Recommendations |
|---------|-------------|--|-------|--|----------------------|--|-------------------------|----------------------|-------------------|------------------------|-------------|----------------|---|--|
| T017 | Not Tagged | Mixed species (Mixed species) | Group | Life Stage: Mature | Owned by the estate. | Group of trees adjacent to west boundary and the Grand Union canal. Limited access to the base of the trees. Crowns in minor conflict with adjacent buildings but have been pruned back in the last 5 years. Any trees with significant defects will be recorded separately. | Fair | Fair | Fair | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51873153981007,-0.48102033915721487 | |
| T018 | 1227 | Sycamore (<i>Acer pseudoplatanus</i>) | Tree | Height (m): 14 Crown Radius (m): 5 DBH (mm): 550 - 600 Life Stage: Mature | Owned by the estate. | Tree within group T017. One main stem removed leaving two. Minor delamination to lower North stem. Major deadwood overhanging canal footway. No access to the base of the tree. | Fair | Fair | Fair | Access | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51751479341157,-0.47949875343079296 | Remove major deadwood Timescale: 30-Jan-2025 (6 Months) |
| T019 | 1230 | Prunus (<i>Prunus sp.</i>) | Tree | Height (m): 6 -10 Crown Radius (m): 5 DBH (mm): 250 - 300 Life Stage: Over Mature | Owned by the estate. | Poor condition overhanging the canal footway. | Poor | Poor | Poor | Ivy / Vines | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.518831773448255,-0.4810667303796787 | Fell to ground level. Timescale: 30-Oct-2024 (3 Months) |
| T020 | 1229 | Prunus (<i>Prunus sp.</i>) | Tree | Height (m): 6 -10 Crown Radius (m): 5 DBH (mm): 250 - 300 Life Stage: Over Mature | Owned by the estate. | Poor condition overhanging the canal footway. | Fair | Poor | Poor | Ivy / Vines | 30-Jul-2024 | 30-Jul-2026 | https://www.google.com/maps/search/?api=1&query=51.51886593428035,-0.48110768066836396 | Fell to ground level. Timescale: 30-Jan-2025 (6 Months) |