



Product Information

Ibstock Code:	A2249A
Type:	Wirecut Extruded
Facing Description:	Smooth
Dry Brick Weight (kg):	2.4kg
Pack Quantity:	380
Packaging (standard):	Banded (Plastic)
Factory:	Lodge Lane
EPD:	

Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Vertically Perforated
Voids (%):	23-28
Compressive Strength (N/mm ²):	75
Active Soluble Salts:	S2
Water Absorption (% weight):	7
Durability:	F2~
Gross Dry Density (Sound Insulation) (Kg/m ³):	1650
Equivalent Thermal Conductivity "K" value 5% Exposed:	1.19
Initial Rate of Absorption (Suction Rate) (Kg/m ² /min):	0.1
EAN:	5.03634E+12