

PLANTING AND MAINTEANCE SCHEULE

**18 ST CATHARINES RD
RUISLIP
HA4 7RU**

DECEMBER 2023

Scope of Work:

Carry out planting and associated maintenance at 18 St Catharine's Rd as per the planting plan (Ref 18/SC/2711) and Schedule of Work

Planning Application Reference:

PP-10114983

Planting:

Northeast boundary

Plant 15no pot grown (60-90cm) *Prunus Laurocerosus* (Common Laurel) at 800mm centres. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm

Southwest boundary

Plant 4no pot grown (60-90cm) *Prunus Laurocerosus* (Common Laurel) inside boundary fence, positioned between trees. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm.

Plant 7no pot grown *Hypericum Hidcote* outside boundary fence at 400mm centres. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm.

Program:

Planting should ideally be completed November to February

Maintenance:

Plants will require watering for up to 24 months from planting dependent on weather.

An annual check will be made for a period of 5 years and any dead plants will be replaced.

Once established, the common laurel will require pruning to prevent it becoming too large, effectively forming a hedge.

4no *Prunus laurocerasus*
800mm Centres
Planting membrane
100mm depth mulch 900mm radius

15no *Prunus laurocerasus*
800mm Centres
Planting membrane
100mm depth mulch 400mm radius

7no *Hypericum hidcote*
500mm centres
Planting membrane
100mm depth mulch 400mm radius

Not to Scale

Drawing No: 18/SC/2711

Planting Scheme

18 St Catharines Rd

Date: 27/11/2023

Issue: 1

