

# PLANTING AND MAINTENANCE SCHEDULE

18 ST CATHARINES RD  
RUISLIP  
HA4 7RU

October 2024

**Scope of Work:**

Carry out planting and associated maintenance at 18 St Catharine's Rd as per the planting plan (Ref 18/SC/2711/2) and Schedule of Work

**Planning Application Reference:**

PP-10114983

**Planting:**

Northeast boundary

Plant 15no pot grown (60-90cm) *Fagus sylvatica* (Beech) at 800mm centres. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm. To be maintained and pruned to achieve a hedge.

Southwest boundary

Plant 4no pot grown (60-90cm) *Prunus Laurocerosus* (Common Laurel) inside boundary fence, positioned between trees. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm.

Plant 7no pot grown *Hypericum Hidcote* outside boundary fence at 400mm centres. Plant through landscaping membrane and apply mulch to a depth of 100mm at a radius of 400mm.

**Program:**

Planting should ideally be completed November to February.

**Maintenance:**

Plants will require watering for up to 24 months from planting dependent on weather.

An annual check will be made for a period of 5 years and any dead plants will be replaced.

Once established, the Beech will require pruning to form a hedge. Insufficient space and location to allow trees to mature.

4no *Prunus laurocerasus* —  
800mm Centres  
Planting membrane  
100mm depth mulch 900mm radius

15no *Fagus sylvatica*  
800mm Centres  
Planting membrane  
100mm depth mulch 400mm radius

## Planting Scheme

18 St Catharines Rd

Date: 08/10/2024

Issue: 2

Not to Scale

Drawing No: 18/SC/2711/

↑  
N

7no *Hypericum* hidcote  
500mm centres  
Planting membrane  
100mm depth mulch 400mm radius