



Key

Existing trees to be retained

Proposed trees

Existing trees to be removed

Proposed instant hedge planting

General ornamental planting across site

Proposed tree protection fencing (refer to arb report)

Wildflower turf incorporating meadow species. (Emorsgate EL1F seed mix to be used for sowing into existing grass lawns).

Proposed grass lawn

Proposed site footpaths

Resin bonded pedestrian path

Proposed terrace / patio area
Textured finish buff paving slab.

Proposed permeable block paving
Road, Pedestrian Crossing, Parking

Proposed tarmac road areas

Proposed tarmac pedestrian paths

Planting Schedule

All plants to be supplied from an HTA approved nursery and in accordance with the National Plant Specification

TREES	
Key	Species
AC	Acer campestre
ACS	Acer campestre 'Streetwise'
AL	Alnus cordata
AM	Amelanchier lamarkii
BU	Betula utilis jacquemontii
CB	Carpinus betulus
FS	Fagus sylvatica
MG	Magnolia grandiflora

INSTANT HEDGING
Instant hedge to be supplied in 1m lengths of single species, 1.5 - 1.8m height

Code	Species	Form	% Mix
PI	Prunus lusitana	In 1m long sections- troughs or field lifted as required	100%

WILDFLOWER GRASS SEEDS
Emorsgate EL1F Wildflowers for Lawns mix overspread existing lawn areas at site entrance.

Latin name	Common name
Galium verum	Lady's Bedstraw
Leontodon hispidus	Rough Hawkbit
Leucanthemum vulgare	Oxeye Daisy
Lotus corniculatus	Birdsfoot Trefoil
Primula veris	Cowslip
Prunella vulgaris	Selfheal
Ranunculus acris	Meadow Buttercup
Rumex acetosa	Common Sorrel
Trifolium pratense	Wild Red Clover

- ### Planting Notes
- 1) Do not scale directly from this drawing.
 - 2) This drawing is to be read in conjunction with all other relevant consultants drawing.
 - 3) All hatch patterns illustrated on this drawing are indicative only and do not represent the size of actual paving units.
 - 4) Please refer to arboricultural report for information relation to existing trees and woodland.
 - 5) Foundation design is to be approved by engineers in regards to existing and proposed trees locations next to building.
 - 6) Immediately prior to planting ALL TREES, TRANSPLANTS AND SHRUBS to be dipped in mycorrhizal inoculate.
 - 7) Emorsgate EL1F Mix Wildflowers for lawns to be supplied by Emorsgate seeds, Limes Farm Tilney All Saints Kings Lynn, Norfolk PE34 4RT. 01553 829028.

B	Amendments to tree planting and paving hatch	02-09-15	ML	BD
A	Amendments to material keying / surface specification, southwest entrance gate repositioned.	01-09-15	DAL	BD
Rev:		Date:	Drawn:	Checked:
Revisions:				
Project: Parkview Hillingdon				
Client: Hunters Architects				
Title: Landscape Strategy				
Drawing number: 15090.101				
Status: FOR INFORMATION				
Drawn By: DAL	Checked By: PH	Date: 27-08-15	Scale @ A1: 1:200	

Parkview, Hillingdon

Landscape Strategy

