



THE NEW STEELS FOR LOFT SHOULD NOT BE INSTALLED INSIDE EXISTING OR REMOVED CHIMNEY BRESTEXISTING FOUNDATIONS & LINTOLS TO BE CHECKED FOR ITS ADEQUACY.

THE ARRANGEMENT OF NEW STAIRCASE TO BE DETERMINED BY CONTRACTOR BEFORE INSTALLATION OF NEW STEELS FOR LOFT FLOOR. ANY SIGNIFICANT CHANGE TO BE NOTIFIED IMMEDIATELY.

IT IS THE RESPOSIBILITY OF CONTRACTOR TO TAKE ALL DIMENSIONS BEFORE OBTAINING ANY MATERIAL INCLUDING STEELS AND WOOD.ANY DISCREPANCIES TO BE NOTIFIED IMMEDIATELY.

PROJECT: 24 CHESTNUT CLOSE HAYES, UB3 1JG	NOTE: 01 IT IS THE RESPONSIBILITY OF OWNER OR BUILDER TO MAKE SURE THAT NO WORK COMMENCES BEFORE THE STRUCTURAL CALCULATION ARE APPROVED BY THE LOCAL AUTHORITY. ANY WORK BEFORE APPROVAL WILL BE SOLELY ON OWNER'S RESPONSIBILITY	NOTE: 02 ANY DIMENSIONS STATED ARE ONLY FOR THE PURPOSE OF STRUCTURAL ENGINEER TO CHECK CALCULATIONS. IT IS THE RESPONSIBILITY OF CONTRACTOR TO TAKE ALL DIMENSIONS ON SITE BEFORE ORDERING ANY MATERIAL	DATE: 111121	MARBLES ENGINEERING SERVICES
			SCALE: NTS	