



LBC Heather Facing Brick

[1 Review](#)**STATUS :** In stock**DELIVERY :** [Local Delivery](#) **SKU :** H001571**Inc VAT:** **£0.88**

For assistance, please call:
020 8362 8100



Product Description

Documents

Questions & Answers

The Heather facing brick is a reddish purple sand faced clay facing brick like the rest of the London brick "fletton" range. It was very widely used in and around London after the war in both domestic and commercial rebuilding.

Characteristics

- Coarse sand textured
- Frogged
- Size : 215x102.5x65mm
- Coverage: 60 bricks per m² in single skin application

Technical

Technical properties BS EN 771-1

Compressive strength : 25N/mm²

Water absorption : ≤23%

Durability : F1

Active soluble salts content : S2

Size tolerance * (/range) : T2 - R1

Brand	Lbc
Barcode	N/A
EDP code	Build153

Product Reviews

Number of reviews : 1

Average rating : 3 /5

[View the trust certificate](#)

K. John the 21/07/2017 3/5

Quite a few bricks chipped or broken

