


EXTERNAL FIRE ESCAPE STAIRCASE WITH DISABLED REFUGE SPACE.

DASHED LINE INDICATES EXISTING SITE LEVELS.

SITE LEVELS RAISED TO ACHIEVE 5% GRADIENT ACROSS MEMORIAL GARDEN.

Materials - Key to Codes

- 1 External Walls
Red facing brickwork.
- 2 External Walls
Painted render finish. Colour: Ivory.
- 3 Roof Covering
Red clay plain roof tiles.
- 4 External Doors
Steel doors and frames, powder coated internally and externally. Colour: Graphite Grey, RAL 7024 to 30% gloss finish.
- 5 Sectional Door
Delivery area insulated sectional door: 2600mm (W) x 2600mm (H). External colour: Graphite Grey, RAL 7024.
- 6 Dock Shelter
Model DSL, 3250mm x 3250mm x 500mm projection and 900mm head curtain, with galvanised steel collapsible linkarm frame. Front curtains polyester mono-filmant 3mm PVC coated to both sides. Colour: Black, with safety marker stripes.
- 7 Shopfront Glazing and Entrance Lobby
Structural aluminium glazing sections by Schueco. All glazing panels to be double-glazed, 8.8 / 16 / min 8mm glass unit. Laminated inner pane. Voids argon filled. Toughened outer pane with Sunguard SN70/SSHT on surface 2. Entrance pod, automatic doors, shopfront glazing and window profiles powder coated Graphite Grey, RAL 7024 on both faces, gloss finish.
- 8 Fencing
Close-boarded timber gate and fence. 2m height.



Client

Lidl Great Britain Ltd

Project

Lidl
Ickenham Road, Ruislip

Title

West Elevation as Proposed

Drawing Ref.

4478-0401

Revision

P06

Scale - unless otherwise stated

1:200

Status

S0

@ A3

Issued For

Preliminary



architects

The Old Steelyard, Poplar Lane
Sproughton, Ipswich, IP8 3HL
t.01473 689532
klh@klharchitects.com
www.klharchitects.com