



Quoins and stone details to be repaired by replacing stones and repairing stones where necessary

Remove vegetation

Cement repairs to cracks in rear wall to be raked out and repaired with lime mortar following the structural engineer's recommendations to stabilise the structure

Roof to be fully re-tiled with any original tiles to be reused on the south elevation

Stone arch to be propped and damaged stones to be removed or cut back for repairs and made good with lime mortar



Quoins to be repaired and stones replaced where necessary using matching bath stone and lime mortar

New gate fixings to be installed

bulge in corner including stone quoins and window frame to be taken down and rebuilt using original stones in same position

Vegetation to be cut back

movement in side wall and arch to be repaired by carefully taking down the stone arch and rebuilding it with the reclaimed stones or replacements where necessary. Brick arch to be retained as is.

<p>Generally:</p> <p>Bath stone colour and texture etc to match existing.</p> <p>Red hatch is where new bath stone facing is required.</p> <p>Rainwater Goods - all existing cast iron works to be retained in place unless full salvage is possible, if so all cast iron including pipes, hoppers and brackets works are to be prioritised on the south elevation.</p>			<p>Project:</p> <p>Gateway at Hillingdon Uxbridge Cemetery Uxbridge Road, UB10 0JF</p>		 <p>Colony Architects Ltd.</p> <p>The Wine Store, Brewery Court, Theale, Reading, RG7 5AJ</p> <p>+44 (0)118 380 0328</p> <p>hello@colonyarchitects.com</p> <p>colonyarchitects.com</p>		
	<p>Collaborating with:</p> <p>Total Construction & Hillingdon Council</p>		<p>Drawing Name:</p> <p>Proposed North Elevation</p>				
	<p>Job: 1048</p>		<p>Date: 12.2024</p>			<p>Status: planning</p>	
	<p>Drawing: 05-11</p>		<p>Drawn By: HS</p>			<p>Checked By: SH</p>	
	<p>Revision: P1</p>						
NOTES	1:50	01	02	03	04	05	06