



stone quoins have been lost where modern extension was added. to be repaired and new stones inserted to ensure a clean corner is reinstated.

Modern brick structure to be taken down and all evidence removed including lead flashing and cement wall plaster and made good with lime mortar

Thick cement flaunching to be removed and structural engineer to inspect behind, structural engineer stabilisation recommendations to be advised and repairs made in lime mortar

<p>Generally: Bath stone colour and texture etc to match existing. Red hatch is where new bath stone facing is required. Rainwater Goods - all existing cast iron works to be retained in place unless to be salvaged or possible, if so all cast iron works including pipes, hoppers and brackets are to be prioritised on the south elevation.</p>	<p>colony Collaborating with: Total Construction & Hillingdon Council Job: 1048 Drawing: 05-12 Revision: P Drawn By: SH Checked By: SS</p>	<p>Project: Gateway at Hillingdon Uxbridge Cemetery Uxbridge Road, UB10 0JF Drawing Name: Proposed South Elevation Date: 12.2024 Status: planning Drawn By: SS Checked By: SS</p>	<p>RIBA Chartered Practice Colony Architects Ltd. The Wine Store, Brewery Court, Theale, Reading, RG7 5AJ +44 (0)118 380 0328 hello@colonyarchitects.com colonyarchitects.com</p>
NOTES 1:50 01 02 03 04 05 06			