



Product Information

Ibstock Code:	4009
Type:	Stock
Facing Description:	Sandfaced
Dry Brick Weight (kg):	2.2kg
Pack Quantity:	500
Packaging (standard):	Banded (Plastic)
Factory:	Ashdown

Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T1 R1
Configuration:	Single Frog
Voids (%):	6-11
Compressive Strength (N/mm ²):	30
Active Soluble Salts:	S2
Water Absorption (% weight):	15
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m ³):	1550
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m ² /min):	Refer to Ibstock
EAN:	5036335024218