

Mr Sandeep Singh  
Shield Berks Ltd  
122-123 High Street  
Uxbridge  
UB8 1JT  
23

12<sup>th</sup> September

Ref: SB1209

Dear Sandeep,

Please find below the Specifications for Gate fabrication and Gate Automation at the above address:

**1. Gate Fabrication:**

Gate will be fabricated as per drawings provided with specifications below:

Posts – 100x100x4mm SHS

Frame – 40x40x4mm SHS

Diagonal Infills – 20x20mm Square bars.

**2. Gate Automation:**

Gate Automation will be Under Ground Motors

Qty 2 x 230 v Underground Motors for Swing gates of up to 3.5 m per leaf, with built-in adjustable opening and closing, stops.

Qty 2 x Foundation box in steel with cataphoresis treatment, Complete with unlocking lever, fixing bracket to the gate and screw for adjusting the limit switch point in the opening.

Qty 1 x Multifunction Control panel for swing gates with two Leaves, graphic alerts display, testing of safety circuits for CAT 2 safety Products and onboard radio programming.

Qty 2 x Release device with lever key.

Qty 1 x Plug-in radio frequency control card.

Qty 2 x Dual frequency 4 button rolling code transmitters (Black), 4,294,967,896 combinations.

Qty 1 x Tuned Antenna

Qty 2 x Pair of Outdoor Photocells - range 10m

Qty 2 x heavy duty Hinge guards.

Qty 3 x Wireless Resistive Safety edges

Qty 1 x Installation which includes cables, junctions' box, connectors.

I hope the above satisfies your query. Should you wish to amend the above or have any queries related to it, please contact us.

Kind Regards

Harry Singh