

Artemis Tree Services Ltd

West Hyde Nursery
Old Uxbridge Road
West Hyde
Rickmansworth
Herts WD3 9XY

T: 01895 821 623
E: office@artemistreeservices.com
W: www.artemistreeservices.com



All work shall be completed in line with BS3998:2010 -Recommendations for Tree Work where appropriate
Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

WORK ORDER

Client: Mrs Morgan 9 Green Lane Northwood HA6 2UX	Site address: 9 Green Lane Northwood HA6 2UX		
Our Ref: 28752	Date: 19th September 2023	Purchase Order No:	

Details of Work Required/Recommended

Priority A works as per survey 27649 recommendations

Tree numbers -

T11

Lime - Remove major deadwood
over 25mm diameter
and/or over 1m length.

Priority B works as per survey 27649 recommendations

Tree numbers -

T7 - Cedar -Remove major deadwood
over 25mm diameter
and/or over 1m length.

Remove broken/hung up
branches. Prune to give
around 2m clearance from
adjacent house by
removing 1.5m from 1x
lowest branch to south.

T8 - Beech - Remove major deadwood
over 25mm diameter
and/or over 1m length.

Prune 1x limb at around
8m to East back approx
4m to shape and rebalance
the crown.

T9 Oak - Remove major deadwood
over 25mm diameter
and/or over 1m length.

T10 - Lime Remove major deadwood

over 25mm diameter
and/or over 1m length.

Climber to inspect wound
at 10m to W for excessive
decay and provide further
management
recommendations if



Registered Office in England: Brandon House, First Floor, 90 The Broadway, Chesham, Buckinghamshire, HP5 1EG
Company No. 579 1625 | VAT No. 888 0779 56 @20%

Artemis Tree Services Ltd

West Hyde Nursery
Old Uxbridge Road
West Hyde
Rickmansworth
Herts WD3 9XY

T: 01895 821 623**E: office@artemistreeservices.com****W: www.artemistreeservices.com**

All work shall be completed in line with BS3998:2010 -Recommendations for Tree Work where appropriate
Artemis Tree Services Ltd will check all TPO and Conservation Area clearance if not already in place

required.

T15 Ash - Climber to inspect wound
at 4.5m to south for
excessive decay and
provide further
management
recommendations if
required.

T21 Plum reducing to 3m height to
reduce lever action and
stress on weakened stems.

Tree Number - T5

Tree Type - 2x stems of Holly (Ilex aquifolium)

Approx. Diameter at 1.5m - 20cm

Approx. Height - 7m

Location - Eastern side of driveway, see map

Service - Section dismantle

Work Required - Section dismantle tree to near ground level and leave the stumps in the ground.

Reason - As per clients wishes, trees appear sparse, potentially in decline.

Priority Code - C

All resulting brushwood and logs will be transported to our recycling depot awaiting transfer to Thetford Power Station to be used as bio-fuel (**unless otherwise stated in work description above**).

Priorities

U - Within 2 weeks (If necessary fencing off the hazard until work can be carried out)

A - Within 3 months B - Within 6 months C - Within 12 months ON - Owner's discretion

Tree Preservation Order/Conservation area status: **In progress.**



Registered Office in England: Brandon House, First Floor, 90 The Broadway, Chesham, Buckinghamshire, HP5 1EG
Company No. 579 1625 | VAT No. 888 0779 56 @20%