

Tree Survey Spreadsheet at Pocket Park - UKPNS EV Charging Project

No	Species	Height	Ø at 1.5m	Spread	Crown	Age	Condition and		Removal	ERC	BS	RPA
							NSEW	clearance	Recommendations			
T1	Horse Chestnut <i>Aesculus hippocastanum</i>	8	255	4/2/3/3	2mN	SM	Physiological Condition: Poor		Y	<10	U	3.06
							Structural Condition: Poor		Fell		B	
							Public Amenity Value: Low					
							Inspection Limitations: Dense vegetation and ivy up trunk					
							Tree leans 20° north over pavement					
							Recommend: Remove for works					
T2	Elm <i>Ulmus procera</i>	6	50+70	1/2/1/4	g/l	SM	Physiological Condition: Poor		N	<10	U	1.72
			115				Structural Condition: Poor					
							Public Amenity Value: Low					
							Inspection Limitations: None					
							m/s from g/l affected by canopy of T3 with canopy bias W					
T3	Oak <i>Quercus robur</i> Heathrow 30656400	22	1105	18.5Ø	4mN	M	Physiological Condition: Good		N	>40	A2	13.26
							Structural Condition: Good		RD		B	
							Public Amenity Value: High					
							Inspection Limitations: None					
							E side of canopy affected by T4. 1 dead limb @12mE to be removed as situated over footpath. Lifted to 4m with epicormic growth through base of canopy					
							Recommend: Remove dead branch					
T4	Horse Chestnut <i>Aesculus hippocastanum</i> Heathrow 30656401	16	1080	17.5Ø	5mE	M	Physiological Condition: Fair		N	>20	B2	12.96
							Structural Condition: Good					
							Public Amenity Value: Moderate					
							Inspection Limitations: None					
							Reduced leaf cover and tree. Horse chestnut leaf miner (Cameraria ohridella) infestation present					
T5	Oak <i>Quercus robur</i> Heathrow 30656402	22	1110	20.0Ø	8mS	M	Physiological Condition: Good		N	>40	A2	13.32
							Structural Condition: Good					
							Public Amenity Value: High					
							Inspection Limitations: None					
							Ivy up trunk - remove. Minor dieback across canopy					
							Previous surgery wounds well headed					
T6	Horse Chestnut <i>Aesculus hippocastanum</i>	9	275	8.0Ø	2.5mN	SM	Physiological Condition: Good		N	>40	A2	3.3
							Structural Condition: Good					
							Public Amenity Value: High					

Tree Survey Spreadsheet at Pocket Park - UKPNS EV Charging Project

Tree Survey Spreadsheet at Pocket Park - UKPNS EV Charging Project