



Motorcycle Locking Loop - Cast In



The VELOPA Motorcycle Locking Loop - Cast In

The Motorcycle Locking Loop - Cast In is ideal for securing motorcycles. The Loop is cast into the ground providing a very high level of security when used with the motorcyclists own locking chain. The lid is designed so it can be operated with gloves on and when not in use presents no trip hazard (with lid lowered).

The loop is fabricated from 20mm solid galvanised steel bar and is therefore extremely durable. The Motorcycle Locking Loop - Cast In is finished in galvanised mild steel making it ideal for use outside where it will retain it's looks for years.

Product Range

Order Code	Description	Weight
138 200 250	Motorcycle Locking Loop - Cast In	6.4kg

Product details

310mm Tall.
150mm x 150mm (Length x Width)
Lid Thickness 6mm, Body Thickness 4mm.
Fully galvanised mild steel.

Installation & use

Installation requires setting with concrete into a hole of at least 200mm x 200mm x 350mm (length x width x depth)
Allow 800-1,000mm between loops and a minimum of 450mm from any obstruction.
This product is guaranteed for 12 months (*if installed and used correctly*).



www.autopa.co.uk
+44 (0)1788 550556

AUTOPA Limited
Cottage Leap, Rugby, Warwickshire CV21 3XP

