

IBSTOCK FUNTON ORCHARD MIXTURE BRICK 65MM



Description	Specification
-------------	---------------

Type:	Stock sandfaced
Brand:	Ibstock
Range:	Funton
Colour:	Buff
Manufacturing Process:	Stock
Configuration:	11-Jun
Pack Quantity:	500
Water Absorption (%):	21
Applicable Standards:	BS EN771-1
Durability Rating:	F2
Strength (N per mm2):	12
Texture:	Sandfaced
Height:	65.0 mm
Width:	102.0 mm
Length:	215.0 mm
Weight:	2.1 kg



Images may vary slightly from actual products due to natural variation in colour and screen resolution.

 Share

Description

Technical Specification

Technical Specifications

Width (mm)	100
Length (mm)	200
Area (m²)	0.02
Joint Size (mm)	5
Depth (mm)	50
Colour	Brindle
Type	Smooth
AX Part Number	GM000062581
Pack Size	1
AreaCalcType	1
Manufacturer Part Number	10012

Rectangular Paving Blocks
60mm Block Paver Brindle

Part Number : 2309069

Size (mm) Finish
200 x 100 x 50 Brindle

1

Please enter
your location
for stock
availability.

Please enter your location for stock availability.

 Enter Location

Add To Favourites

Sandtoft⁺

Clay Tiles

Concrete Tiles

Koramic Tiles

Slate Range

Contact John for more information.

Sandtoft Bold Roll

A deep rolled interlocking profile that gives the roof a strongly undulating surface. The Bold Roll looks best in colours such as Terracotta Red and Rustic which accentuate the Mediterranean look.

Performs down to pitches of 22.5°

BRE Green Guide rating A+

Complies with the requirements of BS EN 490 & 491

Manufactured under quality management system BS EN 9001

Meets the performance requirements of BS 5534

Manufactured with 100% green electricity

Contains on average 15% recycled aggregates

Available Colours – Bold Roll



Rustic



Dark Grey



Terracotta Red

Technical Info:- Bold Roll

Minimum roof pitch	22.5°
Headlap (minimum)	75 mm
Headlap (maximum)	120 mm
Batten spacing at maximum gauge	345 mm
Batten spacing at minimum gauge	300 mm
Size of tile	420 x 334 mm
Covering capacity at maximum gauge	9.7 tiles per m ²
Cover width	300 mm
Profile depth	68 mm
Hanging length	394 mm
Weight as laid	47.5 kg per m ²
Weight per 1000	4.9 tonnes
Weight per tile	4.9 kg
Weight per pallet (including pallet/packaging)	1.0 tonnes
Quantity per pallet	210
Quantity per row/band	35
Quantity per mini pack	N/A
Quantity per layer	105
Mini packs per row	N/A
Battens per m ²	2.91 m
Batten size – up to 450 mm rafter centres	38 x 25 mm
Batten size – up to 600 mm rafter centres	50 x 25 mm
Nail size/type for tiles	80 x 3.75 mm aluminium ring shank clout head
Nail size/type for tile clips	55 x 3.35 mm aluminium ring shank clout head