



Material notes:

Windows and doors to the proposed extension shall be double glazed with white UPVC frames to match the existing property.

The external wall finishes of the extension shall be pebble dash cement render from DPC level up to eaves to match the existing property. Below DPC to be red semi-engineering brickwork. Flank wall facing no.21 shall be red facing brickwork.

Rainwater goods shall consist of black UPVC half round gutters and 75mm dia. downpipes.

Roof of extension to be pitched to min. 18deg with interlocking roof tiles to match existing main roof with 2no skylights.

Project:	Dwg No:	110-04	Client:	Title:	Rev:	Date:	Amendments to:	Scale:	1:50
19 Dartmouth Road Ruislip HA4 0DD			Jennifer Davidson	Proposed Rear Elevation				Format:	A3

Date: July 2020

Drawn by: HB