



PLANTING PLAN 08

Trees					
Number	Species	Common Name	Height	Girth	Specification
2	Acer campestre 'Elsrijk'	Field Maple 'Elsrijk'	400-450cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
2	Acer platanoides 'Emerald Queen'	Norway Maple 'Emerald Queen'	400-450cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
3	Liquidambar styraciflua 'Fastigiata'	Fastigiata Sweet Gum	450-500cm	18-20cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm
2	Liriodendron tulipifera 'Fastigiatum'	Fastigate Tulip Tree	450-500cm	16-18cm	Extra Heavy Standard: 3x: RB: Clear Stem min. 200cm

Shrubs					
Number	Species	Pot Size	Height	Specification	Density
15	Choisya ternata	5L	40-60cm	Bushy: 5 brks: C	3/m ²
15	Hebe pinguifolia 'Sutherlandii'	3L	20-30cm	Bushy: 5 brks: C	3/m ²
44	Lavandula angustifolia 'Alba'	5L	30-40cm	Bushy: 5 brks: C	4/m ²
67	Lonicera nitida 'May Green'	5L	30-40cm	Bushy: 8 brks: C	2/m ²
26	Photinia fraseri 'Red Robin'	10L	60-80cm	Branched: 7 brks: C	1/m ²
8	Rosmarinus officinalis 'Prostratus'	3L	20-30cm	Bushy: 4 brks: C	3/m ²

Herbaceous					
Number	Species	Pot Size	Specification	Density	
8	Achillea 'Terracotta'	2L	Full Pot: C	4/m ²	
14	Festuca glauca 'Elijah Blue'	2L	Full Pot: C	5/m ²	
32	Gaura lindheimeri	2L	Full Pot: C	4/m ²	
6	Kniphofia 'Firefly'	2L	Full Pot: C	3/m ²	
34	Salvia officinalis 'Tricolor'	5L	Bushy: 6 brks: C	3/m ²	
43	Thymus citriodorus 'Aureus'	3L	Full Pot: C	4/m ²	

Conifers					
Number	Species	Pot Size	Height	Specification	Density
147	Taxus baccata	10L	80-100cm	Leader & laterals: feathered to base	0.5Ctr

Grasses					
Number	Species	Specification	Density		
20	Stipa tenuissima	Full Pot: C	5/m ²		

PLANTING NOTES

- Plant material to conform to the National Plant Specification. All planting stock to originate from within the UK. Plant handling and planting operations to be in accordance with MTA 'Handling and Establishing Landscape Plants', Parts I-III.
- Topsoil to be fertile with maximum 35% clay content and 5% maximum organic content pts 8.7-5 and to be free of perennial weeds, weed seeds and contamination. Maximum stone content 20% (20mm+particle size), maximum size of stones 50mm in any direction. Existing topsoil to be ameliorated and/or screened if necessary to achieve this specification.
- Imported topsoil to be BS 3882: General Purpose Grade, from an approved source, and to accord with the above specification. All compost, mulches & soil conditioners to be peat-free. A minimum 25% of all vegetation to be reared in peat free compost.
- Bespoke growing medium for shrub/tree planting on podiums: EGR Lightweight Intensive Substrate (Ref: EGR LWGS) & EGR Intensive Subsoil (Ref: EGR ISS) by Eco Green Roofs (See Soft Details).
- Trees to be planted in pits (1200x1200x1200mm minimum size), backfilled with selected topsoil mixed with 20% peat free organic tree planting compost and 150g 'Sierablen Flora' slow release fertiliser. Base of pit to be broken up to 150mm depth, incorporating coarse sand or grit required for drainage. Soil beneath pit to be sterile water permeable subsoil.
- Extra Heavy Standard & Semi-mature trees to be supported by an approved deadman guying system.

PLANTING BEDS

- Planting beds to have a minimum depth of 450mm topsoil over 150mm broken up ground with all stones over 50mm removed. Soil conditioner: Sanitized and stabilised compost to BSI PAS 100. Apply 50mm depth even coverage and incorporate into topsoil during cultivation operations, to a minimum depth of 150mm. Compost to be Compost Association certified or from approved supplier conforming to this specification. If no local supplies are available an alternative organic peat free compost may be specified, subject to the CAs approval.
- Shrubs to be planted in pits 150mm wider and deeper than root spread (450mm minimum) backfilled with excavated topsoil/compost, mixed with 'Sierablen Flora' slow release fertiliser, quantity in accordance with manufacturer's recommendations.
- All planting beds and tree surrounds to be mulched with matured coniferous bark, with an even particle size between 15-6mm, to a minimum depth of 75mm over weed free soil after completion of all planting and watering operations. Mulch to be free of pests, diseases, fungi and weeds, and with no fines or dust. Mulch source and sample to be approved.
- All hedge planting to be in double staggered rows with 300mm between where applicable.
- All climbers to have a support frame added to assist with growth.

GRASS AREAS

- Grass areas are to have a minimum depth of 150mm topsoil brought to a fine uniform texture. Topsoil to be applied in layers, in areas where grass areas should be uniformly firm. Pre-seeding fertiliser, eg. British Seed Houses BSH2 to be applied prior to grass seeding in accordance with manufacturer's recommendations. Topsoil allowed to settle and sink below applying the grass seed and irregular areas re-filled with approved topsoil.

13. All grass areas to be rolled turf (Ref: Lownlaw medallion or similar approved).

MAINTENANCE NOTES

12. Trees - check guying system and adjust if necessary in summer and Winter. Prune out damaged branches or deadwood, cutting back so as not to affect branch collar. Progressively raise canopies of new trees to provide clearance for vehicles and pedestrians.

13. Shrubs - Weed control measures to continue until canopy of shrubs is closed. Weeds to be cleared by hand or by application of translocated herbicide, with inspections made regularly through the growing season. Prune back any badly damaged shrubs to sound growth. Cut back plants adjacent to paths and access ways where necessary, retaining a balanced shape. Clear litter and debris from planted areas and cut leggy growth hard back to promote bushy growth.

14. Watering - In periods of dry weather apply sufficient water to maintain healthy growth. Allow 10L/m² to planting beds and 50L/tree at each operation.

15. Re-firming - Ensure that all trees and shrubs are firmly bedded in the ground after strong winds, frost heave or other disturbances.

16. Grass Areas - Remove litter, twigs and debris prior to first cut of each Spring. Mow lawn areas regularly, cutting to a height of 35mm, allowing 16 cuts per season.

17. Protection/Restatement - Regularly inspect all planting and grassed areas, eg. once a month, for any pest damage or vandalism/damage caused by others. Any damaged to be reported to the Employer and rectified in the next available season by replacement planting or reseeding/turfing, and protective measures if required.

P1	ISSUED FOR PLANNING	13.02.23
REV	AMENDMENT	DATE

Client: **GREYSTAR**
The Global Leader in Rental Housing

Project: CROWN TRADING CENTRE, HAYES, LONDON

Title: PLANTING PLAN 08

Scale: 1: 100 | A1

Date	FEB 2023
Drawn	DT
Checked	PW

L.D.A
LANDSCAPE DESIGN ARCHITECTURE
17a Cannon Hill Rd
Croydon CR0 4TZ
Tel: 020 76 898666 Mob: 07977 453797
info@landscapearchitects.co.uk

Drawing no. L1115 - 3.1 - 2028

Job no. L1115 Revision: P1

