



Building Product Research, Without the Hassle.

Find, compare and price building products without wasting time on visiting, registering, & navigating multiple manufacturer websites, downloading countless technical documents for comparison, or waiting days for quotes.

[Sign Up](#) [Login](#)



Built to get you results quickly.



Products & information updated daily.



All the information you need in one place.



The largest product database in the UK.



Hoskins Brick Ltd
(<https://www.specifiedby.com/hoskins-brick-ltd>)

★★★★☆

Wickford Antique

[Ask a Question](#)

[Save to project](#)

[Compare](#)



One-Click Quote

Wickford Antique

by Hoskins Brick Ltd (<https://www.specifiedby.com/hoskins-brick-ltd>)

1

TECHNICAL INFORMATION

Units: Wickford Antique

Pack Size: 580

Brick Code: T32

[Request a Quote](#)

Compressive Strength: 20N/mm²

Water Absorption: 14% average

Tolerance Category: T2

Range Category: R1

Dimensional Stability: 0,04 mm/m

Bond Strength (mortar joints): 0,15 N/mm2 (0,30 N/mm2)

Active Soluble: S2

Net Dry Density: 1740 kg/m3 (D1)

Gross Dry Density: 1630 kg/m3 (D1)

Equivalent Thermal Conductivity: 0,45 W/m.k

Freeze/ Thaw resistance: F2

Reaction to Fire: Euroclass A1 (TOC<0,1%)

CE NRM EN 771-1 Cat. I- HD