





Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
								Priority	Inspect Freq (yrs)	Physiological Condition	Life Expectancy (yrs)
										Structural Condition	Retention Category
T1	Semi-Mature Box Elder Acer negundo.	4.5	2.5	23	2.5 3.5 4		Form: Multi-stemmed at 2m with an unbalanced crown. History: No evidence of significant pruning. Defects: In decline. 30% of canopy is dead.	Remove deadwood and monitor.		Very Low Poor Poor	Low <10 C -
	Moderate							1			
T2	Semi-Mature Norway Maple Acer platanoides.	4.5	2	20	3 3 3		Form: Single stemmed and vertical with a well-formed crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		High Good Good	Low 40+ C -
	n/a							3			
T3	Semi-Mature Norway Maple Acer platanoides.	4	2	19	2.5 2.5 2.5		Form: Single stemmed and vertical with a balanced crown. History: No evidence of significant pruning. Defects: Chlorotic foliage. Scattered dead twigs.	No action required.		Low Poor Fair	Low 10-20 C
	n/a							3			
T4	Semi-Mature Norway Maple Acer platanoides.	4.5	2	20	3 2.5 3		Form: Multi-stemmed at 2m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Fair Good	Low 40+ C
	n/a							3			
G5	Semi-Mature Norway Maple Acer platanoides.	av 4.5	av 2	av 20	av 3 3 each		Form: Four evenly spaced trees, all single stemmed and vertical with balanced crowns. History: No evidence of significant pruning. Defects: Significant deadwood to eastern most tree.	No action required.		Moderate Fair Good	Moderate 40+ B -
	n/a							3			
T6	Semi-Mature Norway Maple Acer platanoides.	4	2	18	2 2 2		Form: Single stemmed and vertical with with a sparse crown. History: No evidence of significant pruning. Defects: In decline. 25% of canopy is dead.	Monitor.		Very Low Poor Fair	Low <10 C -
	Moderate							1			
T7	Semi-Mature Norway Maple Acer platanoides.	4.5	2	22	3 3 3		Form: Multi-stemmed at 2.5m with a well-formed crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
	n/a							3			

Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m) 	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Retention Category
T8	Semi-Mature Box Elder Acer negundo.	4	2	21	2.5 2 2		Form: Multi-stemmed at 2m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C
								n/a	3		
T9	Semi-Mature Hornbeam Carpinus betulus.	5	1.5	10	1 1.5 0.5		Form: Single stemmed and vertical with with a sparse crown. History: No evidence of significant pruning. Defects: Significant squirrel damage - significant dead bark and tear wounds. Other: Poor specimen.	No action required.		Low Poor Poor	Low <10 C -
								n/a	3		
T10	Semi-Mature Box Elder Acer negundo.	4.5	1	19	2.5 3 3		Form: Multi-stemmed at 2m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Fair Fair	Low 20-40 C
								n/a	3		
T11	Semi-Mature Box Elder Acer negundo.	5	1	25	2.5 2 2		Form: Multi-stemmed at 1m with a slightly unbalanced crown. Defects: Almost dead.	Remove.		Very Low Very Poor Very Poor	Low <10 U
								Moderate	N/A		
T12	Semi-Mature Box Elder Acer negundo.	5	2	33	4.5 4 5		Form: Multi-stemmed at 2.5m with a well-formed crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Slightly chlorotic foliage.	No action required.		Moderate Good Good	Low 20-40 C +
								n/a	3		
T13	Young Box Elder Acer negundo.	3	2	6	1.5 1.5 1		Form: Multi-stemmed at 2m with a compact crown. History: No evidence of significant pruning. Defects: Very sparse canopy.	No action required.		Very Low Very Poor Poor	Low <10 C -
								n/a	1.5		
T14	Semi-Mature Box Elder Acer negundo.	5.5	2.5	26	4.5 4 3		Form: Multi-stemmed at 2m with a well-formed crown. History: Occasional pruning wounds due to crown lifting. Defects: No significant defects observed.	No action required.		Moderate Fair Good	Low 20-40 C +
								n/a	3		

Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m) 	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Retention Category
T15	Semi-Mature Norway Maple Acer platanoides.	5	2.5	18	2.5 3 2.5		Form: Single stemmed and vertical with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T16	Semi-Mature Norway Maple Acer platanoides.	5	2.5	20	2.5 3		Form: Multi-stemmed at 2.5m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T17	Semi-Mature Norway Maple Acer platanoides.	5.5	2.5	26	4 4 4		Form: Multi-stemmed at 2.5m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T18	Semi-Mature Norway Maple Acer platanoides.	7	2	24	3 5 4		Form: Multi-stemmed at 2.5m with a slightly unbalanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T19	Semi-Mature Norway Maple Acer platanoides.	7.5	2	31	4 5 4.5		Form: Multi-stemmed at 2.5m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T20	Semi-Mature Norway Maple Acer platanoides.	6	2	34	4 5 4		Form: Multi-stemmed at 2.5m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Low 40+ C +
								n/a	3		
T21	Semi-Mature Norway Maple Acer platanoides.	5	2	27	4.5 4		Form: Multi-stemmed at 2.5m with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Sparse canopy.	No action required.		Moderate Good Good	Low 40+ C
								n/a	3		

Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m) N W E S	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
										Physiological Condition	Life Expectancy (yrs)
								Priority	Inspect Freq (yrs)	Structural Condition	Retention Category
T22	Semi-Mature Italian Alder Alnus cordata.	8.5	1.5	14	2 3 2		Form: Single stemmed and vertical with a narrow, upright habit. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		High Good Good	Low 40+ C
								n/a	3		
G23	Semi-Mature Cherry Prunus sp.	av 5	av 1	av 18	av 3.5 3.5 3.5 each		Form: Two close growing specimens. History: No evidence of significant pruning. Defects: No significant defects observed. Other: Southmost has very poor form.	No action required.		Moderate Fair Fair	Low 20-40 C
								n/a	3		
T24	Semi-Mature Cherry Prunus sp.	5	2	20	3 3 4		Form: Single stemmed and vertical with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Fair Fair	Low 20-40 C
								n/a	3		
T25	Early-Mature Cherry Prunus sp.	8	2	33	5 6 4		Form: Single stemmed and vertical with a balanced crown. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Fair Fair	Low 20-40 C
								n/a	3		
G26	Semi-Mature Norway Maple Acer platanoides.	av 8	av 2.5	av 25	av 5 4 4 5 each		Form: Row of three, all single stemmed and vertical with balanced crowns. History: No evidence of significant pruning. Defects: No significant defects observed.	No action required.		Moderate Good Good	Moderate 40+ B
								n/a	3		