7. Recommended tree works.



Site map showing trees/groups with work priorities (orange or yellow labels).
Grey area indicates 20m buffer for ivy removal from tree bases.

Suggested works priority: Orange - within 3 months (by 20/08/2019)

Ref	Recommended Works
T6 ASL	Reduce stems back from Derwent Drive by up to 25% (up to 5m). Remove ivy from stem base(s) to 1.5m above ground level.
T7 ASL	Heavy Pollard to 7m height/spread. Remove ivy from stem base(s) to 1.5m above ground level.
T8 SyC	Clear Ashwood Care Centre building by 3m. Also clear branches from the adjacent Thorn from the Ashwood Care Centre building by 2m. Remove ivy from stem base(s) to 1.5m above ground level.
T9 ASL	Secondary crown lift over path (towards road) by 5m and reduce stem towards road by up to 25% (up to 4m)
T10 ASL	Secondary crown lift to 4m over path. Remove ivy from stem base(s) to 1.5m above ground level.
T11 SyC	Secondary crown lift to 4m over path.

620
1920
460
220
160
180

All arisings stacked in eco piles on site unless removed by

complete arboricultural service
Willow works, Unit 9, Inwood Business Park, Whitton Road, Hounslow, Middlesex TW3 2EB
Tel: 020 8577 8118 Fax: 020 8577 7200 Email: enquiries@thetreecompany.co.uk
The Tree Company (London) Limited Registered Office: 79 High Street, Teddington, Middlesex TW11 8HG Registered in England No. 3751722 Reg. VAT No. 564 0305 66



Site map showing trees/groups with work priorities (orange or yellow labels).
Grey area indicates 20m buffer for ivy removal from tree bases.

Suggested works priority: Yellow - within 12 months (by 20/05/2020)

Ref	Recommended Works	
T3 ASL	Remove ivy from stem base(s) to 1.5m above ground level.	~~160~~ 160
T12 ASL	As above.	~~180~~ 180
G1 Those on edge ASL	Remove ivy from stem base(s) to 1.5m above ground level in area 20m from Eastern site boundary (Derwent Drive).	~~640~~ 960
G2 ASL	As above.	~~320~~ 480
G3 ASL	As above.	~~420~~
G5 ASL	Remove ivy from stem base(s) to 1.5m above ground level in area 20m from Eastern site boundary (Ashwood Care Centre) and Southern site boundary (Uxbridge Road).	~~240~~ 280
G6 ASL	Remove ivy from stem base(s) to 1.5m above ground level in area 20m from Southern site boundary (Uxbridge Road).	~~240~~ 360
G7 ASL	As above.	~~320~~ 320

complete arboricultural service
Willow works, Unit 9, Inwood Business Park, Whitton Road, Hounslow, Middlesex TW3 2EB
Tel: 020 8577 8118 Fax: 020 8577 7200 Email: enquiries@thetreecompany.co.uk
The Tree Company (London) Limited Registered Office: 79 High Street, Teddington, Middlesex TW11 8HG Registered in England No. 3751722 Reg. VAT No. 564 0305 66