...etch plan BT3

...ayes Park, Hayes End Road, Uxbridge, London

...pproximate site boundary

Urgent: This work must be organised as a matter of high priority and carried out as soon as possible.

Normal: This work must be scheduled in as soon as practical, taking proper account of possible habitat restrictions and normal logistical delays, such as adverse weather and administrative workloads. 'Normal' means work to be completed within about one year of the inspection date as a standard default, unless there is reasonable justification for any delays.

T3

Group

Optional: These works are non-essential suggestions in the interests of good management, and are not necessary for safety reasons.

Barrell Drawing Ref: 16117-BT4

Provided Plan Refs: AGL153495

barrell TREE CONSULTANCY

Permission is granted to scale from this drawing for Local Authority Planning Approval purposes relating to tree protection measures only. Where applicable this drawing is to be read in conjunction with the arboricultural report. This drawing is the copyright of Barrell Tree Consultancy 2019. ©

This drawing to be reproduced in colour only.

www.barrelltreecare.co.uk

Tree schedule

Tree No	Species	Notes	Treeworks	Priority
T193	Sycamore	Significant decay activity on stem. Extensive bark necrosis, poor vigour and dieback	Remove	Urgent
T198	Cherry	Significant dieback. Main stem with significant deadwood and defective above main fork from 4m. No pruning options.	Remove	Normal
T299	Oak	Minor deadwood overhanging road	Remove deadwood	Normal
T352	Ash	Twin stem at 2m, leaning, poor, no long term retention potential	Fell	Normal
H1	Hornbeam	Overgrown hedge on old wall which is showing signs of cracking. No long term retention potential.	Manage as a hedge, or remove and replant further away from wall	Optional
G2	Leyland cypress	Poor quality line of trees along northern boundary. Dieback throughout.	Manage by selective removal, or fell entire line and replant	Optional
T12	Lime	New tree, staked and tied which is unnecessary	Remove stakes and ties	Optional
T13	Oak	New tree, staked and tied which is unnecessary	Remove stakes and ties	Optional

This schedule must be read in conjunction with BS 3998 and the report.

