

FOUL PIPE SCHEDULE									
Pipe Name	Diameter	Length	Slope	Material	Pipe Bed	Upstream Manhole	Upstream Invert	Downstream Manhole	Downstream Invert
F-1.00	100 mm	10.568 m	1:32.2	PVC	S or Z	F-1	41.628 m	F-2	41.300 m
F-1.01	100 mm	6.781 m	1:56.5	PVC	S or Z	F-2	41.300 m	F-3	41.180 m
F-1.02	100 mm	9.605 m	1:80.0	PVC	S or Z	F-3	41.180 m	F-4	41.060 m
F-1.03	100 mm	7.757 m	1:80.0	PVC	S or Z	F-4	41.060 m	TW 8101	40.963 m
F-2.00	100 mm	7.877 m	1:80.0	PVC	S or Z	F-5	41.411 m	F-6	41.313 m
F-2.01	100 mm	10.679 m	1:80.0	PVC	S or Z	F-6	41.313 m	F-3	41.180 m
SVP-1	100 mm	4.089 m	1:40.0	PVC	S or Z	SVP-1	41.730 m	F-1	41.628 m
SVP-2	100 mm	3.252 m	1:31.9	PVC	S or Z	SVP-2	41.730 m	F-1	41.628 m
SVP-3	100 mm	4.016 m	1:12.6	PVC	S or Z	SVP-3	41.730 m	F-5	41.411 m

SURFACE WATER PIPE SCHEDULE									
Pipe Name	Diameter	Length	Slope	Material	Pipe Bed	Upstream Manhole	Upstream Invert	Downstream Manhole	Downstream Invert
RWP-1	100 mm	1.492 m	1:100.0	PVC	S or Z	RWP-1	41.124 m	SW-7	41.109 m
RWP-2	100 mm	1.079 m	1:6.7	PVC	S or Z	RWP-2	41.099 m	SW-8	40.938 m
RWP-3	100 mm	1.275 m	1:100.0	PVC	S or Z	RWP-3	41.099 m	SW-1	41.086 m
RWP-4	100 mm	1.453 m	1:7.6	PVC	S or Z	RWP-4	41.099 m	SW-2	40.909 m
SW-1.00	150 mm	17.709 m	1:100.0	PVC	S or Z	SW-1	41.086 m	SW-2	40.909 m
SW-1.01	150 mm	6.977 m	1:100.0	PVC	S or Z	SW-2	40.909 m	SW-3	40.839 m
SW-1.02	150 mm	6.900 m	1:100.0	PVC	S or Z	SW-3	40.839 m	SW-4	40.770 m
SW-1.03	150 mm	1.315 m	1:100.0	PVC	S or Z	SW-4	40.133 m	Tank in	40.120 m
SW-1.04	150 mm	1.321 m	1:100.0	PVC	S or Z	Tank out	40.120 m	SW-5	40.107 m
SW-1.05	63 mm	1.867 m	-1:2.3	MDPE	Rising Main	SW-5	40.088 m	SW-6	40.914 m
SW-1.06	150 mm	5.408 m	1:100.0	PVC	S or Z	SW-6	40.914 m	TW 9106	40.860 m
SW-2.00	150 mm	17.137 m	1:100.0	PVC	S or Z	SW-7	41.109 m	SW-8	40.938 m
SW-2.01	150 mm	9.907 m	1:100.0	PVC	S or Z	SW-8	40.938 m	SW-3	40.839 m
Tank 1	2.000 m x 0.800 m	7.500 m	Horizontal	Cellular Crate	To Manufacturer's Specification	Tank in	40.120 m	Tank out	40.120 m

NOTES

LANMOR Consulting

Civil Engineers & Transport Planning

Thorogood House, 34 Tolworth Close, Surbiton, Surrey, KT6 7EW
Telephone: 0208 339 7899 Fax: 0208 339 7898
e-mail: info@lanmor.co.uk
www.lanmor.co.uk

7 Weadow Close

Proposed Drainage
Pipe
Schedules

DRAWN	RS	CHECKED	KBL	APPROVED	KBL
DATE	Apr 23	DATE	Apr 23	DATE	Apr 23
SCALE	1 : 100	PRJ No.	231628	SIZE	REV
DWG No.	231628/510/02			A1	