


Reference G = Group H = Hedge	Age & Species	Height (m)	Crown Ht (m)	Diameter (cm)	Crown Spread (m)	Scaled Tree Diagram (m)	Notes	Recommendations (Independent of any development proposals)		Vigour	Amenity Value
								Priority	Inspect Freq (yrs)	Physiological Condition	Life Expectancy (yrs)
										Structural Condition	Retention Category
T1	Early-Mature <b>Lawson Cypress</b> <i>Chamaecyparis lawsoniana.</i>	9.5	2	55	3.5		Position: Situated within the front garden of No. 175. Form: Single stemmed and vertical with a narrow, upright habit. History: Previously topped at 7m. Defects: <b>Half of upper canopy is dead.</b>		Remove dead wood and monitor.	Moderate	Moderate
										Poor	10-20
										Fair	<span>C</span>
T2	Mature <b>Blue Atlas Cedar</b> <i>Cedrus atlantica 'glauca'.</i>	18	2	65	9		Position: Adjacent hotel car park. Form: Single stemmed and vertical with a well-formed crown. History: No evidence of significant pruning. Defects: <b>No significant defects.</b> Other: Limited inspection, dimensions estimated.	No action required.	High	High	
										Good	40+
										Good	<span>A</span>
T3	Semi-Mature <b>Western Red Cedar</b> <i>Thuja plicata.</i>	13	2	54	4		Position: Hotel grounds (rear of). Form: Single stemmed and vertical with a narrow, upright habit. History: No evidence of significant pruning. Defects: <b>No significant defects.</b> Other: Breaking boundary fence.	No action required.	High	Low	
										Good	10-20
										Good	<span>C +</span>
T4	Semi-Mature <b>Western Red Cedar</b> <i>Thuja plicata.</i>	13	2	62	4		Position: Hotel grounds (rear of). Form: Single stemmed and vertical with a narrow, upright habit. History: No evidence of significant pruning. Defects: <b>No significant defects.</b> Other: Breaking boundary fence.	No action required.	High	Low	
										Good	10-20
										Good	<span>C +</span>
T5	Semi-Mature <b>Western Red Cedar</b> <i>Thuja plicata.</i>	12	2	59	4		Position: Hotel grounds (rear of). Form: Single stemmed and vertical with a narrow, upright habit. History: No evidence of significant pruning. Defects: <b>No significant defects.</b> Other: Planted within 1m of building corner.	No action required.	High	Low	
										Good	10-20
										Good	<span>C</span>
T6	Early-Mature <b>Western Red Cedar</b> <i>Thuja plicata.</i>	13	1.5	70	3		Form: Single stemmed and vertical with a narrow, upright habit. History: No evidence of significant pruning. Defects: <b>No significant defects.</b>	No action required.	High	Moderate	
										Good	40+
										Good	<span>B -</span>