



KEY

01. Brick Type 01 - light grey multi mix stretcher bond with light mortar colour, final brickwork type / colour TBC
02. Brick Type 02 - light grey multi mix stretcher bond with dark mortar colour, final brickwork type / colour TBC
03. Brick Type 03 - grey/black dark multi mix stretcher bond brickwork with light mortar colour-final brickwork type / colour TBC
04. Solider course brickwork detail
05. Hit and miss brick work wall detail
06. Projected header brickwork detail pattern
07. Brick window sill detail
08. Projecting horizontal concrete/GRC spandrel and window sill profile. (Colour TBC)
09. GRC window head panel. (Colour TBC)
- 10a. Powder coated metal balustrade. Vertical MS flat bars RAL 7021.
- 10b. Powder coated metal balustrade. Vertical MS flat bars RAL 7032.
11. 2no. PPC aluminium railings with solid panels to top of balcony wall to allow for planter box space (RAL. Colour 7021)
- 12a. Aluminium window system, colour to match railings (RAL.7021)
- 12b. Aluminium window system, colour to match railings (RAL.7032)
13. Aluminium door system colour to match windows.
- Doors set in 215mm brick reveal
14. Concrete/GRC coping to roof parapet
15. Obscured glazing to bike store.
16. PPC Aluminium Ventilated louvered doors to refuse /service stores.
17. Signage letter system powder coated (colour tbc)

**stock
wool**
The Pump House 19 Hooper Street
London E1 8BU 020 7264 8600
info@stockwool.co.uk

Client
Millington Road (HPH4) LLP
Project
HPH4 Millington Road, Hayes
Drawing
Block A -Courtyard West
Elevation Bay Study
Status
PLANNING
Scale 1:500A1
CAD File 3552_MillingMainModel PA Housing.pln
Date
Drawn
Checked
0 1000 2000mm
Project no_Drawing no Revision
3552_PL(40)102 P02

