



#### LEGEND (HARD WORKS)

- Bituminous macadam, black with Conservation Kerb 145mm (W) x 915mm (L) x 255mm (D)
- Addagrip resin bound gravel 'Summer Gold', 5mm
- Marshalls - Tegula Priora 'Harvest' concrete block permeable paving 60mm deep, 160 x 160, staggered pattern Charcon Flat Top edging 50mmW x 150mmD x 914mmL
- Bin S Bespoke Shelton Bin Shed, treated timber 3682mm x 4914mm x 2020mm h
- BS Bespoke bike store, fully enclosed timber, secure 4600mm l x 2040mm w x 2100mm h Cycle racks - 6No Sheffield Bike Loop Floor mounted H800 x W715mm
- M Sc Mobility Scooter parking
- Timber seating - Broxap 'Milano' with arm rests l 1800 x w 650 x h 900mm (or similar)
- Close Board fence - 1800mm high in total
- Timber gates, 1800mm high and 1200mm width
- Langfulton 'Rimini' black railings 1200mm height (or similar)
- Exterior Lights UK - Big Nails bollard post, 800mm high, 15w max fluorescent E27 (or similar)
- Areas of permeable asphalt or paving



Date	Reason for revisions	By
15.11.2024	New tree layout	JW
Client		
Simply UK		
Project:		
Proposed Care Home 81 bed unit, 18 Pield Heath Road, Uxbridge, UB8 3NF		
Drawing Title:		
Hard works		
Scale:	1:200@ A1	Date: Oct 2024
Drawing Number:	1313-06	Revision Number: A