

Shrubs and Perennials: Native = (n); wildlife friendly = (w); multi-stemmed (MS)					
Name	Pot Size	Height	Habit	Density per sqm	Number
Acorus variegatus (w)	2l	30-40cm	Evergreen perennial with two colour spikes of leaves 50cm	5	11
Anemone hepuchensis 'September Charm' (w)	2l	20-30cm	Japanese anemone - late summer pink flowers 60cm	7	60
Anemone hybrida 'Richard Ahrens' (w)	2l	20-30cm	Japanese anemone - late summer white flowers at 1.5m	7	30
Asplenium scolopendrium (w)	3l	40-60cm	(Harts Tongue Fern) Evergreen shade tolerant with dark leaves to 100cm	5	69
Blechnum spicant (n)	2l	20-30cm	Evergreen native fern 45cm	7	65
Chaenomeles speciosa 'Pink Lady' (w)	3l	60cm	Shade tolerant wall shrub with early pink spring flowers 90cm	3	7
Choisya ternata 'Aztec Pearl' (w)	2l	40-60cm	Deciduous purple leaved shrub with pale pink flowers summer/autumn up to 1.8m	3	5
Cistus x purpureus (w)	2l	40-60cm	Deciduous purple flowered shrub up 100cm	5	0
Cornus sanguinea (n)	3l	20-40cm	Winter red stems native plant	4	9
Cornus stolonifera 'Ratnams' (w)	3l	20-40cm	Winter yellow stems	4	0
Cylisus scoparius 'Boskoop Ruby' (w)	2l	30-40cm	Red flowers in summer up to 1.2m	4	0
Deutzia gracilis 'Nikko' (w)	3l	30-40cm	Deciduous shrub with white flowers in spring/summer up to 1m	5	24
Digitalis purpurea (n)	2l	20-40cm	Perennial native summer flowering spike purple flowers	7	84
Dryopteris filix-mas (n)	3l	30-40cm	Semi evergreen native 'Male' fern 1.2m	5	17
Euonymus fortunei 'Emerald Gaiety' (w)	2l	20-30cm	Variegated green and white evergreen 50 - 100cm	5	5
Fatsia japonica (w)	3l	30-40cm	Evergreen structural plant up to 1.5m	3	9
Fuchsia magellanica 'alba' (w)	2l	30-40cm	Deciduous shrub with pale pink flower heads through summer 1.2m	4	6
Geranium 'Johnson's Blue' (w)	2l	20-30cm	Summer flowers blue clump forming 50cm	7	42
Hebe 'Garden Beauty Blue' (w)	2l	20-30cm	Blue summer flowers evergreen 50cm	5	24
Hebe 'Garden Beauty White' (w)	2l	20-30cm	White summer flowers evergreen 50cm	5	39
Hydrangea macrophylla 'Fireworks' (w)	3l	40-60cm	Deciduous shrub with white summer flowers 1m	4	6
Liriope muscari (w)	2l	20-30cm	Evergreen narrow leaves with purple flowers in autumn up to 50cm (w)	7	42
Philomis tuberosa 'Amazone' (w)	2l	20-40cm	Pink summer flowers 90cm	5	12
Phormium cookianum 'Cream Delight' (w)	3l	20-40cm	Evergreen structural plant with cream and green variegation 1m	4	3
Potentilla fruticosa 'Abbotswood' (w)	2l	30-40cm	Deciduous shrub with white flowers through summer 100cm	5	8
Rosmarinus officinalis (w)	2l	20-30cm	Evergreen fragrant shrub with blue spring flowers up to 1m	5	0
Ruscus aculeatus (n)	3l	20-30cm	Evergreen native 75cm	3	15
Verben bonariensis (w)	2l	40-60cm	Herbaceous perennial with purple flowers in summer 2m	7	24

Planting beds 16sqm
Plant in in groups of three or five
15No Asplenium scolopendrium
15No Anemone x hybrida 'September Charm'
15No Blechnum spicant
15No Digitalis purpurea
15No Hebe 'Garden Beauty White'
9No Ruscus aculeatus

Planting bed 12sqm
Plant in in groups of three
12No Asplenium scolopendrium
21No Anemone x hybrida 'September Charm'
14No Blechnum spicant
5No Chaenomeles speciosa 'Pink Lady'
21No Digitalis purpurea
6No Hebe 'Garden Beauty White'
6No Ruscus aculeatus

1No Rosa 'The Generous Gardener'
1No Hedera colchica 'Sulphur Heart'

1No Rosa 'The Generous Gardener'

Planting bed 3sqm
Plant in in groups of three or six
5No Acorus variegatus
5No Dryopteris filix-mas
5No Euonymus fortunei 'Emerald Gaiety'
5No Potentilla fruticosa 'Abbotswood'

1No Betula pendula

Hedgerow 22m (5 plants, staggered rows per 1m)
110No Viburnum tinus

Planting bed 2sqm
Plant in in groups of three or six
3No Acorus variegatus
3No Dryopteris filix-mas
3No Euonymus fortunei 'Emerald Gaiety'
3No Potentilla fruticosa 'Abbotswood'

1No Carpinus betulus

Planting bed 7sqm
Plant in in groups of three and six
6No Anemone x hybrida 'Richard Ahrens'
6No Blechnum spicant
6No Dryopteris filix-mas
6No Fatsia japonica
6No Digitalis purpurea
6No Geranium 'Johnson's Blue'
6No Hebe 'Garden Beauty Blue'
6No Liriope muscari

Planting bed 7sqm
Plant in in groups of three and six
6No Asplenium scolopendrium
6No Anemone x hybrida 'September Charm'
6No Blechnum spicant
3No Choisia ternata 'Aztec Pearl'
6No Digitalis purpurea
6No Geranium 'Johnson's Blue'
6No Hebe 'Garden Beauty White'
6No Liriope muscari

1No Hedera colchica 'Sulphur Heart'
1No Clematis armandii 'Apple Blossom'

1No Hydrangea petiolaris

Planting bed 5sqm
Plant in in groups of three or six
3No Cornus sanguinea
6No Digitalis purpurea
6No Dryopteris filix-mas
6No Hebe 'Garden Beauty Blue'
6No Hebe 'Garden Beauty White'
3No Hydrangea macrophylla 'Fireworks'

Planting bed 5sqm
Plant in in groups of three and six
6No Blechnum spicant
6No Digitalis purpurea
6No Geranium 'Johnson's Blue'
6No Liriope muscari
6No Deutzia gracilis 'Nikko'

1No Betula pendula

Planting bed 7sqm
Plant in in groups of three and six
6No Asplenium scolopendrium
6No Anemone x hybrida 'September Charm'
6No Philomis tuberosa 'Amazone'
3No Cornus sanguinea
6No Fuchsia magellanica 'alba'
6No Digitalis purpurea
6No Geranium 'Johnson's Blue'
6No Liriope muscari

Planting bed 5sqm
Plant in in groups of three
12No Asplenium scolopendrium
12No Anemone x hybrida 'Richard Ahrens'
6No Liriope muscari
1No Chaenomeles speciosa 'Pink Lady'
6No Digitalis purpurea
3No Hebe 'Garden Beauty Blue'

1No Rosa 'Rambling Rector'

1No Clematis montana var. rubens 'Elizabeth'

1No Trachelospermum jasminoides

1No Fremontodendron 'California Glory'

1No Solanum cripen 'Glasnevin'

1No Clematis armandii 'Apple Blossom'

1No Rosa 'Rambling Rector'

1No Clematis 'Montana Alba'

1No Wisteria sinensis 'Blue Sapphire'

1No Rosa 'The Generous Gardener'

1No Liquidambar styraciflua 'Stella'

Planting bed 4sqm
Plant in in groups of three or six
6No Asplenium scolopendrium
3No Cornus sanguinea
6No Hebe 'Garden Beauty Blue'
6No Blechnum spicant
6No Geranium 'Johnson's Blue'
6No Liriope muscari
6No Deutzia gracilis 'Nikko'

Planting bed 4sqm
Plant in in groups of three and six
6No Blechnum spicant
6No Geranium 'Johnson's Blue'
6No Liriope muscari
6No Deutzia gracilis 'Nikko'

Climbers: Native = (n); wildlife friendly = (w); multi-stemmed (MS)					
Name	Pot Size	Height	Habit	Density per 1m	Number
Clematis 'Montana Alba' (w)	3l	30cm	Early clematis, white profuse flowers	1	1
Clematis montana var. rubens 'Elizabeth' (w)	3l	30cm	Early clematis, blue profuse flowers	1	1
Clematis armandii 'Apple Blossom' (w)	3l	60cm	Evergreen with early white fragrant flowers 8m	1	2
Fremontodendron 'California Glory' (w)	3l	60cm	Evergreen wall shrub with large yellow flowers through summer up to 8m	1	1
Hedera colchica 'Sulphur Heart' (w)	2l	60cm	Variegated large leafed ivy up to 8m	1	2
Hydrangea petiolaris (w)	3l	60cm	Deciduous self supporting climber with white flowers good in shade	1	1
Rosa 'The Generous Gardener' (w)	2l	60cm	Repeat flowering climbing rose 4m	1	2
Rosa 'Rambling Rector' (w)	2l	60cm	White fragrant rambling rose 7m	1	2
Solanum crispum 'Glasnevin' (w)	3l	60cm	Deciduous with blue summer flowers up to 8m	1	1
Trachelospermum jasminoides (w)	3l	40-60cm	Evergreen highly fragrant 8m	1	1
Wisteria sinensis 'Blue Sapphire' (w)	3l	40-60cm	Deciduous climber blue flower May - June highly fragrant 8m	1	1

Trees - Selected Standard: Native = (n); wildlife friendly = (w); multi-stemmed (MS); Container grown (CG)				
Name	Girth/ root stock	Root condition	Habit	Number
Betula pendula (n)	10-12cm	Root balled	Silver birch - native with a light crown and interesting pale bark, up to 20m	3
Carpinus betulus (n)	10-12cm	Root balled	Hornbeam - native tree with good Autumn colour 20m+	1
Liquidambar styraciflua 'Stella' (w)	10-12cm	Root balled	Liquidamber - bright autumn colour up to 12m	1
Prunus 'Victoria Plum' (w)	St. Julien 'A'	Bare rooted or 5l pot	Desert plum, self fertile	1
Pyrus 'Concorde' (w)	Quince 'A'	Bare rooted or 5l pot	Desert pear, self fertile	1
Malus 'Cox' (self fertile) (w)	M/M106	Root balled or CG	Desert apple, self fertile	1

Formal Hedgerow - 5 per linear metre in staggered rows (formal): Native = (n); wildlife friendly = (w); multi-stemmed (MS)					
Name	Size	Root condition	Habit	Density per 1sqm	
Viburnum tinus (w)	80cm	3l pot	Evergreen	5	110



The planting shall be carried out in the first planting (seeding) season following completion of the development (between December and March inclusive).

All plant stock, plant handling and planting to be undertaken in accordance with the following British Standard Specifications and Code of Practice:

- BS 3936:1992 Part 1 Nursery Stock - Specification for trees and shrubs;
- BS 3936:1998 Part 10 Nursery Stock - Specification for ground cover plants;
- BS 4428:1989 - Code of Practice for General Landscaping Operations (excluding hard surfaces);
- BS 8545:2014 Trees from Nursery to Independence in the Landscape;
- The Code of Practice for Plant Handling 2002 (Horticultural Trades Association).

LEGEND (SOFT WORKS)

Retained tree/hedge/shrubs

Select standard tree

Hedging

Shrubs and perennials

Rain gardens

Climber

Activity Lawn - Tillers Arena Turf available from Tillers Turf Ltd or equal approved - pre grown turf

Species Rich Lawn - Wildflower Turf Species Rich Lawn Turf (WFT-Species-Rich-26), or equal approved - pre grown turf

Notes
Plan to be read in conjunction with the engineer and landscape drawings.

No measurements to be scaled off drawing. Worked from figured dimensions only.

All dimensions shown on drawing are shown in millimetres unless otherwise stated.

All dimensions and levels to be checked on site. Landscape Architect to be notified immediately of any discrepancies prior to the commencement of works.



Date 23.10.2024	Reason for revisions Added rain gardens; removed path; added notes	By JW
Client Simply UK		
Project: Proposed Care Home, 18 Field Heath Road, Uxbridge, UBB 3NF		
Drawing Title: Soft works - North		
Scale: 1:100@ A0	Date: March 2022	
Drawing Number: 1313-01	Revision Number: C	