



NOTES:  
DO NOT SCALE FROM DRAWING  
NOT FOR CONSTRUCTION, FOR PLANNING  
PURPOSES ONLY

#### Hard Landscape Legend

Existing trees to be retained and protected during construction
Bitmac surface, colour grey. Laid in line with engineer's details
Bitmac surface with white painted road markings. In line with engineer's details
Bitmac surface footpath, colour beige, such as Natra-Tex Cotswold as supplied by Natraxes or similar. Laid in line with engineer's details
Concrete Block Omega Flow Paving, Brett 200x100x60mm in Burnt Oak (Bracken equivalent) or similar. Laid in a Herringbone pattern in line with engineer's details.
Residential Footpath/ Private patio: Melton Garden concrete paving slabs 450x450x50mm in Black Speck from Brett or similar. Laid in stretcher bond in line with engineer's details.
Library Footpath: Chaucer concrete paving slabs 450x450x50mm in Charcoal from Brett or similar. Laid in stretcher bond in line with engineer's details.
Concrete Blister Hazard Warning Paving, 450x450x50mm in Natural as supplied by Brett or similar. Laid in a stack bond pattern in line with engineer's details.
Wetpour EPDM safety surface in 3 colours in organic flowing shapes, Light Green, Dark Green and 50:50 Light +Dark Mix Colours as supplied by Soft Surfaces Ltd
Playground Safety Grass Mats 22mm thick as supplied by Grassmats Ltd and installed to manufacturers recommendations.

#### Edge Treatments

EF1	50x150mm Square edged path edging, laid flush unless otherwise stated.
HB2	British Standard Half Battered PCC Kerb
BN1	125x255mm, 6mm upstand: dropped kerbing for access
BN2	125x255mm, Flush Kerb laid with slight fall to channel. Kerb laid upside down where permitted as CS2 alternative
BN3	125x255mm, 50mm upstand

#### Boundary Treatments

Y1	Southwell Bow Top Vertical Black Railing. Railing height 2100mm. 1.4m height gates located as shown. Railings by Alpha Rail Ltd or similar, root fixed to railing design as shown within Architectural details. Including proposed access gate to recreation ground.
Y2	Play Area Railings, 1.8m height as supplied by Alpha Rail Ltd or similar to (BS EN 1176). Polyester powder coated black. 2.75m post centres with 12mm dia bars. With support legs as required, root fixed. Installed to engineers recommendations.
Y3	Outward opening self closing gate of different colour, 2004, Pure Orange.

Notes:  
Play equipment surfacing and structures to be installed

in line with BS EN1176 and BS EN1177 and to receive a post installation RPII accredited play equipment inspection prior to opening of facility. Play equipment to be installed in line with suppliers recommendations. As supplied from Jupiter (or similar).

Nottingham  
The Coach House  
2 North Road  
West Bridgford  
NG2 7NH  
Tel.: 0115 989 9859

Entrance to have additional signage outlining use of facility, exclusion of dogs and adults, unless accompanying a child, management responsibility and emergency contact details



Robinia Stepping Posts  
Product Code: 906110300R (FHS)  
Play Experiences:  
Balancing, coordination, jumping  
Age Range: 5-12  
No of users: 12



Talk Tubes  
Product Code: 9122541100 (FHS)  
Play Experiences:  
Communication, Team Work, Sensory  
Age Range: 2+  
No of users: 2



Fairy Carousel  
Product Code: JP175570  
Play Experiences:  
Spinning, Team work, Balance, Coordination  
Age Range: 3+  
No of users: 2



Goblins Climbing Frame  
Product Code: JP175550 (Lappset)  
Play Experiences:  
Fitness, Motor skills, Balance, Coordination  
Age Range: 6+  
No of users: 1

C	23.05.25	Substation Layout Update	KL
F	19.05.25	Substation Layout Update	KL
E	02.05.25	Client comments	KL
D	25.03.25	Layout update + coordination	KL
C	03.03.25	Client comments + coordination	KL
B	24.02.25	Lighting Update	KL
A	13.02.25	Layout update + client comments	KL
Rev		Details	Drawn

HEAD OFFICE  
Rodbourne Rail Business Centre, Grange Lane,  
Malmesbury, SN16 0ES  
Tel: 01666 825646

Unit 7, Codalming Business Centre, Woolsack Way,  
Godalming, GU7 1HP  
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,  
Eastleigh, SO50 9SX  
Tel: 02382 026300

email:  
mail@acdenv.co.uk

**ACD**  
ENVIRONMENTAL

HEAD OFFICE  
Rodbourne Rail Business Centre, Grange Lane,  
Malmesbury, SN16 0ES  
Tel: 01666 825646

Unit 7, Codalming Business Centre, Woolsack Way,  
Godalming, GU7 1HP  
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close,  
Eastleigh, SO50 9SX  
Tel: 02382 026300

email:  
mail@acdenv.co.uk

**bugler**  
DEVELOPMENTS

scheme: Otterfield Road,  
Viewsley

client: Bugler Developments

drawing: Hard Landscape Proposals

date: October 2024

scale: 1:200@A1

drawn: BUC24699-12

checked: JC

Copyright of ACD Environmental Ltd. All rights reserved in  
Chapter IV of the Copyright, Designs and Patents Act 1988  
have been generally asserted. 2011. Copyright of this plan  
remains with ACD until all fees have been paid in full.