

Infrastruct CS Ltd		Page 1
The Stables High Cogges, Witney Oxfordshire, OX29 6UN		
Date 24/03/2026 15:57 File	Designed by Tim.Trotman Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	20.600	Add Flow / Climate Change (%)	0
Ratio R	0.437	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.126	4-8	0.051

Total Area Contributing (ha) = 0.177

Total Pipe Volume (m³) = 3.855

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	9.000	0.113	80.0	0.011	5.00	0.0	0.600	o	100	Pipe/Conduit	
1.001	10.000	0.125	80.0	0.006	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.002	10.000	0.125	80.0	0.003	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.003	9.500	0.119	80.0	0.013	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.004	15.500	0.194	80.0	0.015	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.17	30.645	0.011	0.0	0.0	0.0	0.86	6.8	1.5
1.001	50.00	5.32	30.483	0.017	0.0	0.0	0.0	1.12	19.9	2.3
1.002	50.00	5.47	30.358	0.020	0.0	0.0	0.0	1.12	19.9	2.7
1.003	50.00	5.61	30.233	0.033	0.0	0.0	0.0	1.12	19.9	4.5
1.004	50.00	5.84	30.114	0.048	0.0	0.0	0.0	1.12	19.9	6.5

Infrastruct CS Ltd

The Stables
High Cogges, Witney
Oxfordshire, OX29 6UN

Date 24/03/2026 15:57
File

Innovyze

Page 2



Designed by Tim.Trotman
Checked by

Network 2020.1.3

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
2.000	21.500	0.215	100.0	0.027	5.00	0.0	0.600	o	150	Pipe/Conduit	
2.001	20.000	0.123	162.0	0.024	0.00	0.0	0.600	o	225	Pipe/Conduit	
2.002	3.000	0.015	200.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.005	11.500	0.058	200.0	0.025	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.006	9.500	0.048	200.0	0.012	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.007	2.000	0.010	200.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.008	10.000	0.020	500.0	0.012	0.00	0.0	0.600	o	225	Pipe/Conduit	
1.009	2.700	0.027	100.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
3.000	10.600	0.177	60.0	0.008	5.00	0.0	0.600	o	100	Pipe/Conduit	
3.001	6.500	0.325	20.0	0.021	0.00	0.0	0.600	o	100	Pipe/Conduit	
1.010	8.000	0.080	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
2.000	50.00	5.36	30.273	0.027	0.0	0.0	0.0	1.00	17.8	3.7
2.001	50.00	5.68	29.983	0.051	0.0	0.0	0.0	1.02	40.7	6.9
2.002	50.00	5.74	29.860	0.051	0.0	0.0	0.0	0.92	36.6	6.9
1.005	50.00	6.05	29.845	0.124	0.0	0.0	0.0	0.92	36.6	16.8
1.006	50.00	6.22	29.787	0.136	0.0	0.0	0.0	0.92	36.6	18.4
1.007	50.00	6.26	29.740	0.136	0.0	0.0	0.0	0.92	36.6	18.4
1.008	50.00	6.55	29.730	0.148	0.0	0.0	0.0	0.58	23.0	20.0
1.009	50.00	6.58	29.710	0.148	0.0	0.0	0.0	1.31	52.0	20.0
3.000	50.00	5.18	30.184	0.008	0.0	0.0	0.0	1.00	7.8	1.1
3.001	50.00	5.24	30.007	0.029	0.0	0.0	0.0	1.73	13.6	3.9
1.010	50.00	6.71	0.000	0.177	0.0	0.0	0.0	1.00	17.8«	24.0

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.010		31.390	-0.080	0.000	0	0

©1982-2020 Innovyze

Infrastruct CS Ltd		Page 3																																																								
The Stables High Cogges, Witney Oxfordshire, OX29 6UN																																																										
Date 24/03/2026 15:57 File	Designed by Tim.Trotman Checked by																																																									
Innovyze Network 2020.1.3																																																										
<u>Simulation Criteria for Storm</u> <table> <tr> <td>Volumetric Runoff Coeff</td> <td>0.750</td> <td>Additional Flow - % of Total Flow</td> <td>0.000</td> </tr> <tr> <td>Areal Reduction Factor</td> <td>1.000</td> <td>MADD Factor * 10m³/ha Storage</td> <td>2.000</td> </tr> <tr> <td>Hot Start (mins)</td> <td>0</td> <td>Inlet Coefficient</td> <td>0.800</td> </tr> <tr> <td>Hot Start Level (mm)</td> <td>0</td> <td>Flow per Person per Day (l/per/day)</td> <td>0.000</td> </tr> <tr> <td>Manhole Headloss Coeff (Global)</td> <td>0.500</td> <td>Run Time (mins)</td> <td>60</td> </tr> <tr> <td>Foul Sewage per hectare (l/s)</td> <td>0.000</td> <td>Output Interval (mins)</td> <td>1</td> </tr> <tr> <td colspan="2">Number of Input Hydrographs</td> <td>0</td> <td>Number of Storage Structures</td> </tr> <tr> <td colspan="2">Number of Online Controls</td> <td>1</td> <td>Number of Time/Area Diagrams</td> </tr> <tr> <td colspan="2">Number of Offline Controls</td> <td>0</td> <td>Number of Real Time Controls</td> </tr> </table> <u>Synthetic Rainfall Details</u> <table> <tr> <td>Rainfall Model</td> <td>FSR</td> <td>Profile Type</td> <td>Summer</td> </tr> <tr> <td>Return Period (years)</td> <td>2</td> <td>Cv (Summer)</td> <td>0.750</td> </tr> <tr> <td>Region</td> <td>England and Wales</td> <td>Cv (Winter)</td> <td>0.840</td> </tr> <tr> <td>M5-60 (mm)</td> <td>20.600</td> <td>Storm Duration (mins)</td> <td>30</td> </tr> <tr> <td>Ratio R</td> <td>0.437</td> <td></td> <td></td> </tr> </table>			Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000	Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	2.000	Hot Start (mins)	0	Inlet Coefficient	0.800	Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000	Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60	Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1	Number of Input Hydrographs		0	Number of Storage Structures	Number of Online Controls		1	Number of Time/Area Diagrams	Number of Offline Controls		0	Number of Real Time Controls	Rainfall Model	FSR	Profile Type	Summer	Return Period (years)	2	Cv (Summer)	0.750	Region	England and Wales	Cv (Winter)	0.840	M5-60 (mm)	20.600	Storm Duration (mins)	30	Ratio R	0.437		
Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000																																																							
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	2.000																																																							
Hot Start (mins)	0	Inlet Coefficient	0.800																																																							
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000																																																							
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60																																																							
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1																																																							
Number of Input Hydrographs		0	Number of Storage Structures																																																							
Number of Online Controls		1	Number of Time/Area Diagrams																																																							
Number of Offline Controls		0	Number of Real Time Controls																																																							
Rainfall Model	FSR	Profile Type	Summer																																																							
Return Period (years)	2	Cv (Summer)	0.750																																																							
Region	England and Wales	Cv (Winter)	0.840																																																							
M5-60 (mm)	20.600	Storm Duration (mins)	30																																																							
Ratio R	0.437																																																									
©1982-2020 Innovyze																																																										

Infrastruct CS Ltd		Page 4
The Stables High Cogges, Witney Oxfordshire, OX29 6UN		
Date 24/03/2026 15:57 File	Designed by Tim.Trotman Checked by	
Innovyze	Network 2020.1.3	

Online Controls for Storm

Hydro-Brake® Optimum Manhole: 16, DS/PN: 1.010, Volume (m³): 35.6

Unit Reference	MD-SHE-0078-2600-0900-2600
Design Head (m)	0.900
Design Flow (l/s)	2.6
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	78
Invert Level (m)	29.682
Minimum Outlet Pipe Diameter (mm)	100
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.900	2.6
Flush-Flo™	0.271	2.6
Kick-Flo®	0.569	2.1
Mean Flow over Head Range	-	2.3

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	2.2	1.200	3.0	3.000	4.5	7.000	6.8
0.200	2.6	1.400	3.2	3.500	4.9	7.500	7.0
0.300	2.6	1.600	3.4	4.000	5.2	8.000	7.2
0.400	2.5	1.800	3.6	4.500	5.5	8.500	7.4
0.500	2.4	2.000	3.8	5.000	5.8	9.000	7.6
0.600	2.2	2.200	3.9	5.500	6.0	9.500	7.8
0.800	2.5	2.400	4.1	6.000	6.3		
1.000	2.7	2.600	4.2	6.500	6.5		

Infrastruct CS Ltd		Page 5
The Stables High Cogges, Witney Oxfordshire, OX29 6UN		
Date 24/03/2026 15:57 File	Designed by Tim.Trotman Checked by	
Innovyze Network 2020.1.3		
<		

Infrastruct CS Ltd

Page 6

The Stables

High Cogges, Witney

Oxfordshire, OX29 6UN

Date 24/03/2026 15:57

Designed by Tim.Trotman

File

Checked by

Innovyze

Network 2020.1.3

Micro Drainage

Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000

Additional Flow - % of Total Flow 0.000

Hot Start (mins) 0

MADD Factor * 10m³/ha Storage 2.000

Hot Start Level (mm) 0

Inlet Coeffiecient 0.800

Manhole Headloss Coeff (Global) 0.500

Flow per Person per Day (l/per/day) 0.000

Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0

Number of Storage Structures 2

Number of Online Controls 1

Number of Time/Area Diagrams 0

Number of Offline Controls 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR

Ratio R 0.437

Region England and Wales Cv (Summer) 0.750

M5-60 (mm) 20.600

Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

Analysis Timestep 2.5

Second Increment (Extended)

DTS Status ON

DVD Status ON

Inertia Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years) 30

Climate Change (%) 0

US/MH

PN

Name

Storm

Return Period

Climate Change

First (X) Surcharge

First (Y) Flood

First (Z) Overflow

Overflow Act.

Water Level (m)

1.000

1

15 Winter

30

+0%

30.704

1.001

2

15 Winter

30

+0%

30.545

1.002

3

15 Winter

30

+0%

30.426

1.003

4

15 Winter

30

+0%

30.326

1.004

5

15 Winter

30

+0%

30.260

2.000

6

15 Winter

30

+0%

30.356

2.001

7

15 Winter

30

+0%

30.098

2.002

8

30 Winter

30

+0%

30.003

1.005

9

15 Winter

30

+0%

30/15 Summer

30.087

1.006

10

15 Winter

30

+0%

30/15 Summer

30.061

1.007

11

15 Summer

30

+0%

30/15 Summer

30.009

1.008

12

15 Winter

30

+0%

30/15 Summer

29.960

1.009

13

360 Winter

30

+0%

29.922

3.000

14

15 Winter

30

+0%

30.228

3.001

15

15 Winter

30

+0%

30.082

1.010

16

360 Winter

30

+0%

30/15 Summer

29.934

©1982-2020

Innovyze

