



<p>NOTES: DO NOT SCALE FROM DRAWING NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY</p> <p>Hard Landscape Legend</p> <ul style="list-style-type: none"> Existing trees to be retained and protected during construction Bitmac surface, colour grey. Laid in line with engineer's details Bitmac surface with white painted road markings. In line with engineer's details Bitmac surface footpath, colour beige, such as NatraTex Cotswold as supplied by Natratrex or similar. Laid in line with engineer's details Concrete Block Omega Flow Paving, Brett 200x100x60mm in Burnt Oak (Bracken equivalent) or similar. Laid in a Herringbone pattern in line with engineer's details Residential Footpath/ Private patio: Melton Garden concrete paving slabs 450x450x50mm in Black Speck from Brett or similar. Laid in stretcher bond in line with engineer's details. Library Footpath: Chaucer concrete paving slabs 450x450x50mm in Charcoal from Brett or similar. Laid in stretcher bond in line with engineer's details. Concrete Blister Hazard Warning Paving, 450x450x50mm in Natural as supplied by Brett or similar. Laid in a stack bond pattern in line with engineer's details. Wetpour EPDM safety surface in 3 colours in organic flowing shapes, Light Green, Dark Green and 50:50 Light +Dark Mix Colours as supplied by Soft Surfaces Ltd Playground Safety Grass Mats 22mm thick as supplied by Grassmats Ltd and installed to manufacturers recommendations. <p>Edge Treatments</p> <ul style="list-style-type: none"> EF1: 50x150mm Square edged path edging, laid flush unless otherwise stated. HB2: British Standard Half Battered PCC Kerb BN1: 125x255mm, 6mm Upstand: dropped kerbing for access BN2: 125x255mm, Flush Kerb laid with slight fall to channel. Kerb laid upside down where permitted as CS2 alternative BN3: 125x255mm, 50mm upstand <p>Lighting Legend</p> <ul style="list-style-type: none"> Y1: City RLB T3 - CTRB2307NWB Y2: City RLB T4 - CTRB23074NWB Y3: City RL T4 - CTRT4330NWB N: Explorer - EPR480ANW City WL - CWL90T2NWB X1: City WL T4 - CWL90T4NWB X2: City WL T4 - CWL280T2NWB X3: City WL T4 - CWL280T2NWB X4: City WL T4 - CWL280T2NWB Existing <p>Refer to the lighting report and the latest revision of detailed lighting proposals, drawing ref 21202 - Otterfield Road, West Drayton - External, produced by Tamlite Lighting, for further detail</p> <p>Boundary Treatments</p> <ul style="list-style-type: none"> Southwell Bow Top Vertical Black Railing. Railing height 2100mm. 1.4m height gates located as shown. Railings by Alpha Rail Ltd or similar, root fixed to railing design as shown within Architectural details. Including proposed access gate to recreation ground. Play Area Railings, 1.8m height as supplied by Alpha Rail Ltd or similar to (BS EN 1176). Polyester powder coated black. 2.75m post centres with 12mm dia bars. With support legs as required, root fixed. Installed to engineers recommendations. Outward opening self closing gate of different colour, 2004, Pure Orange. <p>Street Furniture</p> <ul style="list-style-type: none"> Arca Steel Square Litter Bin 0.55x0.55x1.04m as supplied Boston 3 person Seat Length 1.9m, width 605mm, steel frame a wooden slats. Product Code BOS B6, as supplied by Furnitures, or similar. RAL plastic coating 7001 Grey Passive EV Parking Space and Active EV Parking Space (20% of all spaces) 	<p>NOTES: DO NOT SCALE FROM DRAWING NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY</p> <p>Play Equipment Legend</p> <ul style="list-style-type: none"> Robinia Stepping Posts Product Code: 906110300R (FHS) Play Experiences: Balancing, coordination, jumping Age Range: 5-12 No of users: 12 Talk Tubes Product Code: 912254110 (FHS) Play Experiences: Communication, Team Work, Sensory Age Range: 2+ No of users: 2 Fairy Carousel Product Code: JP175570 Play Experiences: Spinning, Team work, Balance, Coordination Age Range: 3+ No of users: 2 Goblins Climbing Frame Product Code: JP175550 (Lappset) Play Experiences: Fitness, Motor skills, Balance, Coordination Age Range: 6+ No of users: 1 <p>Notes: Play equipment surfacing and structures to be installed in line with BS EN1176 and BS EN1177 and to receive a post installation RPII accredited play equipment inspection prior to opening of facility. Play equipment to be installed in line with suppliers recommendations. As supplied from Jupiter (or similar).</p> <p>Nottingham The Coach House 2 North Road West Bridgford NG2 7NH Tel.: 0115 989 9859</p> <p>Entrance to have additional signage outlining use of facility, exclusion of dogs and adults, unless accompanying a child, management responsibility and emergency contact details</p> <p>H 24.07.25 Layout update ZZ G 23.05.25 Substation Layout Update KL F 19.05.25 Substation Layout Update KL Rev Date Details Drawn</p> <p>ACD ENVIRONMENTAL HEAD OFFICE Rodbourne Rail Business Centre, Grange Lane, Malmesbury, SN16 0ES Tel: 01666 825646 Unit 7, Codalming Business Centre, Woolsack Way, Godalming, GU7 1HP Tel: 01483 425714 Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX Tel: 02382 026300 email: mail@acdenv.co.uk</p> <p>bugler DEVELOPMENTS scheme: Otterfield Road, Viewley client: Bugler Developments drawing: Hard Landscape Proposals date: October 2024 scale: 1:200@A1 drawing no: BUC24699-12 drawn: KL checked: JC</p> <p>Copyright of ACD Environmental Ltd. All rights reserved in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.</p>
--	---