SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTES:
DO NOT SCALE FROM DRAWING
NOT FOR CONSTRUCTION, FOR PLANNING PURPOSES ONLY

Legend

- Existing trees to be retained and protected during construction
- Proposed native tree planting within soft landscape. See tree pit detail below.
- Existing grassland areas to be retained.
- Existing hard surface be retained

See Kompan drawing CAS-416136-Y2F0L4 for hard surface, play equipment and boundary details for Playground.

See ACD drawing BUG24699-11 and BUG24699-12 for soft and hard landscape details for Former Pool Site .

See ACD drawing BUG24775-11 and BUG24775-12 for soft and hard landscape details for Library Site.

See ACD drawing BUG24775-16 for soft and hard landscape details for Family Landscape Garden.

Full Planting Schedule

Trees

Species Name	Girth	Height	Density	Specification	No.
Acer campestre	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	1 -
Betula pendula	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	4 -
Carpinus betulus	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	3 -
Fagus sylvatica	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	2 -
Prunus padus	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	2 -
Quercus robur	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	3 -
Sorbus aucuparia	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	3 -
Tilia cordata	14-16cm	400-450cm	Counted	Standard :Clear Stem 150-175 :RB	4 -

Tree Pit Detail: Soft Landscape
Scale 1:50 @A1



The root flare of the newly planted tree shall be clearly visible at the soil surface and is not to be buried by excess soil or mulch

Stakes to be requisite length, pressure impregnated, debarked softwood 100mm square or diameter, driven into ground sufficient depth to provide full support

Root Rain Metro tree pit irrigation system, or similar

Backfill material is be be applied in layers 150mm in depth, ensuring that the tree is held upright

Once tree has been positioned the hessian and twine surrounding the roots is to be loosened. Wire cages are to be removed

Tree ties to be biodegradable hessian tree ties tied to stakes

1m diameter of decorative bark mulch to be applied to surface of tree pit, to a depth of 75mm

Backfill material to comprise of soil dug from excavated pits (if of sufficient quality) or to be backfilled with 600mm subsoil and 300mm of topsoil, in line with BS3882:2015 Specification for topsoil

Dimension of tree pit to be at least 75mm greater then the rootball. The depth of the pit shall be no deeper than the existing rootball and container depth

Base of tree pit to remain undisturbed unless there is evidence of poor drainage, soil smearing or panning in which case appropriate rectification measures will be required

Components as supplied from GreenBlue Urban or similar

Rev	Date	Details	Drawn

ACD ENVIRONMENTAL

HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane, Malmesbury, SN16 0ES
Tel: 01666 825646

Unit 7, Godalming Business Centre, Woolsack Way, Godalming, GU7 1HP
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

email:
mail@acdenv.co.uk

bugler DEVELOPMENTS

scheme: Falling Lane, Yiewsley
client: Bugler developments
drawing: Park Enhancements Landscape Plan
date: July 2025
scale: 1:250@A1
drawing no: BUG24775 15
drawn: ZZ checked: JS

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.