



EXISTING GROUND FLOOR PLAN
scale 1:100

APPROVED GROUND FLOOR PLAN
(Ref:77427/APP/2023/2946)
scale 1:100

PROPOSED GROUND FLOOR PLAN
scale 1:100

KEY:	
Existing	
Approved	
Proposed	
FIRE PROTECTION AND VENTILATION	
(S)	Smoke detector to be installed within 7.5 meters of the door to every habitable room
(HD)	Interlinked heat detector to be installed in the kitchen
(CO)	Carbon monoxide detector to be installed within 1 metre of the gas appliances
(FD30)	Fire protected doors with 30 minutes fire resistance
(ME)	Mechanical extraction @ 30ltrs/sec if over hob (60ltrs/sec if otherwise)
(UE)	Mechanical extraction @ 30ltrs/sec for utility rooms
(BT)	Mechanical extraction @ 15ltrs/sec for bathrooms, shower rooms and toilets
(W)	Mechanical extraction through wall
↑	Fire Exists
□	Fire Rated Separator

