



**DELIVERY IN 7-10 WORKING DAYS**

**1**

year  
guarantee

Select Your Product

Description

Delivery

Q&A

## Sheffield Bicycle Stands

★★★★★(17)

- Most commonly used in public spaces as well as commercial areas
- Popular with local authorities
- Surface mounted version uses 3x 12mm concrete fixing bolts (not included)
- Can be fixed to tarmac as well providing concrete pads are fitted to tarmac first
- Or set into concrete version which is 300mm taller with ragged top
- Recommended positioning approximately 800mm apart and 450mm from any wall / obstruction
- Galvanised, galvanised powder coated black or stainless steel
- 48mm round tube (3mm thick)
- Looking for these quicker? Check out our range of [Express Sheffield Bicycle Stands](#)
- Dimensions: H 750mm x D 800mm\*

\* Dimensions are above ground

**PLEASE NOTE:** Fixing anything into Tarmac is never as good as into concrete. It is important to not drill the holes too wide as in warm weather the concrete becomes pliable and fixings will naturally loosen.

### Heavy Duty 48mm round tube 3mm thick bike stands for the secure locking of bikes to each side of the Sheffield

Many organisations are now encouraging their staff to use greener forms of transportation such as bicycles to get to and from work. If your organisation uses bicycles it is essential they have somewhere secure to safely store their bicycles. Our heavy duty Sheffield bicycle stands are the ideal location for staff and visitors to store their bicycles.

These 48mm round, 3mm thick tube cycle stands are commonly used in commercial parking areas as well as public areas. Choose from surface mounted or concrete in stands, with a choice of either a galvanised, galvanised powder coated black or grade 304 stainless steel finish.

Both versions are 750mm high (above ground) and manufactured from galvanised mild steel tube, each stand is suitable for two bikes (one each side). We recommend that each Sheffield stand is placed approximately 800mm apart and 450mm from any wall or corner. These stands are ideal used in combination with a [wall-mounted cycle shelter](#) to help keep your bikes dry during inclement weather.

oike parking

oer flange (not

ed into the

ends

50mm from

finish

ffield Stands

nto Concrete.

tarmac



[View full range of  
Cycle Racks](#)

[REQUEST A CALL BACK](#)

**Need it  
QUICKER  
or for  
BULK  
DISCOUNTS**  
**0808 223 0187**

## ffield stand

m work, in order for people to

would provide a secure

choose either surface mounted

for both versions.

the storage of up to two bikes

or obstruction. These bike



[View catalogue page](#)