



1 No. double sided internally illuminated hanging sign. O/a size being 800mm x 800mm, with internal framework complete with projector arm and fixing plate fabricated from mild steel flat bar and 50mm SHS. Framework to be clad in 0.9mm folded gold hairline stainless steel panels aperture cut and backed with 10mm opal acrylic pushed through to sit proud. Faces of pushed through opal applied with 1mm thick descaled stainless steel flat cut letters and logo details, as artwork. Internally illuminated via cool white LEDs and suitable transformer.

1 Proposed Hanging Sign
1:20 @ A3

1 no. sets of halo illuminated lettering reading 'Treatz'. O/a size being 1250mm x 650mm, fabricated from 0.9mm thick gold hairline stainless steel with 80mm returns. Back trays to be fabricated from 5mm opal acrylic, halo illuminated via cool white LEDs and suitable transformers. To be fitted to via nylon spacers.

2 Proposed Illuminated Sign
1:20 @ A3

SOUTH RUISLIP

project Treatz South Ruislip
 stage Planning
 client Treatz Franchising
 drawing Signage Details
 scale 1:20 @ A3
 date Jul 2023
 dwg no 580-201