

Ref.	Address 1	Address 2	Address 3	Address 4	Species	Measurements	Description	Survey Notes	Google Maps	Site	Recommendations
T004	3	Gibson	Rd	R/G	Eucalyptus (<i>Eucalyptus sp.</i>)	Height (m): 12 Crown Radius (m): 3 DBH (cm): 35 Life Stage: Semi Mature	Located in the rear garden to the left hand side to the rear of the shed. Co-dominant stem at base area leaning over garage roof area. Main stem has a progressive lean towards the rear elevation of the building due to being suppressed by the neighbouring Oak Tree.	Rear garden	51.5616924,-0.4648019	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Timescale: 12-Mar-2024 (1 Month)
T003	3	Gibson	Rd	R/G	Prunus (<i>Prunus sp.</i>)	Height (m): 6 Crown Radius (m): 2 DBH (cm): 15 Life Stage: Semi Mature	0001 Located in the rear garden to the left hand side to the rear of the garage. Twin stemmed at ground level. Dominant stem is suppressed by adjacent Eucalyptus Tree and leaning over neighbouring garden and in contact with neighbouring building. Smaller stem is Dead. Owned by the estate.	Rear garden	51.5616586,-0.464794	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)
T017	4	Gibson	Rd	R/G	Cherry (<i>Prunus sp.</i> 'Cherry')	Height (m): 12 Crown Radius (m): 5 DBH (cm): 45 Life Stage: Mature	Located in the rear garden to the rear boundary to the right hand side. Unable to fully view due to no access - viewed from rear garden of 6. Ganoderma bracket on main stem at approximately 1m from ground level. Crown breaks at approximately 3m from ground level with tight union. Low branches over garden area and neighbouring garden. Failed hungup branches over garden area and neighbouring garden in the mid to lower Crown.	Rear garden	51.5614166,-0.463983	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Timescale: 12-Mar-2024 (1 Month)

G1	5	Gibson	Rd	R/G	Mixed species (Mixed species)	Height (m): 8 Crown Radius (m): 1.5 DBH (cm): 15	7x young to mature trees located in the rear garden to the left hand side and rear boundary area. 2x mature dominant trees are in contact with the boundary fence of 3. Both trees have historically been pollarded at a height of approximately 3m from ground level. 1x Younger tree is growing through the boundary fence of 3 and grown in to and around a metal frame. Owned by the estate. <u>Tree in fence line</u>	Rear garden	51.561732,-0.4646028	uxbridge - norq06 - gibson road estate	Fell to ground level 1x leaning Sycamore growing through boundary fence of 3 Gibson Road Timescale: 12-Mar-2024 (1 Month)
T001	5	Gibson	Rd	F/G	Cherry (Prunus sp. 'Cherry')	Height (m): 6 Crown Radius (m): 5 DBH (cm): 60 Life Stage: Mature	0007 Located in the central area of the front garden. Multiple Ganoderma brackets at the base of the main stem and buttress root. High surface buttress roots and surface lateral roots within the front lawn area. Multiple Burrs on main stem Crown breaks at approximately 2.5m from ground level with Multiple horizontal limbs. Dominant over extended horizontal limb growing towards the front elevation of 3 Gibson Road. Previously had lower limbs removed.	Front garden	51.5616666,-0.4644287	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)
T011	7	Gibson	Rd	F/G	Crab apple (Malus sylvestris)	Height (m): 4 Crown Radius (m): 2 DBH (cm): 25 Life Stage: Mature	Located in the central area of the front garden. Ganoderma bracket at ground level. Decay in main stem at approximately 0.5m from ground level. Previously failed co-dominant stem. Previously reduced to approximately 4m from ground level.	Front garden	51.5617999,-0.4641928	uxbridge - norq06 - gibson road estate	Fell to ground level and stump grind Timescale: 12-Mar-2024 (1 Month)
T008	12	Gibson	Rd	R/G	Crab apple (Malus sylvestris)	Height (m): 8 Crown Radius (m): 5 DBH (cm): 30 Life Stage: Mature	0418 Located in the central area of the front garden. Main stem has a progressive lean towards the front elevation of the building. Deadwood throughout the crown. Low over extended limbs towards the entrance path. Owned by the estate.	Front garden	51.5618937,-0.4636217	uxbridge - norq06 - gibson road estate	Remove major deadwood. Reduce over extended limbs by up to approximately 2m of the branch length. Timescale: 12-Mar-

T010	12	Gibson	Rd	S/O	Crab apple (<i>Malus sylvestris</i>)	Height (m): 8 Crown Radius (m): 4 DBH (cm): 40 Life Stage: Mature	0411 Located in the grass area to the side of the property by the junction of Nettleton Road. Decay in the main stem at ground level facing Nettleton Rd. Dominant central stem has previously failed. Upper crown of co-dominant stem has failed and hungup. Decay in low lateral limb over grass area due to a previously failed co-dominant stem.	Grass area by junction of Nettleton Road	51.5620008,-0.4633601	uxbridge - norq06 - gibson road estate	Fell to ground level and stump grind Timescale: 12-Mar-2024 (1 Month)
G7	21	Gibson	Rd	R/G	Mixed species (Mixed species)	Height (m): 12 Crown Radius (m): 3 DBH (cm): 35	Multiple young to mature trees located in the rear garden to the right hand side. 1x Ash, 1x Elderberry and 1x Elm is in conflict with the brick shed and boundary fence. 1x semi mature Elm pushed out the concrete kickboard of the boundary fence in to the adjacent footpath. The surface roots are lifted the Tarmac of the adjacent footpath. The main crown has recently been reduced. Group of Ash Trees located near the rear boundary have recently had the ivy severed.	Rear garden	51.5627045,-0.4634515	uxbridge - norq06 - gibson road estate	Fell to ground level 2x Ash Trees, 1x Elderberry and 2x Elms to the side and rear of the brick shed Timescale: 12-Mar-2024 (1 Month)
T020	22	Gibson	Rd	R/G	Hawthorn (<i>Crataegus</i> sp.)	Height (m): 8 Crown Radius (m): 4 DBH (cm): 25 Stems: 4 Life Stage: Mature	Multi stemmed heavily ivy clad tree located in the rear garden to the rear boundary. Owned by the estate. Target # - dwelling. - Within 1.5x tree height. Occupancy: Occasionally (2)	Rear garden	51.5616983,-0.4634241	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)

T013	23	Gibson	Rd	F/G	Cherry (<i>Prunus</i> <i>sp.</i> 'Cherry')	Height (m): 8 Crown Radius (m): 5 DBH (cm): 50	0024 Located in the central area of the front garden. Unidentified fungus Within cavity at ground level. Crown breaks in to multiple stems at approximately 2m from ground level either tight unions. Cavity in union of 2x stems over entrance path. Cavity in stem over grass area with poor union. Recently had lower branches removed to reduce the encroachment from the footpaths and garden area. Large dead limb in upper crown over grass area. Owned by the estate. Target # - building Target # - car park. Target # - dwelling.	Front garden	51.5620444,-0.4637489	uxbridge - norq06 - gibson road estate	Fell to ground level and stump grind Timescale: 12-Mar-2024 (1 Month)
T027	25	Gibson	Rd	F/G	Birch (<i>Betula</i> <i>sp.</i>)	Height (m): 10 Crown Radius (m): 4 DBH (cm): 30 Life Stage: Early Mature	Located in the front garden of 25/27 Gibson Rd. Surface roots within the lawn area with mower damage. Co-dominant stem at ground level with poor union. Basal and epicormic growth on main stem. Previously had lower limbs removed. BT cable runs through the crown.	Front gardens	51.5627659,-0.4626479	uxbridge - norq06 - gibson road estate	Fell co-dominant stem at ground level. Prune to clear BT cable Timescale: 12-Mar-2024 (1 Month)
G9	27	Gibson	Rd	R/G	Ash x3 (<i>Fraxinus</i> <i>sp.</i>)	Height (m): 18 Crown Radius (m): 6 DBH (cm): 45 Trees: 3 Life Stage: Mature	3x trees located along the rear boundary fence line. Dead and dying ivy on main stems up to the upper crowns. Major deadwood throughout the crowns with signs of Ash Dieback. 1x Ash nearest the neighbouring building is twin stemmed with tight union. Unable to fully view due to extent of ivy. 1x adjacent Ash Tree at the end of the group has recently been felled. Owned by the estate.	Rear garden	51.5630916,-0.4626652	uxbridge - norq06 - gibson road estate	Fell 3x Ash Trees to ground level Timescale: 12-Mar-2024 (1 Month)

T030	27	Gibson	Rd	F/G	Cherry (<i>Prunus</i> sp. 'Cherry')	Height (m): 10 Crown Radius (m): 5 DBH (cm): 65 Life Stage: Mature	0090 Located in the grass area to the right hand side of the driveway between the driveway and Campden Rd. Multiple Ganoderma brackets in Multiple locations around the base of the main stem. Crown breaks at approximately 2m from ground level in to multiple stems. Recent failure of a dominant stem over the driveway. Failure of a secondary limb from dominant limb over the driveway. Deadwood throughout the crown. Owned by the estate. Target # - building	Front garden	51.5627326,-0.4624333	uxbridge - norq06 - gibson road estate	Fell to ground level and stump grind Timescale: 12-Mar-2024 (1 Month)
T35	29	Gibson	Rd	F/G	Cherry (<i>Prunus</i> sp. 'Cherry')	Height (m): 6 Crown Radius (m): 4 DBH (cm): 45 Life Stage: Mature	0097 Located in the central area of the front garden. Ganoderma brackets around the base. Decay and hollowing between buttress root and the base area of the main stem. Hollowing sound up the main stem when tapped with a Nylon Mallet. Crown breaks at approximately 2m from ground level in to multiple stems.	Front garden	51.5626187,-0.4620433	uxbridge - norq06 - gibson road estate	Fell to ground level and stump grind Timescale: 12-Mar-2024 (1 Month)
T36	29	Gibson	Rd	F/O	Cherry (<i>Prunus</i> sp. 'Cherry')	Height (m): 6 Crown Radius (m): 6 DBH (cm): 40 Life Stage: Mature	0094 Located in the grass area between the driveway and Campden Road. Large surface buttress roots growing in to the public footpath. High surface roots within the lawn area with mower damage. Co-dominant stems at approximately 0.5m from ground level with tight unions. Over extended lateral limbs over the public footpath, grass area and driveway.	Front garden	51.5626633,-0.4622162	uxbridge - norq06 - gibson road estate	Reduction of over extended lateral limbs by up to approximately 2-3m of the branch length. Timescale: 12-Mar-2024 (1 Month)

T32	29	Gibson	Rd	S/O	Elder (<i>Sambucus nigra</i>)	Height (m): 5 Crown Radius (m): 2 DBH (cm): 25 Life Stage: Over Mature	Located in the area to the left hand side of the rear garden to the rear boundary fence line adjacent to the neighbouring driveway. Located in raised soil with a progressive lean towards the footpath. Heavily in decline.	Side of the rear garden	51.5628944,-0.4620297	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)
T37	31	Gibson	Rd	R/G	Elm (<i>Ulmus sp.</i>)	Height (m): 8 Crown Radius (m): 2 DBH (cm): 15 Life Stage: Dead	Dead Elm located in the rear garden to the rear boundary. Owned by the estate. Target # - building Target # - dwelling.	Rear garden	51.5627961,-0.4617167	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)
T39	31	Gibson	Rd	R/G	Ash (<i>Fraxinus sp.</i>)	Height (m): 10 Crown Radius (m): 5 DBH (cm): 30 Stems: 3 Life Stage: Semi Mature	Located in the rear garden to the right hand side of the garage. Heavily Ivy Clad. Appears to be multi stemmed at ground level but Unable to fully view due to the extent of the ivy. Previously been reduced back from the side elevation of the building and garage roof. In conflict with the boundary fence and side of the garage.	Side of the garage	51.5626405,-0.4617734	uxbridge - norq06 - gibson road estate	Fell to ground level Timescale: 12-Mar-2024 (1 Month)
T40	31	Gibson	Rd	R/G	Eucalyptus (<i>Eucalyptus sp.</i>)	Height (m): 18 Crown Radius (m): 10 DBH (cm): 60 Life Stage: Mature	Located in the rear garden to the right hand side. Co-dominant stem at approximately 1m from ground level. Secondary stem forks in to 2x stems at approximately 1.5m from main union and extends to the rear boundary. Both stem arch at approximately 5m from main union and partly supported by adjacent Ash Tree. Main Co-dominant stem extends over the main garden of 31. The main stem has a progressive lean towards 33. Owned by the estate.	Rear garden	51.5626812,-0.4617395	uxbridge - norq06 - gibson road estate	Crown reduction of up to approximately 2m of the branch length. Remove both limbs growing towards the rear boundary area. Must be done with T41 Timescale: 12-Mar-2024 (1 Month)

T41	33	Gibson	Rd	R/G	Ash (<i>Fraxinus</i> <i>sp.</i>)	Height (m): 12 Crown Radius (m): 4 DBH (cm): 30 Life Stage: Semi Mature	0103 Located in the rear garden in the fence line of 31. Twin stemmed at ground level. Basal stems previously been removed. Progressive lean over the garden area. Upper crown supporting limb of adjacent Eucalyptus (T40)	Rear garden	51.5627083,- 0.4616906	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Must be done with T40 Timescale: 12-Mar-2024 (1 Month)
T42	33	Gibson	Rd	F/G	Crab apple (<i>Malus</i> <i>sylvestris</i>)	Height (m): 8 Crown Radius (m): 4 DBH (cm): 35 Life Stage: Mature	0104 Located in the central area of the front garden. 3x Lower limb previously removed. Extended limb towards the front elevation of the building. Minor deadwood throughout the crown. BT cable runs through the upper crown.	Front garden	51.5625174,- 0.4617026	uxbridge - norq06 - gibson road estate	Prune to clear BT cable. Reduction of extended limb growing towards the front elevation of the building by up to approximately 2m of the branch length
T43	35	Gibson	Rd	F/G	Crab apple (<i>Malus</i> <i>sylvestris</i>)	Height (m): 8 Crown Radius (m): 5 DBH (cm): 30 Life Stage: Mature	0105 Located in the front garden 3m from footpath. Minor Strimmer damage around base area. Decay within union area of historically removed limb at approximately 1.5m from ground level. Deadwood throughout the crown. BT cables runs through the upper crown.	Front garden	51.5624814,- 0.4615724	uxbridge - norq06 - gibson road estate	Remove major deadwood. Prune to clear BT cables Timescale: 13-Mar-2024 (1 Month)

T44	35	Gibson	Rd	R/G	Ash (<i>Fraxinus</i> <i>sp.</i>)	Height (m): 10 Crown Radius (m): 3 DBH (cm): 20 Stems: 2 Life Stage: Semi Mature	Located in the rear garden adjacent to the rear boundary fence. Twin stemmed at ground level. Dominant stem forks in to 2x stems at approximately 0.5m from ground level with tight union. Rear single stem is in conflict with the boundary fence post. Ivy clad from ground level in to the upper crown. Deadwood throughout the crown showing signs of Ash Dieback. Residents rear of the rear boundary has cut off branches which overhung their garden and chucked them back in to the garden of 35 Gibson Rd. Owned by the estate. Tree in fence line.	Rear garden	51.562694,-0.4613788	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Timescale: 13-Mar-2024 (1 Month)
T45	35	Gibson	Rd	R/G	Ash (<i>Fraxinus</i> <i>sp.</i>)	Height (m): 10 Crown Radius (m): 2 DBH (cm): 15 Life Stage: Young	Located in the rear garden to the right hand side. Single stemmed to approximately 3m from ground level then forks in to 2x stems. Progressive lean towards the rear boundary due to being a by dominant Maple Tree. Owned by the estate.	Rear garden	51.5626548,-0.4613364	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Timescale: 13-Mar-2024 (1 Month)
T46	35	Gibson	Rd	R/G	Maple (<i>Acer</i> <i>sp.</i>)	Height (m): 10 Crown Radius (m): 4 DBH (cm): 30 Life Stage: Semi Mature	Located in the rear garden to the right hand side against the boundary fence line of 37. Basal stem growing over the garden of 37. Progressive lean over the rear boundary due to being suppressed by dominant Maple tree. Branches have been cut off by neighbour to the rear of the rear boundary and chucked back in to the gardens of 35 & 37.	Rear garden	51.5626689,-0.461305	uxbridge - norq06 - gibson road estate	Fell to ground level and apply eco pellets Timescale: 13-Mar-2024 (1 Month)

T093	40	Gibson	Rd	F/G	Crab apple (<i>Malus sylvestris</i>)	Height (m): 8 Crown Radius (m): 5 DBH (cm): 40 Life Stage: Mature	0204 Located in the front garden 3m from the public footpath. Crown breaks at approximately 2m from ground level with Multiple limbs. Decay within main stem below the main union with light coming through. Delamination on stem in upper crown. Previously been reduced to a height of approximately 5m from ground level with approximately 2-3m of regrowth. BT cable runs through the crown.	Front garden	51.5615607,-0.4591902	uxbridge - norq06 - gibson road estate	Crown reduction to previous points Timescale: 14-Mar-2024 (1 Month)
T88	59	Gibson	Rd	F/G	Cherry (<i>Prunus sp. 'Cherry'</i>)	Height (m): 8 Crown Radius (m): 7 DBH (cm): 68 Life Stage: Mature	0187 Located in the front garden to the right hand side. High surface and buttress root within the lawn area with mower damage. Burrs on main stem. Crown breaks at approximately 2m from ground level with Multiple stems. Over extended limbs over garden and road. Encroaching onto the BT pole. Owned by the estate.	Front garden	51.5613539,-0.4586602	uxbridge - norq06 - gibson road estate	Reduction of extended lateral limbs by up to approximately 3m of the branch length. Prune to clear BT cable and pole Timescale: 13-Mar-2024 (1 Month)