

5m	Walls: White stucco Finish on all walls unless specified; Brown clay tiles on main roof and dormer window roof Brown sandstone bands on flat roof ribbons.	Ground Floor Windows X 4 (1.6m X 1.2m): 800mm sill level; sliding mumford pattern; clear double pane glass; black uPVC; brown sandstone lintel(215mm thick) and black uPVC sill(50mm thick) Ground Floor Window X 1 (3m X 1.2m): 800mm sill level; sliding mumford pattern; clear double pane glass; black uPVC; brown Sandstone lintel(215mm thick) and black uPVC sill(50mm thick) Ground Floor Swing Doors X 2 (0.75m wide): Black aluminum fireproof door; with square fixed glass tiles; brown sandstone lintel(215mm thick) and black uPVC sill(50mm thick) First Floor Windows X 4 (1.6m X 1.2m): 800mm sill level; Sliding mumford pattern; clear double pane glass; black uPVC; brown sandstone lintel(215mm thick) and black uPVC sill(50mm thick) First Floor Fixed Triangular Glass Window (3m X 2.7m): Black aluminum frame and mullions; double pane clear toughened glass Loft Floor Windows X 3 (1.45m wide): Bottom fixed glass (850-950mm sill level) with casement window on top; clear double pane glass; black uPVC Loft Floor Dormer Windows X 2 (1.5m wide): Bottom fixed glass (850mm sill level) with casement window on top; clear double pane glass; black uPVC
----	--	--



NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETER.
2. ALL WORK TO COMPLY WITH BUILDING REGULATIONS AND CODE OF PRACTICE.

PROPOSED FRONT ELEVATION

SITE ADDRESS: 13 KEWFERRY DRIVE, NORTHWOOD, HA6 2NT	DRAWN BY: CHIRAG KODWANI, B.ARCH (COA), RTPI
DATE: 15 OCT 2024	
SCALE: 1:75 @ A3	
DRAWING NO.: 10/24-13-KDNH-05, REV-04	