

Schedule

Project	BA SIGNAGE	Issue	P1

Manufacturer: Sloan
Luminaire Ref: SloanLED (Prism)
Luminaire Type: LED Module for Channel Letter Signage
Reference: “_”
Description: Premium 24V LED module for signage and channel letter applications. 4 LEDs per module with peel-n-stick + mechanical fastening. IP66/IP68 rated.

Control Gear: Separate LED Driver
Total Load: 0.86W per module (standard output)

Colour: White

Lamp -

Manufacturer: Sloan

Lamp Type: LED Module

Wattage: 0.86W per module (standard)

No of Lamps: As required by signage area (typically 3.9 modules/meter for standard)

Voltage: 24V DC

Beam angle: Wide

Colour temp: 6500K

Lumen: 138 lm per module (standard)

Notes: LED modules suitable for outdoor signage use in channel letters. Designed for optimal brightness and uniformity with minimal energy use.

Dimensions: 61mm (L) x 14mm (W) x 11mm (D)

