



Butlers Trees LTD
182 Glebe Road
Letchworth Gdn. City
Herts
SG6 1DY
info@butlers-trees.co.uk
01438 571 520

Butlers Trees LTD

TREE CONDITION SURVEY AND

MANAGEMENT WORK RECOMMENDATIONS

SUNDAY, 28 SEPTEMBER 2025
M ARCHITECTURE PLANNING
SANTOS TIMBER
35 The Grove, Ickenham, Uxbridge UB10 8QJ



Tree Condition survey and
Management Work Recommendations

For

M Architecture Planning

Santos Timber

Report by

Luke Butler

Cert Arb L4 (ABC)/Tech Cert (ArborA)

TechArborA

Butlers Trees LTD

Letchworth Garden City

Herefordshire

Company number **12650525**

Arboricultural Tree Survey

Survey Site Address	35 The Grove, Ickenham, Uxbridge UB10 8QJ
Client	M Architecture Planning
Date of Report	28/09/2025

Contact details

Butlers Trees LTD		
182 Glebe Road Letchworth Garden City Herefordshire SG6 1DY	Mr Luke Butler	T: 0787 656 8075 E: info@butlers-trees.co.uk

Luke Butler
28/09/2025

M Architecture Planning
Page **1** of **23**

35 The Grove, Ickenham,
Uxbridge UB10 8QJ

M Architecture Planning		
Suite B 282 Woodham Ln Addlestone KT15 3NT	Mr Murat Surucu	T: 07547 213128 E: info@ma-planning.co.uk

London Borough of Hillingdon Council		
London Borough of Hillingdon High St Uxbridge UB8 1UW		T: 01895 250111 E: planning@hillingsdon.gov.uk

Issue and Revision Record

Descrip\on	Issue/Revision No.	Date	Author
Visual Tree Inspec\on	1	26th of September 2025	Luke Butler
Report	1	28 th of September 2025	Luke Butler

TABLE OF CONTENTS

1. Statement of Instruc\on	3
2. Personal Qualifica\ons and Experience	4
3. Site Details	4
4. Survey Method	4
5. Survey Limita\ons	5
6. Observa\ons	6
7. Discussion	6

8. Conclusions	7
9. Recommendations	8
10. Appendix	9
Appendix A – Tree Data	9
Appendix B – Explanatory notes	11
Appendix C – Pictures	13
Appendix D – Web Information & Bibliography	19
Appendix E – Qualifications and Memberships	21

No part of this report may be copied or reproduced by any means without prior written permission from Butlers Trees LTD. If you have received this report in error, please destroy all copies in your possession or control.

This report has been prepared for the exclusive use of the commissioning party and unless otherwise agreed in writing by Butlers Trees LTD, no other party may use, make use of or rely on the contents of this report.

No liability is accepted by Butlers Trees LTD for any use of this report, other than for the purposes for which it was originally prepared and provided.

Opinions and information provided in the report are on the basis of Butlers Trees LTD using due skill, care and diligence in the preparation of the same and no warranty is provided as to their accuracy.

Surveys are undertaken on the understanding that nothing in the final report will be omitted, amended or misrepresented by the client or any other interested party.

This report and its contents remain the property of Butlers Trees LTD until payment has been made in full.

It should be noted and it is expressly stated that no independent verification of any of the documents or information supplied to Butlers Trees LTD has been made.

1. Statement of Instruction

- 1.1. Instruction was received from Edward Frexio on the 16th of September 2025 to undertake a tree survey in accordance with *British Standard 5837:2012* in respect to an area of land at no.35 The Grove, Ickenham, Uxbridge UB10 8QJ.
- 1.2. The client's instruction allowed for the following;
 - 1.2.1. Attend site and undertake a survey and categorisation of trees there.
 - 1.2.2. Identify species of the trees present and describe the overall condition, age and safe life expectancy.
 - 1.2.3. Produce a report of the site discussing the future management of the trees and produce a Tree Constraints Plan for the Client.
- 1.3. The purpose of this report is to give a tree condition assessment that are a potential risk to person or property.

2. Personal Qualifications and Experience

- 2.1. Career details: I have been working in the Arboriculture sector since 2016 where I started at a small private company as a Ground Person. I then became a Second Climber and Team Leader the following year. In 2018 I moved to a larger company continuing my role as a Second Climber before being promoted to a Contract Manager in 2019. In 2020 I formed my own Arboricultural Company.
- 2.2. Qualifications: In matters of tree safety and risk assessment I have undertaken and completed the LANTRA Awards Professional Tree Inspection Course and integrated assessment. I gained The Level 4 Certificate in Arboriculture from the Skills and Education Group at Myerscough College in 2020. I also hold Level 3 practical qualifications in Tree Surgery from NPTC and Lantra.
- 2.3. Professional Memberships: I am a registered Technical member of the Arboricultural Association, member number TE7969.
- 2.4. Continued Professional Development: I am constantly maintaining and trying to improve my professional knowledge by being an active member in the industry. I do this by attending a high number of seminars and annual conferences, both practical and theoretical.

3. Site Details

- 3.1 The site is situated on the south side of Ickenham in West London, just north of the A40.
- 3.2 The property has two roads adjacent to it. The Grove on its west side and The Chase on its south side.
- 3.3 The north and east are flanked by other residential properties.
- 3.4 The trees are located at the rear of the property and in the neighbouring property.

- 3.5 There are no public access rights through the property.
- 3.6 The site does not contain, reside in or have any Tree Preservation Orders.
- 3.7 The site does lie within a conservation area, reference: Ickenham Village CA-4
- 3.8 The approval of London Borough of Hillingdon Council will be needed before carrying out any work on the trees that are subject to a Tree preservation Order or in a Conservation Area.
- 3.9 Guidance can be found [here](#).

4. Survey Method

- 4.1 A site visit was completed on the 26th of September 2025 by the report's author, Luke Butler.
- 4.2 Three trees were pointed out by the client to which a report needed to be undertaken.
- 4.3 The trees identified have been assigned a reference number, T1, T2 and T3, which are referenced throughout the report.
- 4.4 A ground based visual assessment of the health and condition of the trees has been carried out with the use of an acoustic sounding hammer and a probe.
- 4.5 All tree inspections were carried out in accordance with current best practice (Visual Tree Assessment) to give a systematic, consistent and transparent evaluation method.
- 4.6 No specialist decay diagnostic equipment such as decay micro drilling or tomography was used during the inspection.
- 4.7 Assessment of the health of the trees detailed in this report were arrived at from visual indicators such as crown dieback, previous wounds, cracked or flaking bark etc.
- 4.8 Stem diameter measurements were taken with a girth tape.
- 4.9 Height measurements were taken with a clinometer.

5. Survey Limitations

- 5.1 This survey details the condition of the trees when the assessment was undertaken. Inevitably their condition will change over time. Accordingly, the client is advised that they should have trees in their ownership or for which they are responsible routinely inspected by a competent person so their condition can be regularly assessed.
- 5.2 Other than the enquiries made on the British Geological Society's website, no assessment of the site's soil or its composition was undertaken.
- 5.3 No assessment was made of whether the trees detailed in the survey have or have the potential to cause indirect damage through subsidence or heave to adjacent buildings.
- 5.4 No specialist decay diagnostic equipment was used during the survey.

- 5.5 The survey was undertaken from ground level. No aerial inspection of the trees surveyed was undertaken. If such an inspection has been identified as being required, this will have been detailed as a Preliminary Recommendation.
- 5.6 No soil or tree samples were taken for this report.
- 5.7 The Tree Preservation officer from the Local Planning Authority should be consulted before any work is carried out on site.
- 5.8 Before any work is carried out on site, the trees should be inspected for any activity of any protected species and a written record kept. Under the Wildlife and Countryside Act 1981 it is an offence to destroy or disturb nesting birds, if nesting birds are discovered or suspected no works can proceed and the Local Planning Authority (LPA) and Local Wildlife Trust must be notified for advice as to how to proceed.

6. Observations

- 6.1 Within the proposed inspection area, three significant trees have been identified. (Significant trees are trees with a diameter of more than 75 millimetres at 1.5 metres from ground level).
- 6.2 T1 is located in the neighbouring property of no.33 The Grove. It is a species of Thuja, *Thuja spp.*
The crown appears sparse, more so towards the top, but this is normal for the species.
There are small brown patches of foliage in the crown, but again this is normal. It has been slightly reduced on the south side where it overhangs the garden of no.35 The Grove a few years ago as the pruning cuts have darkened in colour.
There is a co-dominant stem on the south side of the crown at approx. 10m from ground level, growing to approx. 8m tall.
- 6.3 T2 is a Common Yew, *Taxus baccata*, and is in the south east corner of the rear garden of no.35 The Grove.
The base of the tree is growing on a small raised earth bank.
It has been trimmed back on occasion, likely with hedge cutters.
The crown hangs over the footpath with a clearance just under 2m.
- 6.4 T3 is a Silver Birch, *Betula pendula*, and is growing on the street to the south of the property, along the northside of The Chase.
It is quite tall and narrow for its species, which could mean it is a Fasciata variant.
There is a large secondary branch on the south side of west side of the crown. There is a climbing vine, possibly honey suckle, growing over from the adjacent property of no.1 The Chase, up to a height of approx. 9m into the crown.
A branch has snapped off or been removed on the south side/road side of the crown, low down on the stem. It is still lightly coloured so has happened recently. The pruning wound is not clean cut which suggests a snap out.

7. Discussion

- 7.1 All trees appear to be in good health with no serious defects.
- 7.2 The proposal of a 'summer house' style building at the back of the rear garden has been suggested. Due to the size of the root system from T1, which covers approx. 2/3rds of the east side of the rear garden, with T2 making up the final 1/3rd, the options for foundations are limited.
- 7.3 The standard choice for foundations is strip foundations. This is where a trench is dug, either mechanically or by hand, then filled with concrete. Due to the presence of roots, the foundations for this project will have to be hand dug so root damage is limited. This is outlined in BS:5837 section 7.2. Where possible roots over 25mm should be left in place unless otherwise signed off by the Project Arboculturist. Exposed roots should be covered to prevent prolonged exposure to the elements, mostly from drying out or sudden temperature drops. If roots over 25mm need to be severed, the Project Arboculturist should be consulted.
- 7.4 Another option for the foundations would be piling. Traditionally this is carried out with steel and concrete, but timber can also be used in smaller builds and this is probably the most suitable foundation type for this build. A main consideration regarding timber piles is that they should be protected from rotting above groundwater level. Timber will last for a long time below the groundwater level. For timber to rot, two elements are needed: water and oxygen. Below the groundwater level, dissolved oxygen is lacking even though there is ample water. An example is Venice, which has had timber pilings since its beginning. Timber that is to be used above the water table can be protected from decay and insects by numerous forms of wood preservation using pressure treatment.
- Depending on the technique used for piling, compaction of the roots may take place if heavy machinery is to be employed. To mitigate this, ground protection will need to be incorporated, though this can be made clear in an Impact Assessment once the building design and position has been confirmed.
- 7.5 The last option is raas foundations. Raas foundations are relatively shallow slabs of reinforced concrete. They are often uniformly thick and tend to cover the entire area of a building's footprint. The structural loads acting on the foundation are spread, as evenly as possible, through the concrete into the ground below. The foundation itself can therefore be thought of as floating like a raas would on water. If the area beneath the foundation hasn't been prepared correctly, or if the foundation has not been specified properly, then settlement is a risk and the slab might even start to sink. Reinforcement is provided steel rods set within the concrete. This helps deal with the downward and upward bending forces preventing the slab from cracking. The steelwork is built in situ and needs to be inspected by the structural engineer prior to the concrete being poured. Areas where structural loadings are most intense, such as around columns or load bearing walls, will usually require stronger reinforcement.

7.6 T2 may need to be removed for construction to take place, so replanning within the property will need to be undertaken due to the development taking place in a conservation area.

8. Conclusions

- 8.1. No tree work needs to be undertaken at this time.
- 8.2. There are a number of options for the foundations as outlined above. Once the final design and placement of the building is agreed, then the foundation design can be finalised as well.
- 8.3. If T2 is to be removed, replanning will need to take place. This would ideally be the same or similar species or at minimum a British native tree to help maintain the natural food chain.

9. Recommendations

- 9.1. Due to the large root areas and initial placement of the 'summer house', piling of the foundations would be the preferred option to reduce the amount of digging through the root area and thus the amount of stress on the trees.
- 9.2. All works should be carried out as per the recommendations in *BS3998 Tree work – 2011*.

10. Appendix

Appendix A – Tree Data

Tree No.	Species	Age	Stem		Height (m)	Crown (m)			Root Protection		Physiological Condition	Structural condition		Comments and recommendations	Category, Life Expectancy, Work completion date
			No.	Diameter (mm)			Spread	Clearance	Radius (m)	Area (m ²)					
T1	Japanese Thuja <i>Thuja standishii</i>	M	3	495 790 315	20	N E S W	6 6 4 5	1.5	11.8	437	G	C S B	G G G	Crown appears sparse but normal for species. Slight reduction on south west side of crown back to boundary around 3 years ago. Small yew at the base. Small raise on north side. Co dominant stem at 10m on larger stem. Small patches of brown throughout crown. Normal for species.	A2 40+
T2	Common Yew <i>Taxus baccata</i>	M	1	300	5	N E S W	3 3 3 4	n/a	3.6	41	G	C S B	G G G	South east corner On small raised earth bank Stem measurement taken at approx. 1m from ground level due to scaffold branches and stem divergence.	B1 20+
T3	Silver Birch <i>Betula pendula</i>	M	1	250	12.5	N E S W	3 2.5 3.5 4	2	3	28	G	C S B	G G G	Street tree. Tall and narrow for species. Large secondary branch on south side. Climber such as honey suckle growing up east side of tree into mid crown at around 9m. Branch snapped or removed on south side/road side.	B3 20+

Luke Butler
28/09/2025

M Architecture Planning
Page **9** of **20**

35 The Grove, Ickenham,
Uxbridge UB10 8QJ

Appendix B – Explanatory notes

Tree No. - Sequential reference number given to each tree or tree group identified in the survey.

- **T** – Individual Tree.
- **G** – Group of trees (a group of similar trees of similar condition).
- **R** – Row of trees.
- **H** – Hedgerow.

Species - Species of tree shown as its common name with its scientific name in italics below.

Age - The point in its life span at which the tree is estimated to be

- **Y** - Young – First 10 years of growth.
- **SM** - Semi Mature - Less than 1/5 of life completed.
- **M** - Mature – 2/5 – 5/5 of life completed.
- **OM** - Over Mature - more than 5/5 of life completed and declining.
- **V** - Veteran – Veteran trees have no precise definition but are trees considered to be of biological aesthetic or ecological value because of their age.

No. of stems - Number of stems measured at 1.5 metres above ground level.

Stem diameter - Measured at 1.5 metres above ground level in accordance with the conventions detailed in British Standard 5837:2012 and recorded in millimetres.

Crown Spread - The spread of the tree's crown as measured at the points of the compass and expressed in metres.

Crown clearance - The distance from crown level to the base of the crown expressed in metres.

Height - Estimated height of tree expressed in metres.

Physiological Condition - The physiological condition of the tree/s. -

- **G** - Good.
- **F** - Fair.
- **P** - Poor.
- **D** - Dead.

Structural Condition - The structural condition of the tree/s -

- **G** - Good.
- **F** - Fair.
- **P** - Poor.
- **VP** – Very poor.

Recommendations and comments - Recommendations for actions required and comments on physical attributes of the tree/s.

This following section is coloured with a traffic light system to visually show which is most urgent, red being the most urgent and requiring immediate action, yellow requiring action in the short term and green requiring no immediate action.

Category - A category ascribed to the tree based on the definitions outlined in BS5837:2012.

Category (A): Trees whose retention is most desirable and are of high quality and value. These trees are considered to be in such a condition as to be able to make a lasting contribution and may comprise:

1. Trees which are particularly good examples of their species especially rare or unusual, or essential components of groups or of formal or semi-formal arboricultural features.
2. Trees, or groups of trees which provide a definite screening or softening effect to the locality in relation to views into or out of the site, or those of particular visual importance.
3. Trees or groups of significant conservation, historical, commemorative or other value (e.g., Veteran or wood-pasture trees).

Category (B): Trees whose retention is considered desirable and are of moderate quality and value. These trees are considered to be in such a condition as to make a significant contribution and may comprise:

1. Trees that might be included in the high category but because of their numbers or slightly impaired condition, are downgraded in favour of the best individuals;
2. Trees present in numbers such that they form distinct landscape features and attract a higher collective rating than they would as individuals. Individually these trees are not essential components of formal or semi-formal arboricultural features, or trees situated mainly internally to the site and have little visual impact beyond the site;
3. Trees with clearly identifiable conservation or other cultural benefits.

Category (C): Trees that could be retained and are considered to be of low quality and value. These trees are in an adequate condition to remain until new planting could be established or are young trees with a stem diameter below 150 mm and may comprise:

1. Trees not qualifying in higher categories;
2. Trees present in groups or woodlands, but without this conferring on them significantly greater landscape value and or trees offering low or only temporary screening benefit;
3. Trees with very limited conservation or other cultural benefits.

Category (U): Trees that are considered to have no significant landscape value, but it is not presumed that there is any overriding need to remove them unless stated otherwise in the description and recommendations. Trees within this category are:

1. Trees that have a serious irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other category U trees;
2. Trees that are dead or are showing signs of significant, immediate or irreversible overall decline; Trees infected with pathogens of significance to the health and or/safety of other trees nearby, or very low-quality trees suppressing adjacent trees of better quality

Life expectancy - an estimate based on the tree's condition as to how long the tree is likely to be able to be retained and expressed in years (<10, 10+, 20+, 40+).


Work Completion date – The date by which work that has been recommended should be completed by.

Appendix C – Pictures


Site Plan – Circles are not to scale and shouldn't be used as such.



TPO and Conservation Area Map



Tree Constraints Map



T1 – From no.35 and no.33 The Grove

Luke Butler
28/09/2025

M Architecture Planning
Page 17 of 23

35 The Grove, Ickenham,
Uxbridge UB10 8QJ



Base of T1



T2



T3



Appendix D – Web Information & Bibliography

TPO Guidance –

<https://www.gov.uk/guidance/tree-preservation-orders-and-trees-in-conservation-areas>

Health and Safety Executive - http://www.hse.gov.uk/foi/internalops/sims/ag_food/010705.htm

Arboricultural Association - <https://www.trees.org.uk/>

British Geological Survey - <https://mapapps.bgs.ac.uk/geologyofbritain/home.html>

UK Soil Observatory - <http://mapapps2.bgs.ac.uk/ukso/home.html>

TPO and Conservation Map -

Ivy control - <https://www.rhs.org.uk/weeds/ivy-on-trees-ground-cover-weed>
<https://www.trees.org.uk/Help-Advice/Public/Should-Ivy-be-removed-from-trees>

British Standards 3998 (2010) *Tree Work - Recommendations UK*; British Standards Institution

British Standards 5837 (2012) *Trees in relation to design, demolition and construction. Recommendations*; British Standards Institution

Lonsdale, D (1999) *Principle of Tree Hazard Assessment and Management* Edinburgh; Forestry Commission

Maheek, C (2007) *Field Guide for Visual Tree Assessment* Germany; Karlsruhe Research Centre

Shigo, A.L (1991) *Modern Arboriculture* USA; Shigo and Trees, Association

Sterry, P (2007) *Collins Complete British Trees* London; Collins

Strouts, R.G (2000) *Diagnosis of ill-health in trees* Edinburgh; Forestry Commission

Weber, K & Maheek, C (2003) *Manual of wood decay* UK; Arboricultural Association

Schwartz, Engels and Maheek (2000) *Fungal Strategies of Wood Decay in Trees*

Christopher Luley (2005) *Wood decay fungi of living urban trees*

Lynne Boddy (2021) *Fungi and Trees, Their complex relationship*

Humphries and Wright (2021) *Fungi on Trees, A photographic reference*

Countryside and Rights of Way Act 2000.

Conservation of Habitats and Species Regulations 2017.

Health and Safety at Work Act 1974.

Management of Health and Safety at Work Regulations 1999.

The Town & Country Planning Act 1990, The Town and Country Planning (Trees)(England) Regulations 2012, The Planning (Listed Buildings & Conservation Areas) Act 1990.

Wildlife and Countryside Act 1981.

Appendix E – Qualifications and Memberships

2020 - SEG Awards ABC Level 4 in Arboriculture

2019 – Lantra awards for Professional Tree Inspection

Practical Arboriculture Qualifications (NPTC) Level 3

Technical Member of the Arboricultural Association – Member number – TE7969.